

**Call 05 Construction necessary to Construct a Shop at the Materials Lab, known as State Project Nos. BWO-9718-25(001) & LWO-9023-25(003) / 502350304 & 305 in Hinds County.**

Q1. Drawing P402, sheet 98, shows a detail of the sprinkler riser for this project. No backflow preventer is shown in this detail. The City of Jackson is currently requiring backflow prevention for sprinkler systems. Please clarify whether or not we are to figure on installing one?

A1. No, the backflow preventer for the sprinkler system was installed on the previous project.

Q2. In reference to Specification Section 07 56 23 - Fully Reinforced Liquid Roof System, where is this product to be applied? It does not show up on the plans.

A2. Fully Reinforced Liquid Roof System goes on exterior concrete roof deck at Loading Dock. Apply prior to installation of Architectural Screen Wall Louver and Mechanical Equipment shown on Wall Section 1, Working Number A414, Sheet Number 70.

Q3. Spec section 10 21 16: Shower and Dressing Compartments: Reference is made to both corian and HDPE (solid plastic). The specification lists Bobrick Washroom Equipment as the basis of design. Bobrick manufactures neither of these materials. The description leans heavily towards solid plastic and the specs direct you to the finish schedule Division 9 for the color selection. However, the shower compartments are not listed on the finish schedule. Please clarify what material is required. Spec section 10 21 14: Toilet Compartments: The specs reference Bobrick Washroom Equipment as basis of design and then specify their Sierra Series as the required product. However, the finish schedule calls for Scranton as the manufacturer and they make only the HDPE. Which manufacturer and material is required?

A3. The showers are ceramic tile as shown in Drawings, not plastic shower compartments. Section 10 21 16 is included and referenced for the shower partition (pilaster divider) and the shower receptor located in each shower as shown in the Drawings. Benches & Dressing Compartment Pilasters shall be HDPE (Solid Plastic). Section 10 21 14 specifies the Bobrick Sierra Series as the basis for design. Use available Sierra Series colors to choose from instead of Scranton given in Section 09 05 15.

Q4. In reference to Addendum No. 1, Plan Sheet C5.0, Notes 2 and 3, how will work covered under Notes 2 and 3 be paid for?

A4. The Contractor will need to coordinate all work on City right-of-way with the City which is related to notes 2 and 3. This will be a direct cost for City forces to perform this work. The City will provide a quote for this work and MDOT will pay for this by Supplemental Agreement. All other costs related to performing work related to Notes 2 and 3 will be absorbed into the price bid for Pay Item No. 907-242-PP001 Water and Sewer Improvements, Per Plans.