$S \ E \ C \ T \ I \ O \ N \quad 9 \ 0 \ 5 \ -- \ P \ R \ O \ P \ O \ S \ A \ L \quad (CONTINUED)$

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for <u>**five percent (5%) of total bid**</u> and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDU			6/2014	ADDENDUM NO.	DATE		
Rev	Descr ised NTB #5083,	DATED	4, (Must ad Respe DATI BY BY TITL ADD CITY PHON FAX	Sig E RESS , STATE, ZIP NE	ssued prior to o	opening of b	
(To be filled i	in if a corporation)			AIL			
	· ·			c			
		tered under the Law he executives are as		e of		and	the names,
	President			Ad	ddress		
	Secretary			Ad	ddress		
	Treasurer			Ad	ddress		
The following	g is my (our) itemiz	zed proposal.		MD 1006 58(000) / 00	05070204	Dontotoo	County(ica)
Revised 09/21/	2005			MP-1336-58(009) / 30	15210301	PONIOLOC	County(ies)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 5083

CODE: (SP)

DATE: 7/16/2014

SUBJECT: Contract Time

PROJECT: MP-1336-58(009) / 305278301 – Pontotoc County

The calendar date for completion of work to be performed by the Contractor for this project shall be **November 6, 2014** which date or extended date as provided in Subsection 907-108.06 shall be the end of contract time. It is anticipated that the Notice of Award will be issued no later than **July 22, 2014** and the effective date of the Notice to Proceed / Beginning of Contract Time will be simultaneous with the execution of the contract.

The available productive days for this project are <u>59</u>.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 5084

CODE: (SP)

DATE: 07/16/2014

SUBJECT: Scope of Work

PROJECT: MP-1336-58(009) / 305278301 – Pontotoc County

The contract documents do not include an official set of construction plans, but may by reference, include some Standard Drawing or Special Design Drawings. All other references to plans in the contract documents and Standard Specifications for Road and Bridge Construction are to be disregarded.

Work on the project shall be in accordance with the attached typical sections and consist of the following:

HIGHWAY 336 <u>MILL AND OVERLAY FROM</u> <u>COLEMAN ROAD TO HIGHWAY 15 IN PONTOTOC COUNTY</u>

- 1. The Contractor shall erect and maintain construction signing, and provide all signs and traffic handling devices in accordance with the Traffic Control Plan. The cost is to be included in the price bid for pay item No. 618-A001, Maintenance of Traffic. All traffic control devices on this project should comply with Part VI of the MUTCD (Latest Edition). Fluorescent orange sheeting shall be used on all construction and traffic control signs except for those designated in plans to be black legend and border on white background.
- Remove and Undercut Failed Areas as required. Undercut depth of no more than three feet (3') below finished grade or as directed by the Engineer. Backfill with Crushed Stone to 12 inches below finished grade. Place 12 inches of 9.5-mm, MT, Asphalt to finished grade. OMITTED SECTION = STA. 172+00 TO 203+00.
- 1½ inches and variable of Cold Milling from Sta. 0+00 (B.O.P.) to Sta. 172+00 (Omitted Section) Sta. 203+00 to Sta. 471+38 (E.O.P.). Extra Depth Milling will be required in certain failed pavement areas. Note: Multiple passes may be required to achieve normal crown to 2%±. Electronic grade/slope correction equipment shall be required on milling machine.
- 4. Approximately 3,200 tons of Wedging and approximately 6,000 tons of ³/₄ inch and variable pre-leveling required after milling.
- 5. 1¹/₂-inch Overlay with 9.5-mm, MT, Asphalt from Sta. 0+00 (B.O.P.) to Sta. 172+00 (Omitted Section) Sta. 203+00 to Sta. 471+38 (E.O.P.).
- 6. Class 3, Group C Granular Material required on shoulders as directed by the Engineer.

7. 6-inch equivalent Thermoplastic Traffic Stripe Required.

General Note:

Existing County Roads to be paved to end of tapers or as directed by the Engineer. County Roads and driveway pads to be cold milled as directed by the Engineer.

Prior to placing any bituminous pavement and cold milling, the existing shoulders are to be bladed to a minimum of one foot (1') beyond the edge of the existing pavement to remove vegetation and excess shoulder material. Cost of this work shall be included in other items bid.

The boundary of all failed areas shall be saw cut prior to removal of asphalt. Cost of this work shall be included in other items bid.

Temporary striping shall conform to finished stripe specifications for alignment, reflectivity, straightness, and neatness. Temporary stripe shall be placed daily as needed for safe movement of traffic. The Temporary Stripe Quantity reflects placing Temporary Traffic Stripe throughout the project limits twice and on Pre-Leveled areas. All permanent pavement markings are to be hot thermoplastic.







- 5 -

Mill and Overlay of approximately 9 miles of SR 336 from Coleman Road to SR 15, known as State Project No. MP-1336-58(009) / 305278301, in Pontotoc County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price] Roadway Items
0010 Change	202-B005 ed 07/16/2014		100		Removal of Asphalt Pavement, All Depths
0020	202-B076		640	Linear Feet	Removal of Traffic Stripe
0030 Change	203-G003 ed 07/16/2014	(E)	100	Cubic Yard	Excess Excavation, FM, AH
0040 Change	406-A001 ed 07/16/2014		114,706	Square Yard	Cold Milling of Bituminous Pavement, All Depths
0042 Added	605-AA003 07/16/2014	(S)	500	Square Yard	Geotextile for Subsurface Drainage, Type III
0050	619-A1002		32	Mile	Temporary Traffic Stripe, Continuous White
0060	619-A2002		52	Mile	Temporary Traffic Stripe, Continuous Yellow
0070	619-A4006		4	Mile	Temporary Traffic Stripe, Skip Yellow
0080	619-A5002		4,200	Linear Feet	Temporary Traffic Stripe, Detail, Paint
0090	619-A6001		1,340	Linear Feet	Temporary Traffic Stripe, Legend
0100 Change	619-A6002 ed 07/16/2014		39	Square Feet	Temporary Traffic Stripe, Legend
0110	627-K001		7	Each	Red-Clear Reflective High Performance Raised Markers
0120	627-L001		1,100	Each	Two-Way Yellow Reflective High Performance Raised Markers
0130 Change	907-304-A008 ed 07/16/2014	(GY)) 1,800	Cubic Yard	Granular Material, LVM, Class 3, Group C
0140 Change	907-407-A001 ed 07/16/2014	(A2)	19,000	Gallon	Asphalt for Tack Coat
0150	907-618-A001		1	Lump Sum	Maintenance of Traffic
0160	907-618-B001		1	Square Feet	Additional Construction Signs [\$10.00]
0170	907-626-C004		17	Mile	6" Thermoplastic Edge Stripe, Continuous White
0180	907-626-D003		2	Mile	6" Thermoplastic Traffic Stripe, Skip Yellow
0190	907-626-E004		26	Mile	6" Thermoplastic Traffic Stripe, Continuous Yellow
0200	907-626-G004		1,963	Linear Feet	Thermoplastic Detail Stripe, White
0210	907-626-G005		2,236	Linear Feet	Thermoplastic Detail Stripe, Yellow
0220	907-626-H004		1,340	Linear Feet	Thermoplastic Legend, White
0230	907-626-H005		40	Square Feet	Thermoplastic Legend, White
				ALTERNAT	TE GROUP AA NUMBER 1

Section 905 Proposal (Sheet 2 - 2)

Line No.	Item Code	Adj Q Code	Juantity	Units	Description [Fixed Unit Price]		
0240 Change	907-304-H002 ed 07/16/2014	(GY)	100	Cubic Yard	3/4" and Down Crushed Stone Base, LVM		
				ALTERNAT	ALTERNATE GROUP AA NUMBER 2		
0250 Change	907-304-H003 ed 07/16/2014	(GY)	100	Cubic Yard	Size 610 Crushed Stone Base, LVM		
				ALTERNAT	TE GROUP AA NUMBER 3		
0260 Change	907-304-H004 ed 07/16/2014	(GY)	100	Cubic Yard	Size 825B Crushed Stone Base, LVM		
				ALTERNATE GROUP BB NUMBER 1			
0270 Change	907-403-A010 ed 07/16/2014	(BA1)	19,025	Ton	Hot Mix Asphalt, MT, 9.5-mm mixture		
				ALTERNA	FE GROUP BB NUMBER 2		
0280 Change	907-403-M006 ed 07/16/2014	(BA1)	19,025	Ton	Warm Mix Asphalt, MT, 9.5-mm mixture		