

YAZOO (82)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.	Lehman-Roberts Company	
Overlay approximately 4 miles of US 51 from Yazoo/Madison County Line to End of Maintenance, known as State Project Nos. MP-3051-00(098) / 305272301 & 302 in Yazoo and Holmes Counties.					\$1,325,207.00	\$1,411,309.20	\$1,429,076.55	
Ref#	SM Item	Item Description	Item Qty	Units		1	2	
0010	202-B005	Removal of Asphalt Pavement, All Depths	1,147.000	SY		7.00	36.45	
0020	202-B030	Removal of Concrete Pavement, All Depths	803.000	SY		134.90	40.44	
0030	203-G003	Excess Excavation, FM, AH	268.000	CY		14.00	4.48	
0040	406-A001	Cold Milling of Bituminous Pavement, All Depths	13,946.000	SY		4.50	3.90	
0050	619-A1002	Temporary Traffic Stripe, Continuous White	15.000	MI		400.00	400.00	
0060	619-A2002	Temporary Traffic Stripe, Continuous Yellow	7.000	MI		400.00	400.00	
0070	619-A4006	Temporary Traffic Stripe, Skip Yellow	5.000	MI		400.00	400.00	
0080	619-A5001	Temporary Traffic Stripe, Detail	1,500.000	LF		0.15	0.15	
0090	627-J001	Two-Way Clear Reflective High Performance Raised Markers	350.000	EA		3.75	3.75	
0100	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	320.000	EA		3.75	3.75	
0110	907-304-B002	Granular Material, Class 5, Group D	500.000	TON		35.00	28.58	
0120	907-407-A001	Asphalt for Tack Coat	6,600.000	GAL		2.75	3.25	
0130	907-412-A002	Pre-Grinding	2.000	SF		3.25	3.25	
0140	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	9,360.000	LF		3.00	3.00	
0150	907-618-A001	Maintenance of Traffic	1.000	LS		112,000.00	64,706.04	
0160	907-618-B001	Additional Construction Signs	2.000	SF		10.00	10.00	
0170	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	8.000	MI		2,100.00	2,100.00	
0180	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	3.000	MI		850.00	850.00	
0190	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	4.000	MI		2,100.00	2,100.00	
0200	907-626-G004	Thermoplastic Detail Stripe, White	9,000.000	LF		0.80	0.80	
0210	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,850.000	LF		0.80	0.80	
0220	907-304-F002	Size 610 Crushed Stone Base	500.000	TON		52.00	36.20	
0230	907-304-F004	Size 825B Crushed Stone Base	500.000	TON				
0240	907-304-F003	3/4" and Down Crushed Stone Base	500.000	TON				
0250	907-403-A015	Hot Mix Asphalt, ST, 9.5-mm mixture	6,965.000	TON			94.40	
0260	907-403-M001	Warm Mix Asphalt, ST, 9.5-mm mixture	6,965.000	TON		86.50		

YAZOO (82)					MISSISSIPPI DEPARTMENT OF TRANSPORTATION	APAC - Mississippi, Inc.	Lehman-Roberts Company	
Overlay approximately 4 miles of US 51 from Yazoo/Madison County Line to End of Maintenance, known as State Project Nos. MP-3051-00(098) / 305272301 & 302 in Yazoo and Holmes Counties.					\$1,325,207.00	\$1,411,309.20	\$1,429,076.55	
Ref#	SM Item	Item Description	Item Qty	Units		1	2	
0270	907-403-A012	Hot Mix Asphalt, ST, 19-mm mixture	300.000	TON			111.31	
0280	907-403-M004	Warm Mix Asphalt, ST, 19-mm mixture	300.000	TON		71.50		
0290	907-403-B007	Hot Mix Asphalt, ST, 12.5-mm mixture, Leveling	4,800.000	TON			85.77	
0300	907-403-N002	Warm Mix Asphalt, ST, 12.5-mm mixture, Leveling	4,800.000	TON		73.50		