

Call 05 Mill & Overlay approximately 6 miles of US 49 North & Southbound Lanes from Mendenhall to D'Lo, known as Federal Aid Project No. STP-0008-02(103) / 106883301 in Simpson County.

Q1. **1.** Will there be any paving under guardrail pads? **2.** Are all the concrete islands at the SR 540 intersection and East St. intersection to be edge milled? **3.** With the current ride specifications, how is the contractor to account for the existing rumble strip on the edge of pavement?

A1. **1)** Yes, it will be placed if there is no asphalt currently under the existing guardrail pad. **2)** Yes, they are to be milled to tie to the curb. It is shown as a small hatched area on sheets 4 and 14 of the plans. **3)** The new rumble strip will be placed in the same location as the existing rumble strip, so it will not affect the ride specifications.

Q2. Can a list be provided for the anticipated areas for the leveling course?

A2. Leveling will be as directed by the Engineer.