

Call 12 Bridge Replacement on SR 501 over the Leaf River, known as Federal Aid Project No. BR-0333-00(013)/102362301 in Scott County.

Q1. Is it the intention of engineer to install full structure thickness of asphalt specified for roadway (5.5") on the guardrail areas also or just a 2" 12.5mm course?

A1. Guardrail pads should match the top two lifts of the roadway structure.