

**Call 01 Mill & Overlay approximately 12 miles of US 72 from Benton County Line to Alcorn County Line, known as Federal Aid Project No. NH-0007-01(082) / 106945301 in Tippah County.**

Q1. Typical sheets TS1-TS3 show the same scenario for full depth base repairs, where the removal of asphalt shall be absorbed into the Cold Milling item. A General Note also states that any areas that cannot be removed with the milling machine must be saw cut prior to removal. Sheet EQ-2 only shows one full depth repair area. Are there any other full depth repair areas that will have to be repaired? It is difficult to absorb costs into the cold milling when there is no direction as to the amount of saw cutting and removal work that may be required.

A1. The full depth repair shown on EQ-2 is the one (1) repair to be considered when bidding.