

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Tanner Construction Company, Inc. | Key, LLC |
|--|-----------|---|-------------|-------|--|-----------------------------------|-----------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$14,456,148.55 | \$15,573,029.14 | \$15,757,175.61 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0010 | 201-A001 | Clearing and Grubbing | 1.000 | LS | 450,000.00 | 854,000.00 | 200,000.00 |
| 0020 | 202-A001 | Removal of Obstructions | 1.000 | LS | 32,000.00 | 150,000.00 | 335,000.00 |
| 0030 | 202-B005 | Removal of Asphalt Pavement, All Depths | 31,661.000 | SY | 3.25 | 4.86 | 2.50 |
| 0040 | 202-B019 | Removal of Concrete Headwall | 11.000 | EA | 1,200.00 | 200.00 | 500.00 |
| 0050 | 202-B038 | Removal of Curb, All Types | 119.000 | LF | 3.00 | 6.35 | 20.00 |
| 0060 | 202-B064 | Removal of Pipe, 8" And Above | 414.000 | LF | 8.00 | 9.00 | 20.00 |
| 0070 | 202-B076 | Removal of Traffic Stripe | 9,200.000 | LF | 1.00 | 1.00 | 1.00 |
| 0080 | 202-B080 | Removal of Box Culvert | 37.000 | LF | 25.00 | 21.75 | 185.00 |
| 0090 | 202-B102 | Removal of Guard Rail | 2,662.000 | LF | 3.00 | 3.00 | 3.00 |
| 0100 | 203-A003 | Unclassified Excavation, FM, AH | 57,035.000 | CY | 2.50 | 3.60 | 2.60 |
| 0110 | 203-EX017 | Borrow Excavation, AH, FME, Class B9 | 195,422.000 | CY | 5.25 | 7.00 | 5.33 |
| 0120 | 203-G003 | Excess Excavation, FM, AH | 33,102.000 | CY | 2.50 | 4.55 | 2.40 |
| 0130 | 206-A001 | Structure Excavation | 722.000 | CY | 6.50 | 9.25 | 4.00 |
| 0140 | 209-A004 | Geotextile Stabilization, Type V, Non-Woven | 34,632.000 | SY | 2.20 | 1.25 | 1.00 |
| 0150 | 213-C001 | Superphosphate | 35.000 | TON | 600.00 | 600.00 | 650.00 |
| 0160 | 217-A001 | Ditch Liner | 100.000 | SY | 2.00 | 3.50 | 1.30 |
| 0170 | 219-A001 | Watering | 5.000 | KGAL | 20.00 | 20.00 | 20.00 |
| 0180 | 220-A001 | Insect Pest Control | 35.000 | ACRE | 30.00 | 30.00 | 30.00 |
| 0190 | 221-A001 | Portland Cement Concrete Paved Ditch | 29.000 | CY | 650.00 | 425.00 | 550.00 |
| 0200 | 223-A001 | Mowing | 70.000 | ACRE | 50.00 | 50.00 | 50.00 |
| 0210 | 234-A001 | Temporary Silt Fence | 2,900.000 | LF | 3.00 | 3.00 | 2.80 |
| 0220 | 235-A001 | Temporary Erosion Checks | 230.000 | BALE | 7.00 | 7.00 | 5.00 |
| 0230 | 236-A004 | Silt Basin, Type D | 19.000 | EA | 1,500.00 | 1,480.00 | 860.00 |
| 0240 | 239-A001 | Temporary Slope Drains | 875.000 | LF | 7.00 | 7.00 | 4.00 |
| 0250 | 406-A001 | Cold Milling of Bituminous Pavement, All Depths | 1,867.000 | SY | 5.00 | 7.90 | 2.90 |
| 0260 | 423-A001 | Rumble Strips, Ground In | 5.000 | MI | 700.00 | 400.00 | 400.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Tanner Construction Company, Inc. | Key, LLC |
|--|-----------|--|-----------|-------|--|-----------------------------------|-----------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$14,456,148.55 | \$15,573,029.14 | \$15,757,175.61 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0270 | 501-E001 | Expansion Joints, Without Dowels | 443.000 | LF | 7.00 | 12.00 | 16.00 |
| 0280 | 502-A001 | Reinforced Cement Concrete Bridge End Pavement | 1,021.000 | SY | 180.00 | 166.00 | 120.00 |
| 0290 | 602-A001 | Reinforcing Steel | 178.000 | LBS | 1.20 | 5.75 | 1.10 |
| 0300 | 603-CA003 | 24" Reinforced Concrete Pipe, Class III | 988.000 | LF | 37.83 | 50.00 | 50.00 |
| 0310 | 603-CA004 | 30" Reinforced Concrete Pipe, Class III | 120.000 | LF | 52.53 | 60.00 | 60.00 |
| 0320 | 603-CA009 | 60" Reinforced Concrete Pipe, Class III | 100.000 | LF | 180.03 | 145.00 | 160.00 |
| 0330 | 603-CA015 | 24" Reinforced Concrete Pipe, Class IV | 152.000 | LF | 46.75 | 55.00 | 60.00 |
| 0340 | 603-CB002 | 24" Reinforced Concrete End Section | 19.000 | EA | 710.60 | 820.00 | 900.00 |
| 0350 | 603-CB003 | 30" Reinforced Concrete End Section | 2.000 | EA | 783.70 | 860.00 | 950.00 |
| 0360 | 603-CB008 | 60" Reinforced Concrete End Section | 2.000 | EA | 2,876.40 | 2,250.00 | 3,000.00 |
| 0370 | 603-CE004 | 44" x 27" Concrete Arch Pipe, Class A III | 40.000 | LF | 104.89 | 95.00 | 98.00 |
| 0380 | 603-CF004 | 44" x 27" Concrete Arch Pipe End Section | 2.000 | EA | 1,635.40 | 1,440.00 | 1,500.00 |
| 0420 | 606-B001 | Guard Rail, Class A, Type 1 | 1,700.000 | LF | 18.50 | 18.50 | 18.50 |
| 0430 | 606-D012 | Guard Rail, Bridge End Section, Type I | 16.000 | EA | 1,850.00 | 1,850.00 | 1,850.00 |
| 0440 | 606-E002 | Guard Rail, Terminal End Section, Flared | 16.000 | EA | 2,250.00 | 2,250.00 | 2,250.00 |
| 0450 | 609-D002 | Combination Concrete Curb and Gutter Type 2 | 220.000 | LF | 31.15 | 36.00 | 31.15 |
| 0460 | 615-A018 | Concrete Bridge End Barrier, 33.5" | 160.000 | LF | 43.75 | 44.65 | 43.75 |
| 0470 | 619-A1002 | Temporary Traffic Stripe, Continuous White | 6.000 | MI | 800.00 | 800.00 | 800.00 |
| 0480 | 619-A2001 | Temporary Traffic Stripe, Continuous Yellow | 3,248.000 | LF | 0.15 | 0.15 | 0.15 |
| 0490 | 619-A4006 | Temporary Traffic Stripe, Skip Yellow | 3.000 | MI | 800.00 | 800.00 | 800.00 |
| 0500 | 619-A5001 | Temporary Traffic Stripe, Detail | 3,047.000 | LF | 0.25 | 0.25 | 0.25 |
| 0510 | 619-A6001 | Temporary Traffic Stripe, Legend | 527.000 | LF | 1.00 | 1.00 | 1.00 |
| 0520 | 619-C7001 | Two-Way Yellow Reflective High Performance Raised Marker | 266.000 | EA | 6.00 | 6.00 | 6.00 |
| 0530 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 149.000 | SF | 7.25 | 9.90 | 5.50 |
| 0540 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 360.000 | SF | 7.25 | 9.90 | 5.50 |
| 0550 | 619-G4001 | Barricades, Type III, Single Faced | 192.000 | LF | 12.50 | 16.00 | 14.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Tanner Construction Company, Inc. | Key, LLC |
|--|--------------|---|------------|-------|--|-----------------------------------|-----------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$14,456,148.55 | \$15,573,029.14 | \$15,757,175.61 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0560 | 619-G4005 | Barricades, Type III, Double Faced | 24.000 | LF | 15.00 | 16.00 | 14.00 |
| 0570 | 619-G5001 | Free Standing Plastic Drums | 152.000 | EA | 43.00 | 49.50 | 35.00 |
| 0580 | 619-G7001 | Warning Lights, Type "B" | 2.000 | EA | 185.00 | 205.00 | 285.00 |
| 0590 | 620-A001 | Mobilization | 1.000 | LS | 827,250.00 | 1,500,000.00 | 925,000.00 |
| 0600 | 621-A001 | Field Laboratory | 1.000 | EA | 12,000.00 | 10,000.00 | 80,000.00 |
| 0610 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 257.000 | EA | 6.00 | 6.00 | 6.00 |
| 0620 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 20.000 | SF | 19.00 | 19.00 | 19.00 |
| 0630 | 630-A002 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 103.000 | SF | 20.00 | 20.00 | 20.00 |
| 0640 | 630-C003 | Steel U-Section Posts, 3.0 lb/ft | 182.000 | LF | 8.50 | 8.50 | 8.50 |
| 0650 | 630-E004 | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar | 24.000 | LBS | 2.50 | 2.50 | 2.50 |
| 0660 | 630-F001 | Delineators, Guard Rail, White | 88.000 | EA | 18.00 | 18.00 | 18.00 |
| 0670 | 630-G002 | Type 3 Object Markers, OM-3R or OM-3L, Post Mounted | 16.000 | EA | 75.00 | 75.00 | 75.00 |
| 0671 | 630-K003 | Welded & Seamless Steel Pipe Posts, 4" | 31.000 | LF | 45.00 | 45.00 | 45.00 |
| 0680 | 815-A006 | Loose Riprap, Size 100 | 1,943.000 | TON | 42.00 | 30.00 | 32.00 |
| 0690 | 815-A009 | Loose Riprap, Size 300 | 3,920.000 | TON | 42.00 | 30.00 | 36.00 |
| 0700 | 815-E001 | Geotextile under Riprap | 2,110.000 | SY | 2.25 | 1.45 | 1.00 |
| 0710 | 907-216-A001 | Solid Sodding | 248.000 | SY | 4.00 | 4.00 | 3.00 |
| 0720 | 907-225-A001 | Grassing | 70.000 | ACRE | 600.00 | 600.00 | 1,050.00 |
| 0730 | 907-225-B001 | Agricultural Limestone | 208.000 | TON | 50.00 | 50.00 | 25.00 |
| 0740 | 907-225-C001 | Mulch, Vegetative Mulch | 139.000 | TON | 175.00 | 175.00 | 100.00 |
| 0750 | 907-226-A001 | Temporary Grassing | 70.000 | ACRE | 600.00 | 600.00 | 500.00 |
| 0760 | 907-234-C002 | Super Silt Fence | 13,735.000 | LF | 7.00 | 7.00 | 6.50 |
| 0770 | 907-234-F001 | Turbidity Barrier | 600.000 | LF | 16.00 | 16.00 | 17.00 |
| 0780 | 907-237-A003 | Wattles, 20" | 570.000 | LF | 4.00 | 4.00 | 3.75 |
| 0790 | 907-245-A001 | Triangular Silt Dike | 570.000 | LF | 7.00 | 7.00 | 6.50 |
| 0800 | 907-246-A001 | Sandbags | 570.000 | LF | 3.50 | 3.50 | 7.50 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Tanner Construction Company, Inc. | Key, LLC |
|--|---------------|--|-------------|-------|--|-----------------------------------|-----------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$14,456,148.55 | \$15,573,029.14 | \$15,757,175.61 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0810 | 907-249-A001 | Riprap for Erosion Control | 336.000 | TON | 50.00 | 32.50 | 60.00 |
| 0820 | 907-304-A011 | Granular Material, LVM, Class 9, Group A | 107,815.000 | CY | 4.25 | 7.50 | 3.00 |
| 0830 | 907-304-B009 | Granular Material, Class 3, Group D | 7,715.000 | TON | 27.10 | 25.40 | 28.00 |
| 0840 | 907-307-C003 | 6" Soil-Lime-Water Mixing, Class C | 20,885.000 | SY | 1.50 | 0.80 | 1.50 |
| 0850 | 907-307-D001 | Lime | 192.000 | TON | 225.00 | 125.00 | 225.00 |
| 0860 | 907-307-S001 | Bituminous Curing Seal | 3,538.000 | GAL | 4.50 | 3.00 | 4.50 |
| 0870 | 907-403-A022 | 9.5-mm, MT, Asphalt Pavement | 3,629.000 | TON | 97.91 | 97.71 | 93.50 |
| 0880 | 907-403-A023 | 12.5-mm, MT, Asphalt Pavement | 4,025.000 | TON | 91.10 | 90.92 | 87.00 |
| 0890 | 907-403-A024 | 19-mm, MT, Asphalt Pavement | 4,037.000 | TON | 77.49 | 77.33 | 74.00 |
| 0900 | 907-407-A001 | Asphalt for Tack Coat | 3,622.000 | GAL | 3.14 | 3.14 | 3.00 |
| 0910 | 907-413-E001 | Sawing and Sealing Transverse Joints in Asphalt Pavement | 375.000 | LF | 10.00 | 8.00 | 13.00 |
| 0920 | 907-601-B003 | Class "B" Structural Concrete, Minor Structures | 8.000 | CY | 2,000.00 | 975.00 | 1,250.00 |
| 0930 | 907-603-ALT01 | 18" Type A Alternate Pipe | 472.000 | LF | 24.00 | 32.00 | 32.00 |
| 0940 | 907-603-ALT02 | 24" Type A Alternate Pipe | 328.000 | LF | 32.85 | 39.00 | 42.00 |
| 0970 | 907-617-A001 | Right-of-Way Marker | 66.000 | EA | 250.00 | 300.00 | 170.00 |
| 0980 | 907-618-A001 | Maintenance of Traffic | 1.000 | LS | 25,000.00 | 25,000.00 | 20,000.00 |
| 0990 | 907-626-C004 | 6" Thermoplastic Edge Stripe, Continuous White | 5.000 | MI | 2,400.00 | 2,400.00 | 2,400.00 |
| 1000 | 907-626-D003 | 6" Thermoplastic Traffic Stripe, Skip Yellow | 3.000 | MI | 1,000.00 | 1,000.00 | 1,000.00 |
| 1010 | 907-626-E004 | 6" Thermoplastic Traffic Stripe, Continuous Yellow | 1.000 | MI | 2,400.00 | 2,400.00 | 2,400.00 |
| 1020 | 907-626-G004 | Thermoplastic Detail Stripe, White | 741.000 | LF | 2.00 | 2.00 | 2.00 |
| 1030 | 907-626-H004 | Thermoplastic Legend, White | 186.000 | LF | 4.00 | 4.00 | 4.00 |
| 1040 | 907-631-B001 | Flowable Fill, Non-Excavatable | 11.000 | CY | 200.00 | 320.00 | 650.00 |
| 1050 | 907-699-A002 | Roadway Construction Stakes | 1.000 | LS | 160,000.00 | 185,000.00 | 165,000.00 |
| 1060 | 907-815-F001 | Sediment Control Stone | 400.000 | TON | 60.00 | 30.00 | 32.00 |
| 1070 | 907-906001 | Trainees | 720.000 | HRS | 5.00 | 5.00 | 5.00 |
| 1080 | 907-304-F002 | Size 610 Crushed Stone Base | 13,812.000 | TON | | 28.40 | 25.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Tanner Construction Company, Inc. | Key, LLC |
|--|--------------|---|-------------|-------|--|-----------------------------------|-----------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$14,456,148.55 | \$15,573,029.14 | \$15,757,175.61 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 1090 | 907-304-F003 | 3/4" and Down Crushed Stone Base | 13,812.000 | TON | 31.15 | | |
| 1100 | 907-304-F004 | Size 825B Crushed Stone Base | 13,812.000 | TON | | | |
| 1110 | 907-308-A001 | Portland Cement | 128.000 | TON | 175.00 | 170.00 | 175.00 |
| 1120 | 907-308-B001 | Soil-Cement-Water Mixing, Optional Mixers, Base | 20,885.000 | SY | 1.50 | 1.85 | 1.50 |
| 1130 | 907-308-S001 | Bituminous Curing Seal | 3,538.000 | GAL | 4.50 | 4.00 | 4.50 |
| 1140 | 907-311-A003 | Processing Lime and Fly Ash Treated Course, 6" Thick | 20,885.000 | SY | | | |
| 1150 | 907-311-B001 | Lime | 96.000 | TON | | | |
| 1160 | 907-311-C001 | Fly Ash, Class C | 431.000 | TON | | | |
| 1170 | 907-311-S001 | Bituminous Curing Seal | 3,538.000 | GAL | | | |
| 1180 | 907-626-J003 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White | 5,258.000 | LF | | | |
| 1190 | 907-626-K003 | 6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow | 1,240.000 | LF | | | |
| 1200 | 907-626-L001 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow | 2,006.000 | LF | | | |
| 1210 | 628-J002 | 6" High Performance Cold Plastic Traffic Stripe, Continuous White | 5,258.000 | LF | 6.00 | 6.00 | 6.00 |
| 1220 | 628-L002 | 6" High Performance Cold Plastic Traffic Stripe, Skip Yellow | 1,240.000 | LF | 5.00 | 5.00 | 5.00 |
| 1230 | 628-M002 | 6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow | 2,006.000 | LF | 6.00 | 6.00 | 6.00 |
| 1240 | 501-K001 | Transverse Grooving | 10,865.000 | SY | 2.00 | 2.00 | 2.00 |
| 1250 | 803-B002 | Conventional Static Pile Load Test | 4.000 | EA | 5,000.00 | 5,000.00 | 5,000.00 |
| 1260 | 803-D006 | HP 14 x 117 Steel Piling | 14,115.000 | LF | 73.30 | 69.00 | 82.50 |
| 1270 | 803-D007 | HP 14 x 89 Steel Piling | 4,080.000 | LF | 60.00 | 56.00 | 63.50 |
| 1280 | 803-D009 | HP 16 x 183 Steel Piling | 1,700.000 | LF | 124.60 | 112.00 | 168.25 |
| 1290 | 803-D010 | HP 18 x 181 Steel Piling | 2,180.000 | LF | 123.50 | 112.00 | 168.75 |
| 1300 | 803-I001 | PDA Test Pile | 25.000 | EA | 14,350.00 | 11,000.00 | 9,500.00 |
| 1310 | 803-J001 | Pile Restrike | 4.000 | EA | 700.00 | 1,600.00 | 2,250.00 |
| 1320 | 805-A001 | Reinforcement | 996,072.000 | LBS | 0.83 | 0.85 | 1.00 |
| 1330 | 813-A002 | Concrete Railing, 32" | 4,890.000 | LF | 47.25 | 44.65 | 43.75 |
| 1340 | 815-A009 | Loose Riprap, Size 300 | 3,898.000 | TON | 42.00 | 30.00 | 38.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Tanner Construction Company, Inc. | Key, LLC |
|--|--------------|--|------------|-------|--|-----------------------------------|-----------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$14,456,148.55 | \$15,573,029.14 | \$15,757,175.61 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 1350 | 815-E001 | Geotextile under Riprap | 5,594.000 | SY | 2.25 | 1.30 | 1.00 |
| 1360 | 907-803-P004 | 36" Steel Pipe Piling, Wall Thickness 0.750" | 1,760.000 | LF | 258.00 | 178.00 | 450.00 |
| 1370 | 907-804-A001 | Bridge Concrete, Class AA | 4,982.000 | CY | 546.00 | 520.00 | 655.00 |
| 1380 | 907-804-C012 | 135' Prestressed Concrete Beam, Type BT-72 | 674.000 | LF | 205.40 | 160.00 | 250.00 |
| 1390 | 907-804-C016 | 40' Prestressed Concrete Beam, Type I+2 | 10,852.000 | LF | 79.00 | 65.00 | 95.00 |
| 1400 | 907-804-C030 | 80' Prestressed Concrete Beam, Type III | 957.000 | LF | 126.40 | 100.00 | 125.00 |
| 1410 | 907-804-C150 | 110' Prestressed Concrete Beam, Type IV | 659.000 | LF | 166.30 | 162.00 | 205.00 |
| 1420 | 907-804-C171 | 100' Prestressed Concrete Beam, Type IV | 1,197.000 | LF | 156.45 | 132.00 | 205.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | T. L. Wallace Construction, Inc. | L & A Contracting Company | Dement Construction Company, LLC |
|--|-----------|---|-------------|-------|----------------------------------|---------------------------|----------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$15,852,935.80 | \$15,999,402.50 | \$16,226,091.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0010 | 201-A001 | Clearing and Grubbing | 1.000 | LS | 600,000.00 | 250,000.00 | 267,000.00 |
| 0020 | 202-A001 | Removal of Obstructions | 1.000 | LS | 363,000.00 | 400,000.00 | 175,000.00 |
| 0030 | 202-B005 | Removal of Asphalt Pavement, All Depths | 31,661.000 | SY | 2.45 | 4.90 | 3.50 |
| 0040 | 202-B019 | Removal of Concrete Headwall | 11.000 | EA | 553.00 | 525.00 | 125.00 |
| 0050 | 202-B038 | Removal of Curb, All Types | 119.000 | LF | 22.10 | 21.00 | 2.00 |
| 0060 | 202-B064 | Removal of Pipe, 8" And Above | 414.000 | LF | 22.10 | 21.00 | 10.00 |
| 0070 | 202-B076 | Removal of Traffic Stripe | 9,200.000 | LF | 1.05 | 1.01 | 1.00 |
| 0080 | 202-B080 | Removal of Box Culvert | 37.000 | LF | 200.00 | 194.25 | 70.00 |
| 0090 | 202-B102 | Removal of Guard Rail | 2,662.000 | LF | 3.15 | 3.00 | 1.85 |
| 0100 | 203-A003 | Unclassified Excavation, FM, AH | 57,035.000 | CY | 2.85 | 2.73 | 3.50 |
| 0110 | 203-EX017 | Borrow Excavation, AH, FME, Class B9 | 195,422.000 | CY | 5.90 | 5.60 | 6.00 |
| 0120 | 203-G003 | Excess Excavation, FM, AH | 33,102.000 | CY | 2.65 | 2.52 | 3.60 |
| 0130 | 206-A001 | Structure Excavation | 722.000 | CY | 4.40 | 4.20 | 4.00 |
| 0140 | 209-A004 | Geotextile Stabilization, Type V, Non-Woven | 34,632.000 | SY | 1.10 | 1.05 | 1.50 |
| 0150 | 213-C001 | Superphosphate | 35.000 | TON | 718.00 | 682.50 | 600.00 |
| 0160 | 217-A001 | Ditch Liner | 100.000 | SY | 1.45 | 1.37 | 2.00 |
| 0170 | 219-A001 | Watering | 5.000 | KGAL | 20.00 | 20.00 | 20.00 |
| 0180 | 220-A001 | Insect Pest Control | 35.000 | ACRE | 30.00 | 30.00 | 30.00 |
| 0190 | 221-A001 | Portland Cement Concrete Paved Ditch | 29.000 | CY | 1,210.00 | 682.50 | 600.00 |
| 0200 | 223-A001 | Mowing | 70.000 | ACRE | 50.00 | 50.00 | 50.00 |
| 0210 | 234-A001 | Temporary Silt Fence | 2,900.000 | LF | 3.10 | 10.30 | 3.00 |
| 0220 | 235-A001 | Temporary Erosion Checks | 230.000 | BALE | 5.55 | 5.25 | 7.00 |
| 0230 | 236-A004 | Silt Basin, Type D | 19.000 | EA | 951.00 | 903.00 | 850.00 |
| 0240 | 239-A001 | Temporary Slope Drains | 875.000 | LF | 4.40 | 4.20 | 7.00 |
| 0250 | 406-A001 | Cold Milling of Bituminous Pavement, All Depths | 1,867.000 | SY | 3.05 | 7.93 | 7.55 |
| 0260 | 423-A001 | Rumble Strips, Ground In | 5.000 | MI | 510.00 | 420.00 | 400.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | T. L. Wallace Construction, Inc. | L & A Contracting Company | Dement Construction Company, LLC |
|--|-----------|--|-----------|-------|----------------------------------|---------------------------|----------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$15,852,935.80 | \$15,999,402.50 | \$16,226,091.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0270 | 501-E001 | Expansion Joints, Without Dowels | 443.000 | LF | 21.05 | 15.75 | 12.50 |
| 0280 | 502-A001 | Reinforced Cement Concrete Bridge End Pavement | 1,021.000 | SY | 170.00 | 168.00 | 150.00 |
| 0290 | 602-A001 | Reinforcing Steel | 178.000 | LBS | 1.45 | 3.68 | 2.00 |
| 0300 | 603-CA003 | 24" Reinforced Concrete Pipe, Class III | 988.000 | LF | 55.25 | 52.50 | 39.00 |
| 0310 | 603-CA004 | 30" Reinforced Concrete Pipe, Class III | 120.000 | LF | 66.30 | 63.00 | 51.00 |
| 0320 | 603-CA009 | 60" Reinforced Concrete Pipe, Class III | 100.000 | LF | 177.00 | 168.00 | 148.00 |
| 0330 | 603-CA015 | 24" Reinforced Concrete Pipe, Class IV | 152.000 | LF | 66.30 | 63.00 | 46.00 |
| 0340 | 603-CB002 | 24" Reinforced Concrete End Section | 19.000 | EA | 995.00 | 945.00 | 600.00 |
| 0350 | 603-CB003 | 30" Reinforced Concrete End Section | 2.000 | EA | 1,050.00 | 997.50 | 700.00 |
| 0360 | 603-CB008 | 60" Reinforced Concrete End Section | 2.000 | EA | 3,320.00 | 3,150.00 | 2,300.00 |
| 0370 | 603-CE004 | 44" x 27" Concrete Arch Pipe, Class A III | 40.000 | LF | 108.00 | 102.90 | 90.00 |
| 0380 | 603-CF004 | 44" x 27" Concrete Arch Pipe End Section | 2.000 | EA | 1,660.00 | 1,575.00 | 1,400.00 |
| 0420 | 606-B001 | Guard Rail, Class A, Type 1 | 1,700.000 | LF | 19.45 | 18.60 | 18.30 |
| 0430 | 606-D012 | Guard Rail, Bridge End Section, Type 1 | 16.000 | EA | 1,950.00 | 1,858.50 | 2,173.00 |
| 0440 | 606-E002 | Guard Rail, Terminal End Section, Flared | 16.000 | EA | 2,370.00 | 2,260.65 | 1,990.00 |
| 0450 | 609-D002 | Combination Concrete Curb and Gutter Type 2 | 220.000 | LF | 32.80 | 36.49 | 20.00 |
| 0460 | 615-A018 | Concrete Bridge End Barrier, 33.5" | 160.000 | LF | 50.45 | 47.76 | 77.46 |
| 0470 | 619-A1002 | Temporary Traffic Stripe, Continuous White | 6.000 | MI | 842.00 | 803.83 | 800.00 |
| 0480 | 619-A2001 | Temporary Traffic Stripe, Continuous Yellow | 3,248.000 | LF | 0.15 | 0.15 | 0.15 |
| 0490 | 619-A4006 | Temporary Traffic Stripe, Skip Yellow | 3.000 | MI | 842.00 | 803.83 | 800.00 |
| 0500 | 619-A5001 | Temporary Traffic Stripe, Detail | 3,047.000 | LF | 0.25 | 0.25 | 0.25 |
| 0510 | 619-A6001 | Temporary Traffic Stripe, Legend | 527.000 | LF | 1.05 | 1.01 | 1.00 |
| 0520 | 619-C7001 | Two-Way Yellow Reflective High Performance Raised Marker | 266.000 | EA | 6.30 | 6.03 | 6.00 |
| 0530 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 149.000 | SF | 7.65 | 5.25 | 7.25 |
| 0540 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 360.000 | SF | 7.65 | 5.25 | 7.25 |
| 0550 | 619-G4001 | Barricades, Type III, Single Faced | 192.000 | LF | 13.15 | 12.60 | 12.50 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | T. L. Wallace Construction, Inc. | L & A Contracting Company | Dement Construction Company, LLC |
|--|--------------|---|------------|-------|----------------------------------|---------------------------|----------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$15,852,935.80 | \$15,999,402.50 | \$16,226,091.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0560 | 619-G4005 | Barricades, Type III, Double Faced | 24.000 | LF | 15.80 | 15.75 | 15.00 |
| 0570 | 619-G5001 | Free Standing Plastic Drums | 152.000 | EA | 45.25 | 46.20 | 43.00 |
| 0580 | 619-G7001 | Warning Lights, Type "B" | 2.000 | EA | 195.00 | 446.25 | 185.00 |
| 0590 | 620-A001 | Mobilization | 1.000 | LS | 1,200,000.00 | 1,400,000.00 | 1,600,000.00 |
| 0600 | 621-A001 | Field Laboratory | 1.000 | EA | 18,000.00 | 52,500.00 | 100,000.00 |
| 0610 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 257.000 | EA | 6.30 | 6.03 | 6.00 |
| 0620 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 20.000 | SF | 20.00 | 19.10 | 19.00 |
| 0630 | 630-A002 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 103.000 | SF | 21.05 | 20.11 | 20.00 |
| 0640 | 630-C003 | Steel U-Section Posts, 3.0 lb/ft | 182.000 | LF | 8.95 | 8.56 | 8.50 |
| 0650 | 630-E004 | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar | 24.000 | LBS | 2.65 | 2.52 | 2.50 |
| 0660 | 630-F001 | Delineators, Guard Rail, White | 88.000 | EA | 18.95 | 18.08 | 18.00 |
| 0670 | 630-G002 | Type 3 Object Markers, OM-3R or OM-3L, Post Mounted | 16.000 | EA | 78.95 | 75.36 | 65.00 |
| 0671 | 630-K003 | Welded & Seamless Steel Pipe Posts, 4" | 31.000 | LF | 47.35 | 45.21 | 45.00 |
| 0680 | 815-A006 | Loose Riprap, Size 100 | 1,943.000 | TON | 35.35 | 33.60 | 35.00 |
| 0690 | 815-A009 | Loose Riprap, Size 300 | 3,920.000 | TON | 39.80 | 37.80 | 35.00 |
| 0700 | 815-E001 | Geotextile under Riprap | 2,110.000 | SY | 1.10 | 1.84 | 2.00 |
| 0710 | 907-216-A001 | Solid Sodding | 248.000 | SY | 3.30 | 3.15 | 4.00 |
| 0720 | 907-225-A001 | Grassing | 70.000 | ACRE | 1,160.00 | 1,102.50 | 600.00 |
| 0730 | 907-225-B001 | Agricultural Limestone | 208.000 | TON | 27.65 | 26.25 | 50.00 |
| 0740 | 907-225-C001 | Mulch, Vegetative Mulch | 139.000 | TON | 111.00 | 105.00 | 175.00 |
| 0750 | 907-226-A001 | Temporary Grassing | 70.000 | ACRE | 553.00 | 525.00 | 600.00 |
| 0760 | 907-234-C002 | Super Silt Fence | 13,735.000 | LF | 7.20 | 8.69 | 7.00 |
| 0770 | 907-234-F001 | Turbidity Barrier | 600.000 | LF | 10.25 | 17.85 | 16.00 |
| 0780 | 907-237-A003 | Wattles, 20" | 570.000 | LF | 4.15 | 3.94 | 4.00 |
| 0790 | 907-245-A001 | Triangular Silt Dike | 570.000 | LF | 7.20 | 6.83 | 7.00 |
| 0800 | 907-246-A001 | Sandbags | 570.000 | LF | 8.30 | 7.88 | 3.50 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | T. L. Wallace Construction, Inc. | L & A Contracting Company | Dement Construction Company, LLC |
|--|---------------|--|-------------|-------|----------------------------------|---------------------------|----------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$15,852,935.80 | \$15,999,402.50 | \$16,226,091.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0810 | 907-249-A001 | Riprap for Erosion Control | 336.000 | TON | 66.30 | 63.00 | 31.00 |
| 0820 | 907-304-A011 | Granular Material, LVM, Class 9, Group A | 107,815.000 | CY | 3.30 | 3.15 | 3.90 |
| 0830 | 907-304-B009 | Granular Material, Class 3, Group D | 7,715.000 | TON | 30.95 | 29.40 | 26.00 |
| 0840 | 907-307-C003 | 6" Soil-Lime-Water Mixing, Class C | 20,885.000 | SY | 1.60 | 1.51 | 1.50 |
| 0850 | 907-307-D001 | Lime | 192.000 | TON | 237.00 | 226.08 | 225.00 |
| 0860 | 907-307-S001 | Bituminous Curing Seal | 3,538.000 | GAL | 4.75 | 4.52 | 4.50 |
| 0870 | 907-403-A022 | 9.5-mm, MT, Asphalt Pavement | 3,629.000 | TON | 103.00 | 98.18 | 93.50 |
| 0880 | 907-403-A023 | 12.5-mm, MT, Asphalt Pavement | 4,025.000 | TON | 95.70 | 91.35 | 87.00 |
| 0890 | 907-403-A024 | 19-mm, MT, Asphalt Pavement | 4,037.000 | TON | 81.40 | 77.70 | 74.00 |
| 0900 | 907-407-A001 | Asphalt for Tack Coat | 3,622.000 | GAL | 3.30 | 3.15 | 3.00 |
| 0910 | 907-413-E001 | Sawing and Sealing Transverse Joints in Asphalt Pavement | 375.000 | LF | 13.70 | 13.65 | 13.00 |
| 0920 | 907-601-B003 | Class "B" Structural Concrete, Minor Structures | 8.000 | CY | 1,320.00 | 1,050.00 | 875.00 |
| 0930 | 907-603-ALT01 | 18" Type A Alternate Pipe | 472.000 | LF | 35.35 | 33.60 | 23.00 |
| 0940 | 907-603-ALT02 | 24" Type A Alternate Pipe | 328.000 | LF | 46.40 | 44.10 | 33.00 |
| 0970 | 907-617-A001 | Right-of-Way Marker | 66.000 | EA | 184.00 | 178.50 | 250.00 |
| 0980 | 907-618-A001 | Maintenance of Traffic | 1.000 | LS | 5,680.00 | 81,000.00 | 100,000.00 |
| 0990 | 907-626-C004 | 6" Thermoplastic Edge Stripe, Continuous White | 5.000 | MI | 2,530.00 | 2,411.50 | 2,400.00 |
| 1000 | 907-626-D003 | 6" Thermoplastic Traffic Stripe, Skip Yellow | 3.000 | MI | 1,050.00 | 1,005.00 | 1,000.00 |
| 1010 | 907-626-E004 | 6" Thermoplastic Traffic Stripe, Continuous Yellow | 1.000 | MI | 2,530.00 | 2,411.50 | 2,400.00 |
| 1020 | 907-626-G004 | Thermoplastic Detail Stripe, White | 741.000 | LF | 2.10 | 2.01 | 2.00 |
| 1030 | 907-626-H004 | Thermoplastic Legend, White | 186.000 | LF | 4.20 | 4.02 | 4.00 |
| 1040 | 907-631-B001 | Flowable Fill, Non-Excavatable | 11.000 | CY | 179.00 | 250.00 | 250.00 |
| 1050 | 907-699-A002 | Roadway Construction Stakes | 1.000 | LS | 199,000.00 | 350,000.00 | 250,000.00 |
| 1060 | 907-815-F001 | Sediment Control Stone | 400.000 | TON | 35.35 | 33.60 | 40.00 |
| 1070 | 907-906001 | Trainees | 720.000 | HRS | 5.00 | 5.00 | 5.00 |
| 1080 | 907-304-F002 | Size 610 Crushed Stone Base | 13,812.000 | TON | 27.65 | 26.25 | |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | T. L. Wallace Construction, Inc. | L & A Contracting Company | Dement Construction Company, LLC |
|--|--------------|---|-------------|-------|----------------------------------|---------------------------|----------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$15,852,935.80 | \$15,999,402.50 | \$16,226,091.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 1090 | 907-304-F003 | 3/4" and Down Crushed Stone Base | 13,812.000 | TON | | | 31.00 |
| 1100 | 907-304-F004 | Size 825B Crushed Stone Base | 13,812.000 | TON | | | |
| 1110 | 907-308-A001 | Portland Cement | 128.000 | TON | 184.00 | 176.00 | 175.00 |
| 1120 | 907-308-B001 | Soil-Cement-Water Mixing, Optional Mixers, Base | 20,885.000 | SY | 1.60 | 1.51 | 1.50 |
| 1130 | 907-308-S001 | Bituminous Curing Seal | 3,538.000 | GAL | 4.75 | 4.52 | 4.50 |
| 1140 | 907-311-A003 | Processing Lime and Fly Ash Treated Course, 6" Thick | 20,885.000 | SY | | | |
| 1150 | 907-311-B001 | Lime | 96.000 | TON | | | |
| 1160 | 907-311-C001 | Fly Ash, Class C | 431.000 | TON | | | |
| 1170 | 907-311-S001 | Bituminous Curing Seal | 3,538.000 | GAL | | | |
| 1180 | 907-626-J003 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White | 5,258.000 | LF | | | |
| 1190 | 907-626-K003 | 6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow | 1,240.000 | LF | | | |
| 1200 | 907-626-L001 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow | 2,006.000 | LF | | | |
| 1210 | 628-J002 | 6" High Performance Cold Plastic Traffic Stripe, Continuous White | 5,258.000 | LF | 6.30 | 6.03 | 6.00 |
| 1220 | 628-L002 | 6" High Performance Cold Plastic Traffic Stripe, Skip Yellow | 1,240.000 | LF | 5.25 | 5.02 | 5.00 |
| 1230 | 628-M002 | 6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow | 2,006.000 | LF | 6.30 | 6.03 | 6.00 |
| 1240 | 501-K001 | Transverse Grooving | 10,865.000 | SY | 2.10 | 2.10 | 2.00 |
| 1250 | 803-B002 | Conventional Static Pile Load Test | 4.000 | EA | 5,000.00 | 5,000.00 | 5,000.00 |
| 1260 | 803-D006 | HP 14 x 117 Steel Piling | 14,115.000 | LF | 76.95 | 68.40 | 54.00 |
| 1270 | 803-D007 | HP 14 x 89 Steel Piling | 4,080.000 | LF | 63.15 | 57.80 | 42.00 |
| 1280 | 803-D009 | HP 16 x 183 Steel Piling | 1,700.000 | LF | 122.00 | 131.35 | 112.00 |
| 1290 | 803-D010 | HP 18 x 181 Steel Piling | 2,180.000 | LF | 128.00 | 128.60 | 111.00 |
| 1300 | 803-I001 | PDA Test Pile | 25.000 | EA | 11,000.00 | 11,168.00 | 2,000.00 |
| 1310 | 803-J001 | Pile Restrike | 4.000 | EA | 823.00 | 3,234.00 | 1,500.00 |
| 1320 | 805-A001 | Reinforcement | 996,072.000 | LBS | 0.85 | 0.92 | 0.80 |
| 1330 | 813-A002 | Concrete Railing, 32" | 4,890.000 | LF | 50.45 | 47.76 | 60.00 |
| 1340 | 815-A009 | Loose Riprap, Size 300 | 3,898.000 | TON | 31.90 | 45.60 | 45.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | T. L. Wallace Construction, Inc. | L & A Contracting Company | Dement Construction Company, LLC |
|--|--------------|--|------------|-------|----------------------------------|---------------------------|----------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$15,852,935.80 | \$15,999,402.50 | \$16,226,091.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 1350 | 815-E001 | Geotextile under Riprap | 5,594.000 | SY | 2.60 | 1.20 | 3.00 |
| 1360 | 907-803-P004 | 36" Steel Pipe Piling, Wall Thickness 0.750" | 1,760.000 | LF | 335.00 | 180.00 | 225.00 |
| 1370 | 907-804-A001 | Bridge Concrete, Class AA | 4,982.000 | CY | 650.00 | 699.00 | 510.00 |
| 1380 | 907-804-C012 | 135' Prestressed Concrete Beam, Type BT-72 | 674.000 | LF | 165.00 | 174.42 | 289.00 |
| 1390 | 907-804-C016 | 40' Prestressed Concrete Beam, Type I+2 | 10,852.000 | LF | 67.00 | 77.46 | 200.00 |
| 1400 | 907-804-C030 | 80' Prestressed Concrete Beam, Type III | 957.000 | LF | 107.00 | 112.20 | 235.00 |
| 1410 | 907-804-C150 | 110' Prestressed Concrete Beam, Type IV | 659.000 | LF | 170.00 | 181.20 | 260.00 |
| 1420 | 907-804-C171 | 100' Prestressed Concrete Beam, Type IV | 1,197.000 | LF | 138.00 | 147.90 | 265.00 |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Century Construction & Realty, Inc. | Eutaw Construction Company, Inc. | |
|--|-----------|---|-------------|-------|-------------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$16,982,269.01 | \$17,059,840.60 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0010 | 201-A001 | Clearing and Grubbing | 1.000 | LS | 445,120.00 | 540,000.00 | |
| 0020 | 202-A001 | Removal of Obstructions | 1.000 | LS | 136,109.82 | 300,000.00 | |
| 0030 | 202-B005 | Removal of Asphalt Pavement, All Depths | 31,661.000 | SY | 4.62 | 5.00 | |
| 0040 | 202-B019 | Removal of Concrete Headwall | 11.000 | EA | 1,070.00 | 350.00 | |
| 0050 | 202-B038 | Removal of Curb, All Types | 119.000 | LF | 16.05 | 8.75 | |
| 0060 | 202-B064 | Removal of Pipe, 8" And Above | 414.000 | LF | 12.84 | 10.00 | |
| 0070 | 202-B076 | Removal of Traffic Stripe | 9,200.000 | LF | 1.07 | 0.97 | |
| 0080 | 202-B080 | Removal of Box Culvert | 37.000 | LF | 195.93 | 125.00 | |
| 0090 | 202-B102 | Removal of Guard Rail | 2,662.000 | LF | 3.22 | 2.90 | |
| 0100 | 203-A003 | Unclassified Excavation, FM, AH | 57,035.000 | CY | 4.28 | 5.90 | |
| 0110 | 203-EX017 | Borrow Excavation, AH, FME, Class B9 | 195,422.000 | CY | 4.28 | 7.75 | |
| 0120 | 203-G003 | Excess Excavation, FM, AH | 33,102.000 | CY | 4.28 | 4.80 | |
| 0130 | 206-A001 | Structure Excavation | 722.000 | CY | 7.49 | 7.00 | |
| 0140 | 209-A004 | Geotextile Stabilization, Type V, Non-Woven | 34,632.000 | SY | 1.39 | 1.50 | |
| 0150 | 213-C001 | Superphosphate | 35.000 | TON | 642.00 | 670.68 | |
| 0160 | 217-A001 | Ditch Liner | 100.000 | SY | 2.14 | 1.21 | |
| 0170 | 219-A001 | Watering | 5.000 | KGAL | 20.00 | 20.00 | |
| 0180 | 220-A001 | Insect Pest Control | 35.000 | ACRE | 30.00 | 30.00 | |
| 0190 | 221-A001 | Portland Cement Concrete Paved Ditch | 29.000 | CY | 390.55 | 637.56 | |
| 0200 | 223-A001 | Mowing | 70.000 | ACRE | 50.00 | 50.00 | |
| 0210 | 234-A001 | Temporary Silt Fence | 2,900.000 | LF | 3.21 | 3.00 | |
| 0220 | 235-A001 | Temporary Erosion Checks | 230.000 | BALE | 7.49 | 9.00 | |
| 0230 | 236-A004 | Silt Basin, Type D | 19.000 | EA | 1,979.50 | 325.00 | |
| 0240 | 239-A001 | Temporary Slope Drains | 875.000 | LF | 7.49 | 5.50 | |
| 0250 | 406-A001 | Cold Milling of Bituminous Pavement, All Depths | 1,867.000 | SY | 7.37 | 9.10 | |
| 0260 | 423-A001 | Rumble Strips, Ground In | 5.000 | MI | 428.00 | 386.00 | |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Century Construction & Realty, Inc. | Eutaw Construction Company, Inc. | |
|--|-----------|--|-----------|-------|-------------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$16,982,269.01 | \$17,059,840.60 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0270 | 501-E001 | Expansion Joints, Without Dowels | 443.000 | LF | 12.84 | 9.50 | |
| 0280 | 502-A001 | Reinforced Cement Concrete Bridge End Pavement | 1,021.000 | SY | 132.47 | 105.00 | |
| 0290 | 602-A001 | Reinforcing Steel | 178.000 | LBS | 3.82 | 0.50 | |
| 0300 | 603-CA003 | 24" Reinforced Concrete Pipe, Class III | 988.000 | LF | 44.94 | 42.00 | |
| 0310 | 603-CA004 | 30" Reinforced Concrete Pipe, Class III | 120.000 | LF | 62.06 | 52.00 | |
| 0320 | 603-CA009 | 60" Reinforced Concrete Pipe, Class III | 100.000 | LF | 155.15 | 145.00 | |
| 0330 | 603-CA015 | 24" Reinforced Concrete Pipe, Class IV | 152.000 | LF | 51.36 | 48.00 | |
| 0340 | 603-CB002 | 24" Reinforced Concrete End Section | 19.000 | EA | 909.50 | 810.00 | |
| 0350 | 603-CB003 | 30" Reinforced Concrete End Section | 2.000 | EA | 963.00 | 560.00 | |
| 0360 | 603-CB008 | 60" Reinforced Concrete End Section | 2.000 | EA | 3,424.00 | 2,665.00 | |
| 0370 | 603-CE004 | 44" x 27" Concrete Arch Pipe, Class A III | 40.000 | LF | 101.65 | 88.00 | |
| 0380 | 603-CF004 | 44" x 27" Concrete Arch Pipe End Section | 2.000 | EA | 1,498.00 | 1,450.00 | |
| 0420 | 606-B001 | Guard Rail, Class A, Type 1 | 1,700.000 | LF | 19.80 | 17.85 | |
| 0430 | 606-D012 | Guard Rail, Bridge End Section, Type 1 | 16.000 | EA | 1,979.50 | 1,785.25 | |
| 0440 | 606-E002 | Guard Rail, Terminal End Section, Flared | 16.000 | EA | 2,407.50 | 2,171.25 | |
| 0450 | 609-D002 | Combination Concrete Curb and Gutter Type 2 | 220.000 | LF | 33.33 | 34.74 | |
| 0460 | 615-A018 | Concrete Bridge End Barrier, 33.5" | 160.000 | LF | 48.42 | 43.09 | |
| 0470 | 619-A1002 | Temporary Traffic Stripe, Continuous White | 6.000 | MI | 856.00 | 772.00 | |
| 0480 | 619-A2001 | Temporary Traffic Stripe, Continuous Yellow | 3,248.000 | LF | 0.16 | 0.14 | |
| 0490 | 619-A4006 | Temporary Traffic Stripe, Skip Yellow | 3.000 | MI | 856.00 | 772.00 | |
| 0500 | 619-A5001 | Temporary Traffic Stripe, Detail | 3,047.000 | LF | 0.27 | 0.24 | |
| 0510 | 619-A6001 | Temporary Traffic Stripe, Legend | 527.000 | LF | 1.07 | 0.97 | |
| 0520 | 619-C7001 | Two-Way Yellow Reflective High Performance Raised Marker | 266.000 | EA | 6.42 | 5.79 | |
| 0530 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 149.000 | SF | 7.76 | 7.00 | |
| 0540 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 360.000 | SF | 7.76 | 7.00 | |
| 0550 | 619-G4001 | Barricades, Type III, Single Faced | 192.000 | LF | 13.38 | 12.06 | |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Century Construction & Realty, Inc. | Eutaw Construction Company, Inc. | |
|--|--------------|---|------------|-------|-------------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$16,982,269.01 | \$17,059,840.60 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0560 | 619-G4005 | Barricades, Type III, Double Faced | 24.000 | LF | 16.05 | 14.48 | |
| 0570 | 619-G5001 | Free Standing Plastic Drums | 152.000 | EA | 46.01 | 41.50 | |
| 0580 | 619-G7001 | Warning Lights, Type "B" | 2.000 | EA | 197.95 | 178.53 | |
| 0590 | 620-A001 | Mobilization | 1.000 | LS | 1,682,147.00 | 1,530,000.00 | |
| 0600 | 621-A001 | Field Laboratory | 1.000 | EA | 30,336.12 | 28,000.00 | |
| 0610 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 257.000 | EA | 6.42 | 5.79 | |
| 0620 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 20.000 | SF | 20.33 | 18.34 | |
| 0630 | 630-A002 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 103.000 | SF | 21.40 | 19.30 | |
| 0640 | 630-C003 | Steel U-Section Posts, 3.0 lb/ft | 182.000 | LF | 9.10 | 8.20 | |
| 0650 | 630-E004 | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar | 24.000 | LBS | 2.68 | 2.41 | |
| 0660 | 630-F001 | Delineators, Guard Rail, White | 88.000 | EA | 19.26 | 17.37 | |
| 0670 | 630-G002 | Type 3 Object Markers, OM-3R or OM-3L, Post Mounted | 16.000 | EA | 80.25 | 72.38 | |
| 0671 | 630-K003 | Welded & Seamless Steel Pipe Posts, 4" | 31.000 | LF | 48.15 | 43.43 | |
| 0680 | 815-A006 | Loose Riprap, Size 100 | 1,943.000 | TON | 32.10 | 38.00 | |
| 0690 | 815-A009 | Loose Riprap, Size 300 | 3,920.000 | TON | 32.10 | 38.00 | |
| 0700 | 815-E001 | Geotextile under Riprap | 2,110.000 | SY | 1.34 | 2.75 | |
| 0710 | 907-216-A001 | Solid Sodding | 248.000 | SY | 4.28 | 3.62 | |
| 0720 | 907-225-A001 | Grassing | 70.000 | ACRE | 642.00 | 718.93 | |
| 0730 | 907-225-B001 | Agricultural Limestone | 208.000 | TON | 53.50 | 62.73 | |
| 0740 | 907-225-C001 | Mulch, Vegetative Mulch | 139.000 | TON | 187.25 | 149.58 | |
| 0750 | 907-226-A001 | Temporary Grassing | 70.000 | ACRE | 642.00 | 574.18 | |
| 0760 | 907-234-C002 | Super Silt Fence | 13,735.000 | LF | 7.49 | 8.35 | |
| 0770 | 907-234-F001 | Turbidity Barrier | 600.000 | LF | 17.12 | 18.00 | |
| 0780 | 907-237-A003 | Wattles, 20" | 570.000 | LF | 4.28 | 5.00 | |
| 0790 | 907-245-A001 | Triangular Silt Dike | 570.000 | LF | 7.49 | 9.50 | |
| 0800 | 907-246-A001 | Sandbags | 570.000 | LF | 3.75 | 7.50 | |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Century Construction & Realty, Inc. | Eutaw Construction Company, Inc. | |
|--|---------------|--|-------------|-------|-------------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$16,982,269.01 | \$17,059,840.60 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0810 | 907-249-A001 | Riprap for Erosion Control | 336.000 | TON | 32.10 | 38.00 | |
| 0820 | 907-304-A011 | Granular Material, LVM, Class 9, Group A | 107,815.000 | CY | 4.28 | 6.25 | |
| 0830 | 907-304-B009 | Granular Material, Class 3, Group D | 7,715.000 | TON | 32.10 | 35.00 | |
| 0840 | 907-307-C003 | 6" Soil-Lime-Water Mixing, Class C | 20,885.000 | SY | 1.61 | 1.45 | |
| 0850 | 907-307-D001 | Lime | 192.000 | TON | 240.75 | 217.13 | |
| 0860 | 907-307-S001 | Bituminous Curing Seal | 3,538.000 | GAL | 4.82 | 4.34 | |
| 0870 | 907-403-A022 | 9.5-mm, MT, Asphalt Pavement | 3,629.000 | TON | 100.05 | 94.44 | |
| 0880 | 907-403-A023 | 12.5-mm, MT, Asphalt Pavement | 4,025.000 | TON | 93.09 | 87.88 | |
| 0890 | 907-403-A024 | 19-mm, MT, Asphalt Pavement | 4,037.000 | TON | 79.18 | 74.75 | |
| 0900 | 907-407-A001 | Asphalt for Tack Coat | 3,622.000 | GAL | 3.21 | 3.03 | |
| 0910 | 907-413-E001 | Sawing and Sealing Transverse Joints in Asphalt Pavement | 375.000 | LF | 13.91 | 12.55 | |
| 0920 | 907-601-B003 | Class "B" Structural Concrete, Minor Structures | 8.000 | CY | 1,582.54 | 1,644.68 | |
| 0930 | 907-603-ALT01 | 18" Type A Alternate Pipe | 472.000 | LF | 26.75 | 21.00 | |
| 0940 | 907-603-ALT02 | 24" Type A Alternate Pipe | 328.000 | LF | 62.06 | 30.00 | |
| 0970 | 907-617-A001 | Right-of-Way Marker | 66.000 | EA | 224.70 | 145.00 | |
| 0980 | 907-618-A001 | Maintenance of Traffic | 1.000 | LS | 48,881.98 | 280,000.00 | |
| 0990 | 907-626-C004 | 6" Thermoplastic Edge Stripe, Continuous White | 5.000 | MI | 2,568.00 | 2,316.00 | |
| 1000 | 907-626-D003 | 6" Thermoplastic Traffic Stripe, Skip Yellow | 3.000 | MI | 1,070.00 | 965.00 | |
| 1010 | 907-626-E004 | 6" Thermoplastic Traffic Stripe, Continuous Yellow | 1.000 | MI | 2,568.00 | 2,316.00 | |
| 1020 | 907-626-G004 | Thermoplastic Detail Stripe, White | 741.000 | LF | 2.14 | 1.93 | |
| 1030 | 907-626-H004 | Thermoplastic Legend, White | 186.000 | LF | 4.28 | 3.86 | |
| 1040 | 907-631-B001 | Flowable Fill, Non-Excavatable | 11.000 | CY | 184.68 | 325.00 | |
| 1050 | 907-699-A002 | Roadway Construction Stakes | 1.000 | LS | 285,420.32 | 195,000.00 | |
| 1060 | 907-815-F001 | Sediment Control Stone | 400.000 | TON | 50.00 | 36.00 | |
| 1070 | 907-906001 | Trainees | 720.000 | HRS | 5.00 | 5.00 | |
| 1080 | 907-304-F002 | Size 610 Crushed Stone Base | 13,812.000 | TON | 26.75 | 26.50 | |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Century Construction & Realty, Inc. | Eutaw Construction Company, Inc. | |
|--|--------------|---|-------------|-------|-------------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$16,982,269.01 | \$17,059,840.60 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 1090 | 907-304-F003 | 3/4" and Down Crushed Stone Base | 13,812.000 | TON | | | |
| 1100 | 907-304-F004 | Size 825B Crushed Stone Base | 13,812.000 | TON | | | |
| 1110 | 907-308-A001 | Portland Cement | 128.000 | TON | 187.25 | 168.88 | |
| 1120 | 907-308-B001 | Soil-Cement-Water Mixing, Optional Mixers, Base | 20,885.000 | SY | 1.61 | 1.45 | |
| 1130 | 907-308-S001 | Bituminous Curing Seal | 3,538.000 | GAL | 4.82 | 4.34 | |
| 1140 | 907-311-A003 | Processing Lime and Fly Ash Treated Course, 6" Thick | 20,885.000 | SY | | | |
| 1150 | 907-311-B001 | Lime | 96.000 | TON | | | |
| 1160 | 907-311-C001 | Fly Ash, Class C | 431.000 | TON | | | |
| 1170 | 907-311-S001 | Bituminous Curing Seal | 3,538.000 | GAL | | | |
| 1180 | 907-626-J003 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White | 5,258.000 | LF | | | |
| 1190 | 907-626-K003 | 6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow | 1,240.000 | LF | | | |
| 1200 | 907-626-L001 | 6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow | 2,006.000 | LF | | | |
| 1210 | 628-J002 | 6" High Performance Cold Plastic Traffic Stripe, Continuous White | 5,258.000 | LF | 6.42 | 5.79 | |
| 1220 | 628-L002 | 6" High Performance Cold Plastic Traffic Stripe, Skip Yellow | 1,240.000 | LF | 5.35 | 4.83 | |
| 1230 | 628-M002 | 6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow | 2,006.000 | LF | 6.42 | 5.79 | |
| 1240 | 501-K001 | Transverse Grooving | 10,865.000 | SY | 2.14 | 1.93 | |
| 1250 | 803-B002 | Conventional Static Pile Load Test | 4.000 | EA | 5,000.00 | 5,000.00 | |
| 1260 | 803-D006 | HP 14 x 117 Steel Piling | 14,115.000 | LF | 89.72 | 50.00 | |
| 1270 | 803-D007 | HP 14 x 89 Steel Piling | 4,080.000 | LF | 75.44 | 40.00 | |
| 1280 | 803-D009 | HP 16 x 183 Steel Piling | 1,700.000 | LF | 173.01 | 90.00 | |
| 1290 | 803-D010 | HP 18 x 181 Steel Piling | 2,180.000 | LF | 163.32 | 100.00 | |
| 1300 | 803-I001 | PDA Test Pile | 25.000 | EA | 10,353.46 | 11,000.00 | |
| 1310 | 803-J001 | Pile Restrike | 4.000 | EA | 942.92 | 1,150.00 | |
| 1320 | 805-A001 | Reinforcement | 996,072.000 | LBS | 0.91 | 0.91 | |
| 1330 | 813-A002 | Concrete Railing, 32" | 4,890.000 | LF | 50.16 | 46.39 | |
| 1340 | 815-A009 | Loose Riprap, Size 300 | 3,898.000 | TON | 7.53 | 38.00 | |

| Replacing Bridge Nos. 166.2, 166.4, 167.8, & 168.3 on SR 7, known as Federal Aid Project No. BR-0019-02(054) / 105189302 in Benton County. | | | | | Century Construction & Realty, Inc. | Eutaw Construction Company, Inc. | |
|--|--------------|--|------------|-------|-------------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$15,009,999.60 | | | | | \$16,982,269.01 | \$17,059,840.60 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 1350 | 815-E001 | Geotextile under Riprap | 5,594.000 | SY | 2.27 | 2.75 | |
| 1360 | 907-803-P004 | 36" Steel Pipe Piling, Wall Thickness 0.750" | 1,760.000 | LF | 435.89 | 235.00 | |
| 1370 | 907-804-A001 | Bridge Concrete, Class AA | 4,982.000 | CY | 717.48 | 780.00 | |
| 1380 | 907-804-C012 | 135' Prestressed Concrete Beam, Type BT-72 | 674.000 | LF | 188.68 | 160.00 | |
| 1390 | 907-804-C016 | 40' Prestressed Concrete Beam, Type I+2 | 10,852.000 | LF | 75.93 | 70.00 | |
| 1400 | 907-804-C030 | 80' Prestressed Concrete Beam, Type III | 957.000 | LF | 120.09 | 100.00 | |
| 1410 | 907-804-C150 | 110' Prestressed Concrete Beam, Type IV | 659.000 | LF | 187.66 | 140.00 | |
| 1420 | 907-804-C171 | 100' Prestressed Concrete Beam, Type IV | 1,197.000 | LF | 151.12 | 140.00 | |