

**Call 02 US 82 Abandoned RR Bridge Removal in Leland, known as Federal Aid Project No. NHPP-0011-01(066) / 106532301 in Washington County.**

Q1. **1.** Signal questions: working # TRS-1, sheet 2001 traffic signal construction notes: # 13 where does this note apply? **2.** Pay item # 666-B041 6/3 conductor, where is a 1040' to be used? I see about 200' max. **3.** In order to calculate the monthly cost from utility company, how long will it take MDOT to inspect the traffic signal and get the monthly bill in their name after contractor has completed the work? **4.** Several of the 3" bores have multiple conduits. How will this item be measured? **5.** Lighting: what is the scale on working # SL-1 sheet number 4001? **6.** How long is the burn in time? **7.** After contractor is completed: How long will it take MDOT to inspect the work? **8.** How long will it take MDOT to get monthly bill in their name?

A1. **1.** This note is in reference to the traffic control cabinet for installation of a service pole/meter base. **2.** This is an estimated quantity, field conditions will dictate. **3.** After all work is completed a final inspection will be scheduled. **4.** The bores will be paid for as per the plans and separately if plans dictate. **5.** There is nothing to scale on this page. **6.** As per Section 681.02.1 of the 2004 Mississippi Standard Specifications for Road and Bridge Construction, it will be 14 Days. **7.** Reference answer in Number #3. **8.** Approximately 1 month after a final maintenance release.