

**Call 17 Scrub Seal approximately 34 miles of roadway throughout the District, known as State Project No. MP-7000-00(182) / 305460301 Districtwide (7).**

Q1. **1.** Scope of work note #3 states that removal of all thermoplastic markings will be removed prior to placement of seal which is equal to +/- 550,440 LF of removal, is that your intentions? **2.** Will you require any temporary paint to be placed after removing all stripe and prior to placement of seal or will chip seal markers be enough?

A1. **1.** The roadway contains thermoplastic, cold plastic and a majority of paint striping. Only the thermoplastic and cold plastic will require removal and will be paid for using the Removal of Traffic Stripe pay item. Paint will not be removed. **2.** Temporary paint will not be required but the chip seal markers will be required.