

Overlay approximately 5 miles of US 84 from East end of Bude Bypass to Homochitto River Bridge, known as Federal Aid Project No. NH-0015-01(131) / 106697301 in Franklin County.					W. E. Blain & Sons, Inc.	Dickerson & Bowen, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,865,620.53					\$2,051,859.46	\$2,245,277.76	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B053	Removal of Guard Rail Including Post, Blockouts & Hardware	837.000	LF	4.00	4.00	
0020	202-B076	Removal of Traffic Stripe	2,119.000	LF	0.50	0.50	
0030	203-G004	Excess Excavation, LVM, AH	51.000	CY	100.00	200.00	
0040	406-A001	Cold Milling of Bituminous Pavement, All Depths	20,308.000	SY	4.50	6.00	
0050	423-A001	Rumble Strips, Ground In	15.000	MI	505.00	500.00	
0060	606-B001	Guard Rail, Class A, Type 1	625.000	LF	19.00	19.00	
0070	606-D007	Guard Rail, Bridge End Section, Type G, Modified	4.000	EA	1,800.00	1,800.00	
0080	606-E002	Guard Rail, Terminal End Section, Flared	4.000	EA	2,150.00	2,150.00	
0090	619-A1002	Temporary Traffic Stripe, Continuous White	8.000	MI	300.00	300.00	
0100	619-A2002	Temporary Traffic Stripe, Continuous Yellow	7.000	MI	300.00	300.00	
0110	619-A3006	Temporary Traffic Stripe, Skip White	8.000	MI	300.00	300.00	
0120	619-A5001	Temporary Traffic Stripe, Detail	28,292.000	LF	0.03	0.03	
0130	619-A6001	Temporary Traffic Stripe, Legend	1,152.000	LF	0.50	0.50	
0140	619-A6002	Temporary Traffic Stripe, Legend	342.000	SF	1.00	1.00	
0150	627-J001	Two-Way Clear Reflective High Performance Raised Markers	303.000	EA	3.00	3.00	
0160	627-K001	Red-Clear Reflective High Performance Raised Markers	864.000	EA	3.00	3.00	
0170	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	92.000	EA	3.00	3.00	
0180	630-F001	Delineators, Guard Rail, White	49.000	EA	18.00	18.00	
0190	630-F002	Delineators, Guard Rail, Yellow	49.000	EA	18.00	18.00	
0200	630-F003	Delineators, Flexible Post Mounted, Crossover, Type I, Green	14.000	EA	35.00	35.00	
0210	630-F004	Delineators, Flexible Post Mounted, Crossover, Type I, Yellow	14.000	EA	35.00	35.00	
0220	630-F005	Delineators, Flexible Post Mounted, Crossover, Type II	6.000	EA	40.00	40.00	
0230	907-304-A003	Granular Material, LVM, Class 6, Group D	6,086.000	CY	20.00	40.00	
0240	907-403-A022	9.5-mm, MT, Asphalt Pavement	14,081.000	TON	85.00	89.50	
0250	907-403-B016	9.5-mm, MT, Asphalt Pavement, Leveling	830.000	TON	95.00	137.00	
0260	907-407-A001	Asphalt for Tack Coat	14,562.000	GAL	3.10	4.50	

Overlay approximately 5 miles of US 84 from East end of Bude Bypass to Homochitto River Bridge, known as Federal Aid Project No. NH-0015-01(131) / 106697301 in Franklin County.					W. E. Blain & Sons, Inc.	Dickerson & Bowen, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,865,620.53					\$2,051,859.46	\$2,245,277.76	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	160.000	LF	5.00	5.00	
0280	907-420-A001	Undersealing Concrete Pavement	12,000.000	LBS	2.25	4.05	
0290	907-618-A001	Maintenance of Traffic	1.000	LS	379,000.00	275,000.00	
0300	907-618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	
0310	907-626-A003	6" Thermoplastic Traffic Stripe, Skip White	8.000	MI	900.00	900.00	
0320	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	8.000	MI	2,000.00	2,000.00	
0330	907-626-F003	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	7.000	MI	1,900.00	1,900.00	
0340	907-626-G004	Thermoplastic Detail Stripe, White	13,188.000	LF	0.45	0.45	
0350	907-626-G005	Thermoplastic Detail Stripe, Yellow	15,104.000	LF	0.40	0.40	
0360	907-626-H004	Thermoplastic Legend, White	1,152.000	LF	0.90	0.90	
0370	907-626-H005	Thermoplastic Legend, White	342.000	SF	4.00	4.00	