

Overlay with High Friction Surface Treatment approximately 2 miles of SR 537 from 100 feet South of the Northview / Hwy 537 Intersection to 100 feet North of Buck Temple Road, known as Federal Aid Project No. HSIP-0225-00(005) / 107003301 in Jones County.					Dunn Roadbuilders, LLC		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$895,380.53					\$976,814.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-A001	Removal of Obstructions	1.000	LS	15,000.00		
0020	202-B053	Removal of Guard Rail Including Post, Blockouts & Hardware	970.000	LF	6.00		
0030	202-B076	Removal of Traffic Stripe	700.000	LF	2.00		
0040	202-B078	Removal of Pavement, All Types and Depths	50.000	SY	21.00		
0050	406-A001	Cold Milling of Bituminous Pavement, All Depths	3,415.000	SY	7.00		
0060	606-B005	Guard Rail, Class A, Type 1, 'W' Beam	350.000	LF	21.00		
0070	606-D015	Guard Rail, Bridge End Section	8.000	EA	1,980.00		
0080	606-E003	Guard Rail, Terminal End Section, Non-Flared	12.000	EA	2,729.00		
0090	619-A1002	Temporary Traffic Stripe, Continuous White	10.000	MI	535.00		
0100	619-A2002	Temporary Traffic Stripe, Continuous Yellow	9.000	MI	535.00		
0110	619-A4006	Temporary Traffic Stripe, Skip Yellow	2.000	MI	535.00		
0120	619-A5001	Temporary Traffic Stripe, Detail	2,500.000	LF	1.00		
0130	619-A6001	Temporary Traffic Stripe, Legend	1,500.000	LF	1.00		
0140	627-J001	Two-Way Clear Reflective High Performance Raised Markers	180.000	EA	5.00		
0150	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	360.000	EA	5.00		
0160	630-F001	Delineators, Guard Rail, White	48.000	EA	20.00		
0170	630-G001	Type 3 Object Markers, OM-3R, Post Mounted	6.000	EA	80.00		
0180	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	6.000	EA	80.00		
0190	907-304-F004	Size 825B Crushed Stone Base	700.000	TON	60.00		
0200	907-403-A017	9.5-mm, ST, Asphalt Pavement	2,500.000	TON	129.00		
0210	907-403-A019	19-mm, ST, Asphalt Pavement	50.000	TON	166.00		
0220	907-403-B013	12.5-mm, ST, Asphalt Pavement, Leveling	1,400.000	TON	121.00		
0230	907-407-A001	Asphalt for Tack Coat	4,300.000	GAL	4.00		
0240	907-410-D001	High Friction Surface Treatment	6,600.000	SY	28.00		
0250	907-618-A001	Maintenance of Traffic	1.000	LS	80,000.00		
0260	907-618-B001	Additional Construction Signs	1.000	SF	10.00		

Overlay with High Friction Surface Treatment approximately 2 miles of SR 537 from 100 feet South of the Northview / Hwy 537 Intersection to 100 feet North of Buck Temple Road, known as Federal Aid Project No. HSIP-0225-00(005) / 107003301 in Jones County.					Dunn Roadbuilders, LLC		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$895,380.53					\$976,814.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	5.000	MI	2,675.00		
0280	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	1.000	MI	1,605.00		
0290	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	4.000	MI	2,675.00		
0300	907-626-G004	Thermoplastic Detail Stripe, White	854.000	LF	2.00		
0310	907-626-G005	Thermoplastic Detail Stripe, Yellow	392.000	LF	2.00		
0320	907-626-H004	Thermoplastic Legend, White	732.000	LF	2.00		