

**Call 12 Bridge Replacement on SR 429 at Yockanookany River Bridge No. 3.6, known as State Project No. EXB-0521-00(006) / 100592301 in Leake County.**

Q1. Most of the area designated as wetlands appears to be sandy material. Can tracked equipment be used in the clearing operations?

A1. Yes

Q2. Per sheet number 8003, 30" pipe piles are to be 0.5 inches. Per sheet number 8013 section A-A, 30" pipe piles are to be 0.75 inches. Which is the correct wall thickness?

A2. The correct thickness is 0.5 inches. The pay item shown on the bid sheets is correct.