

Call 01 Work necessary for Intersection Improvements on SR 302 from I-55 to Marshall County Line, known as Federal Aid Project No. HSIP-0021-01(061) / 106779302 in Desoto County.

Q1. We purchased the plans for this project in the earlier letting. Have there been any changes done since then to the plans?

A1. Yes

Q2. **1.** Is the 4" metal post, foundation concrete, prepare to stop sign, when flashing sign included in this pay item? Or will these items be paid for under other pay items? **2.** For both east and west bound inside signs, I do not see a junction box shown on prints, where will the waterproof fuse be located? Do (2) type 2 pull boxes need to be added? Note 3 on sheet 2015 calls for a waterproof cut-off switch at meter. **3.** RE: Where is the pay items for the (2) modified type 5 curb ramps shown on sheet MD-3 sheet # 65? **4.** RE: Will MDOT be providing any surveying/layout services? **5.** RE: 907-642-C001 GPS clock system, at which intersection will this be installed?

A2. **1.** It will be absorbed in the pay item for the sign. **2.** There are Type 2 pull boxes for each approach at the signs shown in TSI-7. **3.** It is covered by note 4 on the same sheet 65. **4.** No, the contractor will be responsible for layout/surveying. We have a roadway construction stakes pay item. **5.** Craft Rd. see TSI-5

Q3. Why do plan quantity and bid x spread sheet not match?

A3. A Supplemental Agreement may be issued after award of the contract to address any pay item(s) that were inadvertently omitted from the bid sheets. The Contractor's bid should reflect only the bid items listed on the bid sheets.