

Mill and Overlay approximately 11 miles of SR 15 from the Chickasaw County Line to SR 41, known as State Project No. MP-1015-58 (002) / 305719301 in Pontotoc County.					APAC - Mississippi, Inc.	Lehman-Roberts Company	WG Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,574,650.71					\$2,182,177.35	\$2,348,532.63	\$2,914,779.00
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	202-B005	Removal of Asphalt Pavement, All Depths	2,167.000	SY	17.85	14.16	20.00
0020	202-B076	Removal of Traffic Stripe	1,538.000	LF	1.00	1.00	1.00
0030	203-G003	Excess Excavation, FM, AH	1,625.000	CY	10.50	4.80	22.00
0040	423-A001	Rumble Strips, Ground In	21.000	MI	260.00	414.78	460.00
0050	619-A1002	Temporary Traffic Stripe, Continuous White	42.000	MI	400.00	400.00	400.00
0060	619-A2002	Temporary Traffic Stripe, Continuous Yellow	20.000	MI	500.00	500.00	500.00
0070	619-A4006	Temporary Traffic Stripe, Skip Yellow	16.000	MI	500.00	500.00	500.00
0080	619-A5002	Temporary Traffic Stripe, Detail, Paint	5,506.000	LF	0.25	0.25	0.25
0090	619-A6001	Temporary Traffic Stripe, Legend	1,443.000	LF	1.00	1.00	1.00
0100	620-A001	Mobilization	1.000	LS	125,000.00	84,426.92	210,000.00
0110	627-J001	Two-Way Clear Reflective High Performance Raised Markers	468.000	EA	5.50	5.50	5.50
0120	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,032.000	EA	5.50	5.50	5.50
0130	907-304-A008	Granular Material, LVM, Class 3, Group C	540.000	CY	50.00	69.97	42.00
0140	907-403-A022	9.5-mm, MT, Asphalt Pavement	16,824.000	TON	70.00	77.81	89.00
0145	907-403-A024	19-mm, MT, Asphalt Pavement	1,430.000	TON	100.00	85.47	100.00
0150	907-406-D001	Fine Milling of Bituminous Pavement, All Depths	185,487.000	SY	1.30	1.78	2.00
0160	907-407-A001	Asphalt for Tack Coat	15,485.000	GAL	2.50	2.88	4.00
0170	907-618-A001	Maintenance of Traffic	1.000	LS	125,000.00	60,790.56	210,000.00
0180	907-618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	10.00
0190	907-626-B004	6" Thermoplastic Traffic Stripe, Continuous White	21.000	MI	2,200.00	2,200.00	2,200.00
0200	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	10.000	MI	1,100.00	1,100.00	1,100.00
0210	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	8.000	MI	2,200.00	2,200.00	2,200.00
0220	907-626-G004	Thermoplastic Detail Stripe, White	4,319.000	LF	1.25	1.25	1.25
0230	907-626-G005	Thermoplastic Detail Stripe, Yellow	1,187.000	LF	1.25	1.25	1.25
0240	907-626-H004	Thermoplastic Legend, White	1,443.000	LF	3.00	3.00	3.00
0250	907-304-H002	3/4" and Down Crushed Stone Base, LVM	2,445.000	CY	40.74		68.00

Mill and Overlay approximately 11 miles of SR 15 from the Chickasaw County Line to SR 41, known as State Project No. MP-1015-58 (002) / 305719301 in Pontotoc County.					APAC - Mississippi, Inc.	Lehman-Roberts Company	WG Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,574,650.71					\$2,182,177.35	\$2,348,532.63	\$2,914,779.00
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0260	907-304-H003	Size 610 Crushed Stone Base, LVM	2,445.000	CY		68.89	
0270	907-304-H004	Size 825B Crushed Stone Base, LVM	2,445.000	CY			
0280	907-626-K003	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow	694.000	LF			
0290	907-626-L001	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous Yellow	1,388.000	LF			
0300	628-J002	6" High Performance Cold Plastic Traffic Stripe, Continuous White	1,388.000	LF	5.00	5.00	5.00
0310	628-L002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	694.000	LF	5.00	5.00	5.00