

Call 08 Bridge Replacement on SR 32 between Webb & Charleston (Bridge Nos. 43.1, 43.5, 43.7, & R.R. Bridge) , known as State Project No. EXB-0051-02(021) / 102383301 in Tallahatchie County.

Q1. Is the 3' cut off on the concrete pile included in the estimated pile length shown on the pile schedule?

A1. The 3' cut off is accounted for in the estimated quantities but not accounted for in the estimated pile lengths shown on the pile schedule.

Q2. Pay Item 621-A001 Field Lab in on the summary of quantities sheet #13, but does not appear on the EBS file bid document. Please clarify. Pay Item 907-815-F001 Sediment Control Stone list a qty of 175 tons, but Note 1 & 2 indicates that qty includes 987 tons for silt basins and 40 tons for ditch treatment. Please clarify.

A2. See the upcoming addendum.

Q3. Will the Q&A from the prior advertisement of this project be posted or do the questions need to be resubmitted?

A3. Questions should be resubmitted.

Q4. NTB 6016 in Addendum #1 states "Settlement Plate data will not be considered for any excavation payment." Does MDOT have an idea of how much subsidence will occur at each site? This would be valuable information in that this will be made up of borrow material the contractor hauls to the sites and will not be paid for.

A4. The contractor will be compensated for the borrow material placed, and will be paid for the excess that is removed by cross sections. The NTB states that cross sections will be taken upon reaching the specified plan finish grade on the specified lift, and immediately prior to any subsequent lifts. This will ensure the contractor is properly compensated.