

Call 09 Bridge Replacement on SR 32 Between Webb and Charleston (Bridge Nos. 53 & 53.3), known as State Project No. EXB-0051-02(025) / 102383304 in Tallahatchie County.

Q1. Is the 3' cut off on the concrete pile included in the estimated pile length shown on the pile schedule?

A1. The 3' cut off is accounted for in the estimated quantities but not accounted for in the estimated pile lengths shown on the pile schedule.

Q2. Is the top three foot of the 16" concrete pile subsidiary to the pay item "16"x16" Prest. Conc. Piling," or is the top three feet included in the lengths on the pile schedule?

A2. See QandA #1.

Q3. The following Pay Items appear on the Summary of Quantities Sheet 11 - 13, but do not appear on the EBS file: 203-EX017 223-A001 907-249-A001 408-A003 606-B001 619-A1003 619-D1001 907-626-C003 630-G002 Please clarify.

A3. See the upcoming addendum.

Q4. The plans show a bid item for "203-EX017 Borrow Excavation, AH, FME, Class B9 - 28,948 CY", but it is not shown in the expedite file. Please verify.

A4. See the upcoming addendum.

Q5. Is there a pay item for < less than construction signs?

A5. See the upcoming addendum.