

Bridge Replacement on SR 473 at Vaughn Creek, known as State Project No. EXB-0398-00(002) / 100585301 in Hinds County.					Joe McGee Construction Company, Inc.	Dozer, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,713,408.65					\$1,880,790.93	\$2,320,152.85	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-A001	Clearing and Grubbing	1.000	LS	150,000.00	260,000.00	
0020	201-B001	Clearing and Grubbing	1.000	ACRE	6,600.00	10,000.00	
0030	202-A001	Removal of Obstructions	1.000	LS	15,000.00	20,000.00	
0040	202-B005	Removal of Asphalt Pavement, All Depths	3,067.000	SY	7.00	10.00	
0050	202-B053	Removal of Guard Rail Including Post, Blockouts & Hardware	796.000	LF	5.00	5.00	
0060	202-B064	Removal of Pipe, 8" And Above	60.000	LF	11.75	25.00	
0070	203-A003	Unclassified Excavation, FM, AH	2,582.000	CY	7.40	10.00	
0080	203-EX035	Borrow Excavation, AH, FME, Class B9-6	6,236.000	CY	16.85	20.00	
0090	203-G003	Excess Excavation, FM, AH	500.000	CY	16.00	10.00	
0100	209-A004	Geotextile Stabilization, Type V, Non-Woven	6,359.000	SY	2.00	3.00	
0110	213-C001	Superphosphate	2.000	TON	750.00	525.00	
0120	217-A001	Ditch Liner	49.000	SY	5.00	3.00	
0130	219-A001	Watering	2.000	KGAL	20.00	20.00	
0140	220-A001	Insect Pest Control	2.000	ACRE	30.00	30.00	
0150	221-A001	Portland Cement Concrete Paved Ditch	11.000	CY	675.00	520.00	
0160	223-A001	Mowing	4.000	ACRE	50.00	50.00	
0170	224-A001	Soil Reinforcing Mat	701.000	SY	5.00	2.50	
0180	234-A001	Temporary Silt Fence	2,745.000	LF	3.75	3.50	
0190	236-A004	Silt Basin, Type D	3.000	EA	3,000.00	2,500.00	
0200	423-A001	Rumble Strips, Ground In	1.000	MI	500.00	500.00	
0210	501-E001	Expansion Joints, Without Dowels	78.000	LF	0.01	5.25	
0220	502-A001	Reinforced Cement Concrete Bridge End Pavement	166.000	SY	235.00	204.75	
0230	606-B001	Guard Rail, Class A, Type 1	400.000	LF	18.00	18.00	
0240	606-D012	Guard Rail, Bridge End Section, Type 1	4.000	EA	1,950.00	1,950.00	
0250	606-E001	Guard Rail, Terminal End Section	4.000	EA	2,250.00	2,250.00	
0260	615-A015	Concrete Bridge End Barrier, 32"	40.000	LF	50.00	52.00	

Bridge Replacement on SR 473 at Vaughn Creek, known as State Project No. EXB-0398-00(002) / 100585301 in Hinds County.					Joe McGee Construction Company, Inc.	Dozer, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,713,408.65					\$1,880,790.93	\$2,320,152.85	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	619-A1001	Temporary Traffic Stripe, Continuous White	3,400.000	LF	0.50	0.75	
0280	619-A2001	Temporary Traffic Stripe, Continuous Yellow	3,400.000	LF	0.50	0.75	
0290	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	343.000	SF	7.50	7.50	
0300	619-G4005	Barricades, Type III, Double Faced	108.000	LF	20.00	18.00	
0310	619-G7001	Warning Lights, Type "B"	4.000	EA	210.00	485.00	
0320	620-A001	Mobilization	1.000	LS	135,000.00	222,800.00	
0330	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	28.000	EA	15.00	40.00	
0340	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	12.000	SF	18.00	18.00	
0350	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	18.000	SF	19.00	19.00	
0360	630-C003	Steel U-Section Posts, 3.0 lb/ft	66.000	LF	8.50	8.50	
0370	630-F001	Delineators, Guard Rail, White	22.000	EA	18.00	18.00	
0380	815-A009	Loose Riprap, Size 300	820.000	TON	75.00	62.55	
0390	815-E001	Geotextile under Riprap	521.000	SY	2.00	3.00	
0400	907-216-A001	Solid Sodding	82.000	SY	10.00	10.00	
0410	907-225-A001	Grassing	4.000	ACRE	1,250.00	1,200.00	
0420	907-225-B001	Agricultural Limestone	2.000	TON	125.00	100.00	
0430	907-225-C001	Mulch, Vegetative Mulch	9.000	TON	200.00	200.00	
0440	907-226-A001	Temporary Grassing	4.000	ACRE	1,250.00	1,200.00	
0450	907-234-C002	Super Silt Fence	435.000	LF	10.00	9.50	
0460	907-234-F001	Turbidity Barrier	200.000	LF	8.00	25.00	
0470	907-237-A003	Wattles, 20"	250.000	LF	5.00	9.00	
0480	907-249-A001	Riprap for Erosion Control	50.000	TON	75.00	62.55	
0490	907-253-A001	Coir Fiber Baffle	380.000	LF	6.50	25.00	
0500	907-304-B007	Granular Material, Class 5, Group E	839.000	TON	19.00	35.00	
0510	907-403-A018	12.5-mm, ST, Asphalt Pavement	683.000	TON	95.00	94.00	
0520	907-403-A019	19-mm, ST, Asphalt Pavement	756.000	TON	90.00	85.00	

Bridge Replacement on SR 473 at Vaughn Creek, known as State Project No. EXB-0398-00(002) / 100585301 in Hinds County.					Joe McGee Construction Company, Inc.	Dozer, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,713,408.65					\$1,880,790.93	\$2,320,152.85	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	907-403-C009	19-mm, ST, Asphalt Pavement, Trench Widening	18.000	TON	105.00	220.00	
0540	907-406-A001	Cold Milling of Bituminous Pavement, All Depths	595.000	SY	9.00	17.00	
0550	907-407-A001	Asphalt for Tack Coat	259.000	GAL	3.25	2.50	
0560	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	272.000	LF	8.00	9.75	
0570	907-603-ALT01	18" Type A Alternate Pipe	72.000	LF	24.50	35.00	
0580	907-618-A001	Maintenance of Traffic	1.000	LS	7,500.00	26,500.00	
0590	907-619-E3001	Changeable Message Sign	2.000	EA	4,500.00	13,400.00	
0600	907-626-C007	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,400.000	LF	0.75	1.25	
0610	907-626-E005	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	3,400.000	LF	0.75	1.25	
0620	907-699-B002	Bridge Construction Stakes	1.000	LS	35,000.00	44,650.00	
0630	907-815-F001	Sediment Control Stone	79.000	TON	65.00	55.55	
0640	907-304-F002	Size 610 Crushed Stone Base	2,857.000	TON	47.00	53.55	
0650	907-304-F003	3/4" and Down Crushed Stone Base	2,857.000	TON			
0660	907-304-F004	Size 825B Crushed Stone Base	2,857.000	TON			
0670	803-B002	Conventional Static Pile Load Test	1.000	EA	5,000.00	5,000.00	
0680	803-D002	HP 12 x 53 Steel Piling	650.000	LF	43.00	47.00	
0690	803-D003	HP 14 x 73 Steel Piling	970.000	LF	59.00	60.00	
0700	803-I003	PDA Test Pile, HP Steel Pile	3.000	EA	9,000.00	10,000.00	
0710	803-J001	Pile Restrike	2.000	EA	500.00	1,000.00	
0720	805-A001	Reinforcement	11,007.000	LBS	1.25	1.00	
0730	813-A002	Concrete Railing, 32"	400.000	LF	50.00	52.00	
0740	815-A009	Loose Riprap, Size 300	2,591.000	TON	75.00	62.55	
0750	815-E001	Geotextile under Riprap	2,848.000	SY	2.00	3.00	
0760	907-804-A018	Bridge Concrete, Substructure, Class AA	73.000	CY	1,350.00	895.00	
0770	907-804-E001	40' Prestressed Concrete Voided Slab, 4'-0" Interior	40.000	EA	7,600.00	9,500.00	
0780	907-804-F001	40' Prestressed Concrete Voided Slab, 3'-5" Exterior	10.000	EA	8,700.00	9,500.00	

Bridge Replacement on SR 473 at Vaughn Creek, known as State Project No. EXB-0398-00(002) / 100585301 in Hinds County.					Joe McGee Construction Company, Inc.	Dozer, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,713,408.65					\$1,880,790.93	\$2,320,152.85	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0790	907-826-A001	Waterproofing Membrane	800.000	SY	9.00	120.00	

Letting Date: 5/24/2016

Call Number: 11

Page 4 of 4