

Call 01 Shoulder Widening approximately 11 miles of US 49 from Old Hwy 49/Wilson Holmes Road to Witherspoon Road, known as Federal Aid Project No. HSIP-0008-04(063) / 106963301 in Yazoo County.

Q1. Pay Item 907-406-A003 has a quantity of 6,500 tons. The scope of work does not detail describe any milling. Will milling be required on this project? If so, where?

A1. Milling will be done on all local roads, 4 lane median cross-overs, and cross-overs which connect Old Highway 49 to the new 4 lane 49 facility. These areas will be paved with 12.5mm asphalt at the proper lines and grades. These areas will receive stripe in accordance with the MUTCD latest edition. Milled surfaces shall be covered with asphalt within 3 days of milling.

Q2. **1.** What will the depth of the milling be on local roads and crossovers? **2.** Pay item 907-304-F002 has a quantity of 500 tons, what will this be used for?

A2. **1.** One and one-half (1 ½) inches and variable depth. **2.** It will be used as directed by the Engineer for repair of failed areas if encountered.

Q3. How is the contractor to address driveway pads that will conflict with the trench widening?

A3. Reference the last paragraph of item 4 in the Scope of Work (Notice to Bidders 6339).

Q4. REMOVAL OF TRAFFIC STRIPE 20 MILES. Is this quantity correct? If so, which lines will be removed? There appears to be 40 MILES of Edge-line and 20 MILES of Skip existing.

A4. The existing edge lines will not have to be removed.