

Call 10 Mill & Overlay approximately 6 miles of SR 305 from Lewisburg to Begin 5-lane, known as State Project MP-2305-17(004) / 305831301 in Desoto County.

Q1. **1.** Can all of the milling be performed before the placement of the 9.5mm? **2.** How long will traffic be allowed to drive on the milled surface?

A1. **1.** Yes, provided the contractor provide paper joints to allow a smooth transition between milled surface and existing pavement. The contractor will be responsible for the maintenance of the paper joints until the surface lift has been placed. **2.** There will not be a time limit for the milled locations on this project.

Q2. In reference to the scope of work Item #6 where it states install (6) inch rumble strips for rumble stripe, will there be a pay item set up for rumble strips?

A2. See the addendum to the project.