

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) hereby certify by digital signature and electronic submission via Bid Express of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 7/20/2016 ADDENDUM NO. _____ DATED _____
 ADDENDUM NO. _____ DATED _____ ADDENDUM NO. _____ DATED _____

Number	Description
1	Revised Bid Items; Amendment EBS Download Required.

TOTAL ADDENDA: 1
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

 Contractor

BY _____
 Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

 President Address

 Secretary Address

 Treasurer Address

The following is my (our) itemized proposal.

MP-2008-07(005)/ 305881301000

Calhoun County(ies)

Mill & Overlay approximately 10 miles of SR 8 from Calhoun City to Chickasaw CL, known as State Project No. MP-2008-07(005) / 305881301 in Calhoun County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	202-B005		50	Square Yard	Removal of Asphalt Pavement, All Depths
0020	202-B033		168	Square Yard	Removal of Concrete Pavement w/ Variable Depth Overlay
0030	202-B076		3,305	Linear Feet	Removal of Traffic Stripe (Cold Plastic Stripe on Bridges)
0040	202-B254		600	Linear Feet	Removal of Guard Rail, Including Rail, Posts & Cable Anchor s
0050	203-G003	(E)	30	Cubic Yard	Excess Excavation, FM, AH
0060	423-A001		14	Mile	Rumble Strips, Ground In
0070	606-B001		400	Linear Feet	Guard Rail, Class A, Type 1
0080	606-D008		4	Each	Guard Rail, Bridge End Section, Type H
0090	606-E002		4	Each	Guard Rail, Terminal End Section, Flared
0100	619-A1002		37	Mile	Temporary Traffic Stripe, Continuous White
0110	619-A2002		13	Mile	Temporary Traffic Stripe, Continuous Yellow
0120	619-A4006		14	Mile	Temporary Traffic Stripe, Skip Yellow
0130	619-A5001		11,800	Linear Feet	Temporary Traffic Stripe, Detail
0140	619-A6001		3,200	Linear Feet	Temporary Traffic Stripe, Legend
0150	619-A6002		150	Square Feet	Temporary Traffic Stripe, Legend
0160	619-F3004		32	Each	Delineators, Guard Rail, White
0170	620-A001		1	Lump Sum	Mobilization
0180	627-L001		1,200	Each	Two-Way Yellow Reflective High Performance Raised Markers
0190	907-304-B009	(GT)	4,210	Ton	Granular Material, Class 3, Group D
0200	907-403-A019	(BA1)	110	Ton	19-mm, ST, Asphalt Pavement
0210	907-403-A022	(BA1)	17,500	Ton	9.5-mm, MT, Asphalt Pavement
0220	907-403-B016	(BA1)	6,300	Ton	9.5-mm, MT, Asphalt Pavement, Leveling
0230	907-403-C009	(BA1)	840	Ton	19-mm, ST, Asphalt Pavement, Trench Widening
0240	907-406-D001		150,850	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0250	907-407-A001	(A2)	23,000	Gallon	Asphalt for Tack Coat
0260	907-413-E001		7,000	Linear Feet	Sawing and Sealing Transverse Joints in Asphalt Pavement
0270	907-618-A001		1	Lump Sum	Maintenance of Traffic
0280	907-618-B001		10	Square Feet	Additional Construction Signs [\$10.00]
0290	907-626-C004		19	Mile	6" Thermoplastic Edge Stripe, Continuous White
0300	907-626-C007		2,800	Linear Feet	6" Thermoplastic Double Drop Edge Stripe, Continuous White
0310	907-626-D003		7	Mile	6" Thermoplastic Traffic Stripe, Skip Yellow
0320	907-626-D005		350	Linear Feet	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	907-626-E004		7	Mile	6" Thermoplastic Traffic Stripe, Continuous Yellow
0340	907-626-G004		6,150	Linear Feet	Thermoplastic Detail Stripe, White
0350	907-626-G005		5,625	Linear Feet	Thermoplastic Detail Stripe, Yellow
0360	907-626-H004		3,200	Linear Feet	Thermoplastic Legend, White
0370	907-626-H005		150	Square Feet	Thermoplastic Legend, White
ALTERNATE GROUP AA NUMBER 1					
0380	907-304-F002	(GT)	50	Ton	Size 610 Crushed Stone Base
ALTERNATE GROUP AA NUMBER 2					
0390	907-304-F003	(GT)	50	Ton	3/4" and Down Crushed Stone Base
ALTERNATE GROUP AA NUMBER 3					
0400	907-304-F004	(GT)	50	Ton	Size 825B Crushed Stone Base