

| Intersection Improvements on US 45A at Tarlton Road, known as Federal Aid Project No. HSIP-0079-01(032) / 106987301 in Lowndes County. |           |  |            |       | Ausbern Construction Company, Inc. | Phillips Contracting Co., Inc. |  |
|--|-----------|--|------------|-------|------------------------------------|--------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,062,166.43   |           |  |            |       | \$2,156,817.88                     | \$2,159,084.00                 |  |
| Ref#   | Item      | Item Description   | Item Qty   | Units | 1                                  | 2                              |  |
| 0010   | 201-A001  | Clearing and Grubbing                                    | 1.000      | LS    | 18,000.00                          | 110,000.00                     |  |
| 0020   | 202-B005  | Removal of Asphalt Pavement, All Depths                  | 328.000    | SY    | 10.00                              | 20.00                          |  |
| 0030   | 202-B024  | Removal of Concrete Median & Island Pavement, All Depths | 12.000     | SY    | 75.00                              | 80.00                          |  |
| 0040   | 202-B025  | Removal of Concrete Paved Ditch                          | 46.000     | SY    | 20.00                              | 40.00                          |  |
| 0050   | 202-B042  | Removal of Flared End Section, All Sizes                 | 1.000      | EA    | 750.00                             | 500.00                         |  |
| 0060   | 202-B057  | Removal of Inlets, All Sizes                             | 3.000      | EA    | 1,500.00                           | 1,000.00                       |  |
| 0070   | 202-B069  | Removal of Sign  | 24.000     | EA    | 85.00                              | 450.00                         |  |
| 0080   | 202-B076  | Removal of Traffic Stripe                                | 14,348.000 | LF    | 1.00                               | 1.00                           |  |
| 0090   | 202-B093  | Removal of Curb & Gutter, All Types                      | 110.000    | LF    | 10.00                              | 20.00                          |  |
| 0100   | 202-B141  | Removal of Edge Drain                                    | 300.000    | LF    | 10.00                              | 20.00                          |  |
| 0110   | 203-A003  | Unclassified Excavation, FM, AH                          | 3,270.000  | CY    | 8.00                               | 8.00                           |  |
| 0120   | 203-EX019 | Borrow Excavation, AH, FME, Class B10                    | 408.000    | CY    | 35.00                              | 20.00                          |  |
| 0130   | 203-G003  | Excess Excavation, FM, AH                                | 1,189.000  | CY    | 8.00                               | 10.00                          |  |
| 0140   | 206-A001  | Structure Excavation                                     | 276.000    | CY    | 15.00                              | 20.00                          |  |
| 0150   | 206-B001  | Select Material for Undercuts, Contractor Furnished, FM  | 11.000     | CY    | 150.00                             | 80.00                          |  |
| 0160   | 209-A004  | Geotextile Stabilization, Type V, Non-Woven              | 12,464.000 | SY    | 3.00                               | 3.00                           |  |
| 0170   | 211-B001  | Topsoil for Slope Treatment, Contractor Furnished        | 3,338.000  | CY    | 20.00                              | 1.00                           |  |
| 0180   | 213-C001  | Superphosphate   | 4.000      | TON   | 600.00                             | 1,000.00                       |  |
| 0190   | 217-A001  | Ditch Liner  | 200.000    | SY    | 1.65                               | 4.00                           |  |
| 0200   | 219-A001  | Watering   | 2.000      | KGAL  | 20.00                              | 20.00                          |  |
| 0210   | 220-A001  | Insect Pest Control                                      | 8.000      | ACRE  | 30.00                              | 30.00                          |  |
| 0220   | 221-A001  | Portland Cement Concrete Paved Ditch                     | 24.000     | CY    | 700.00                             | 500.00                         |  |
| 0230   | 223-A001  | Mowing   | 8.000      | ACRE  | 50.00                              | 50.00                          |  |
| 0240   | 234-A001  | Temporary Silt Fence                                     | 4,000.000  | LF    | 3.25                               | 4.00                           |  |
| 0250   | 239-A001  | Temporary Slope Drains                                   | 75.000     | LF    | 25.00                              | 30.00                          |  |
| 0260   | 423-A001  | Rumble Strips, Ground In                                 | 2.000      | MI    | 450.00                             | 450.00                         |  |

| Intersection Improvements on US 45A at Tarlton Road, known as Federal Aid Project No. HSIP-0079-01(032) / 106987301 in Lowndes County. |           |  |            |       | Ausbern Construction Company, Inc. | Phillips Contracting Co., Inc. |  |
|--|-----------|--|------------|-------|------------------------------------|--------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,062,166.43   |           |  |            |       | \$2,156,817.88                     | \$2,159,084.00                 |  |
| Ref#   | Item      | Item Description   | Item Qty   | Units | 1                                  | 2                              |  |
| 0270   | 503-C007  | Saw Cut, Full Depth  | 744.000    | LF    | 7.00                               | 6.00                           |  |
| 0280   | 602-A001  | Reinforcing Steel  | 2,346.000  | LBS   | 3.00                               | 1.00                           |  |
| 0290   | 603-CA002 | 18" Reinforced Concrete Pipe, Class III                        | 96.000     | LF    | 31.50                              | 40.00                          |  |
| 0300   | 603-CA003 | 24" Reinforced Concrete Pipe, Class III                        | 312.000    | LF    | 46.00                              | 55.00                          |  |
| 0310   | 603-CA004 | 30" Reinforced Concrete Pipe, Class III                        | 8.000      | LF    | 100.00                             | 80.00                          |  |
| 0320   | 603-CB001 | 18" Reinforced Concrete End Section                            | 1.000      | EA    | 800.00                             | 1,000.00                       |  |
| 0330   | 603-SB004 | 24" Branch Connections, Stub into Box Culvert                  | 1.000      | EA    | 4,000.00                           | 1,500.00                       |  |
| 0340   | 604-A001  | Castings   | 79.000     | LBS   | 5.00                               | 5.00                           |  |
| 0350   | 604-B001  | Gratings   | 1,000.000  | LBS   | 6.00                               | 5.00                           |  |
| 0360   | 609-D007  | Combination Concrete Curb and Gutter Type 2 Modified           | 4,873.000  | LF    | 16.05                              | 21.20                          |  |
| 0370   | 616-A003  | Concrete Median and/or Island Pavement, 10-inch                | 416.000    | SY    | 63.80                              | 98.25                          |  |
| 0380   | 619-A1002 | Temporary Traffic Stripe, Continuous White                     | 5.000      | MI    | 850.00                             | 850.00                         |  |
| 0390   | 619-A2002 | Temporary Traffic Stripe, Continuous Yellow                    | 4.000      | MI    | 850.00                             | 850.00                         |  |
| 0400   | 619-A3006 | Temporary Traffic Stripe, Skip White                           | 6.000      | MI    | 850.00                             | 850.00                         |  |
| 0410   | 619-A5001 | Temporary Traffic Stripe, Detail                               | 19,669.000 | LF    | 0.15                               | 0.15                           |  |
| 0420   | 619-A6002 | Temporary Traffic Stripe, Legend                               | 1,745.000  | SF    | 1.00                               | 1.00                           |  |
| 0430   | 619-C6001 | Red-Clear Reflective High Performance Raised Marker            | 1,219.000  | EA    | 4.50                               | 4.50                           |  |
| 0440   | 619-C7001 | Two-Way Yellow Reflective High Performance Raised Marker       | 97.000     | EA    | 4.50                               | 4.50                           |  |
| 0450   | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 158.000    | SF    | 5.00                               | 5.00                           |  |
| 0460   | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More   | 664.000    | SF    | 5.00                               | 5.00                           |  |
| 0470   | 619-F1001 | Concrete Median Barrier, Precast                               | 4,066.000  | LF    | 56.00                              | 45.00                          |  |
| 0480   | 619-F2001 | Remove and Reset Concrete Median Barrier, Precast              | 5,263.000  | LF    | 4.00                               | 15.00                          |  |
| 0490   | 619-G4001 | Barricades, Type III, Single Faced                             | 48.000     | LF    | 12.00                              | 12.00                          |  |
| 0500   | 619-G4005 | Barricades, Type III, Double Faced                             | 108.000    | LF    | 14.00                              | 14.00                          |  |
| 0510   | 619-G5001 | Free Standing Plastic Drums                                    | 97.000     | EA    | 40.00                              | 40.00                          |  |
| 0520   | 619-G7001 | Warning Lights, Type "B"                                       | 8.000      | EA    | 135.00                             | 135.00                         |  |

| Intersection Improvements on US 45A at Tarlton Road, known as Federal Aid Project No. HSIP-0079-01(032) / 106987301 in Lowndes County. |              |   |          |       | Ausbern Construction Company, Inc. | Phillips Contracting Co., Inc. |  |
|--|--------------|---|----------|-------|------------------------------------|--------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,062,166.43   |              |   |          |       | \$2,156,817.88                     | \$2,159,084.00                 |  |
| Ref#   | Item         | Item Description  | Item Qty | Units | 1                                  | 2                              |  |
| 0530   | 619-J1004    | Impact Attenuator, 70 MPH                                     | 2.000    | UNIT  | 5,000.00                           | 5,000.00                       |  |
| 0540   | 619-J2003    | Impact Attenuator, 70 MPH, Replacement Package                | 1.000    | EA    | 2,500.00                           | 2,500.00                       |  |
| 0550   | 620-A001     | Mobilization  | 1.000    | LS    | 165,500.00                         | 150,000.00                     |  |
| 0560   | 627-K001     | Red-Clear Reflective High Performance Raised Markers          | 619.000  | EA    | 4.50                               | 4.50                           |  |
| 0570   | 627-L001     | Two-Way Yellow Reflective High Performance Raised Markers     | 144.000  | EA    | 4.50                               | 4.50                           |  |
| 0580   | 630-A001     | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness     | 88.000   | SF    | 18.00                              | 19.00                          |  |
| 0590   | 630-A002     | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness     | 210.000  | SF    | 20.00                              | 20.00                          |  |
| 0600   | 630-C002     | Steel U-Section Posts, 2.0 to 2.5 lb/ft                       | 45.000   | LF    | 7.00                               | 7.50                           |  |
| 0610   | 630-C004     | Steel U-Section Posts, 3.0 to 3.5 lb/ft                       | 482.000  | LF    | 9.00                               | 8.50                           |  |
| 0620   | 630-D003     | Structural Steel Beams, W6 x 9                                | 224.000  | LF    | 40.00                              | 55.00                          |  |
| 0630   | 630-E001     | Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles         | 247.000  | LBS   | 2.75                               | 2.50                           |  |
| 0640   | 630-E004     | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar       | 97.000   | LBS   | 2.75                               | 2.50                           |  |
| 0650   | 630-F003     | Delineators, Flexible Post Mounted, Crossover, Type I, Green  | 6.000    | EA    | 30.00                              | 45.00                          |  |
| 0660   | 630-F004     | Delineators, Flexible Post Mounted, Crossover, Type I, Yellow | 6.000    | EA    | 30.00                              | 45.00                          |  |
| 0670   | 630-K001     | Welded & Seamless Steel Pipe Posts, 3"                        | 15.000   | LF    | 40.00                              | 40.00                          |  |
| 0680   | 630-K002     | Welded & Seamless Steel Pipe Posts, 3 1/2"                    | 66.000   | LF    | 45.00                              | 45.00                          |  |
| 0690   | 907-216-A001 | Solid Sodding   | 106.000  | SY    | 10.00                              | 6.00                           |  |
| 0700   | 907-225-A001 | Grassing  | 8.000    | ACRE  | 800.00                             | 1,500.00                       |  |
| 0710   | 907-225-B001 | Agricultural Limestone  | 4.000    | TON   | 120.00                             | 90.00                          |  |
| 0720   | 907-225-C001 | Mulch, Vegetative Mulch                                       | 17.000   | TON   | 180.00                             | 200.00                         |  |
| 0730   | 907-226-A001 | Temporary Grassing  | 8.000    | ACRE  | 650.00                             | 850.00                         |  |
| 0740   | 907-234-D001 | Inlet Siltation Guard   | 3.000    | EA    | 485.00                             | 1,000.00                       |  |
| 0750   | 907-237-A002 | Wattles, 12"  | 188.000  | LF    | 3.65                               | 6.00                           |  |
| 0760   | 907-237-A003 | Wattles, 20"  | 828.000  | LF    | 4.85                               | 7.00                           |  |
| 0770   | 907-245-A001 | Triangular Silt Dike  | 200.000  | LF    | 10.00                              | 10.00                          |  |
| 0780   | 907-247-A001 | Temporary Stream Diversion                                    | 1.000    | EA    | 7,500.00                           | 500.00                         |  |

| Intersection Improvements on US 45A at Tarlton Road, known as Federal Aid Project No. HSIP-0079-01(032) / 106987301 in Lowndes County. |               |  |            |       | Ausbern Construction Company, Inc. | Phillips Contracting Co., Inc. |  |
|--|---------------|--|------------|-------|------------------------------------|--------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,062,166.43   |               |  |            |       | \$2,156,817.88                     | \$2,159,084.00                 |  |
| Ref#   | Item          | Item Description   | Item Qty   | Units | 1                                  | 2                              |  |
| 0790   | 907-249-A001  | Riprap for Erosion Control   | 8.000      | TON   | 300.00                             | 75.00                          |  |
| 0800   | 907-304-B010  | Granular Material, Class 3, Group C  | 2,557.000  | TON   | 31.00                              | 23.00                          |  |
| 0810   | 907-403-A022  | 9.5-mm, MT, Asphalt Pavement   | 3,053.000  | TON   | 94.69                              | 92.00                          |  |
| 0820   | 907-403-A024  | 19-mm, MT, Asphalt Pavement  | 2,614.000  | TON   | 92.89                              | 85.00                          |  |
| 0830   | 907-406-D001  | Fine Milling of Bituminous Pavement, All Depths                              | 27,503.000 | SY    | 2.00                               | 2.00                           |  |
| 0840   | 907-407-A001  | Asphalt for Tack Coat  | 2,799.000  | GAL   | 3.25                               | 3.75                           |  |
| 0850   | 907-601-A001  | Class "B" Structural Concrete  | 7.000      | CY    | 3,575.00                           | 3,400.00                       |  |
| 0860   | 907-601-B003  | Class "B" Structural Concrete, Minor Structures                              | 21.000     | CY    | 3,300.00                           | 2,000.00                       |  |
| 0870   | 907-605-H002  | Prefabricated Edge Drain   | 100.000    | LF    | 100.00                             | 70.00                          |  |
| 0880   | 907-605-U002  | 6" Non-perforated Pipe for Underdrains                                       | 1,005.000  | LF    | 15.00                              | 20.00                          |  |
| 0890   | 907-618-A001  | Maintenance of Traffic   | 1.000      | LS    | 75,000.00                          | 65,000.00                      |  |
| 0900   | 907-619-E3001 | Changeable Message Sign  | 2.000      | EA    | 4,850.00                           | 4,850.00                       |  |
| 0910   | 907-626-A004  | 6" Thermoplastic Traffic Stripe, Skip White                                  | 8,080.000  | LF    | 0.60                               | 0.60                           |  |
| 0920   | 907-626-B003  | 6" Thermoplastic Traffic Stripe, Continuous White                            | 2,746.000  | LF    | 0.60                               | 0.60                           |  |
| 0930   | 907-626-C008  | 6" Thermoplastic Edge Stripe, Continuous White                               | 7,010.000  | LF    | 0.60                               | 0.60                           |  |
| 0940   | 907-626-E003  | 6" Thermoplastic Traffic Stripe, Continuous Yellow                           | 1,492.000  | LF    | 0.60                               | 0.60                           |  |
| 0950   | 907-626-F008  | 6" Thermoplastic Edge Stripe, Continuous Yellow                              | 3,777.000  | LF    | 0.60                               | 0.60                           |  |
| 0960   | 907-626-G004  | Thermoplastic Detail Stripe, White   | 11,571.000 | LF    | 0.80                               | 0.80                           |  |
| 0970   | 907-626-G005  | Thermoplastic Detail Stripe, Yellow  | 5,895.000  | LF    | 0.80                               | 0.80                           |  |
| 0980   | 907-626-H004  | Thermoplastic Legend, White  | 48.000     | LF    | 3.00                               | 3.00                           |  |
| 0990   | 907-626-H005  | Thermoplastic Legend, White  | 1,011.000  | SF    | 6.00                               | 6.00                           |  |
| 1000   | 907-630-PP010 | Roadside Directional Signs, Sheet Aluminum, 0.125" Thickness, Ground Mounted | 213.000    | SF    | 20.00                              | 22.00                          |  |
| 1010   | 907-699-A002  | Roadway Construction Stakes  | 1.000      | LS    | 80,000.00                          | 50,000.00                      |  |
| 1020   | 907-304-F002  | Size 610 Crushed Stone Base  | 4,708.000  | TON   | 52.00                              | 60.00                          |  |
| 1030   | 907-304-F003  | 3/4" and Down Crushed Stone Base   | 4,708.000  | TON   |                                    |                                |  |
| 1040   | 907-304-F004  | Size 825B Crushed Stone Base   | 4,708.000  | TON   |                                    |                                |  |