

Reconstruction of SR 43 between Picayune and Henleyfield, known as Federal Aid Project No. HSIP-0032-01(025) / 102186301 in Pearl River County.					Huey P Stockstill LLC	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,762,144.10					\$4,880,764.30	\$5,658,693.42	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-A001	Clearing and Grubbing	1.000	LS	108,000.00	425,000.00	
0020	202-B057	Removal of Inlets, All Sizes	1.000	EA	300.00	650.00	
0030	202-B064	Removal of Pipe, 8" And Above	290.000	LF	11.50	12.00	
0040	202-B078	Removal of Pavement, All Types and Depths	21,582.000	SY	3.50	3.54	
0050	203-A003	Unclassified Excavation, FM, AH	36,093.000	CY	7.00	5.50	
0060	203-EX013	Borrow Excavation, AH, FME, Class B7	66,737.000	CY	13.30	13.15	
0070	206-A001	Structure Excavation	307.000	CY	18.00	9.00	
0080	206-B001	Select Material for Undercuts, Contractor Furnished, FM	50.000	CY	11.00	115.00	
0090	209-A004	Geotextile Stabilization, Type V, Non-Woven	44,195.000	SY	0.75	1.65	
0100	211-A001	Topsoil for Slope Treatment, From Right-of-Way	86,222.000	SY	0.85	0.55	
0110	213-C001	Superphosphate	18.000	TON	420.00	675.00	
0120	217-A001	Ditch Liner	2,065.000	SY	3.00	1.63	
0130	220-A001	Insect Pest Control	18.000	ACRE	30.00	30.00	
0140	223-A001	Mowing	36.000	ACRE	50.00	50.00	
0150	234-A001	Temporary Silt Fence	8,063.000	LF	3.00	12.00	
0160	423-A001	Rumble Strips, Ground In	3.000	MI	1,100.00	380.00	
0170	602-A001	Reinforcing Steel	182.000	LBS	2.00	3.75	
0180	603-CA088	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	56.000	LF	67.00	35.00	
0190	603-CA089	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	492.000	LF	57.00	45.00	
0200	603-CA090	30" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	8.000	LF	142.00	55.00	
0210	603-CA095	24" Reinforced Concrete Pipe, Class IV, Rubber Type Gaskets	156.000	LF	65.00	50.00	
0220	603-CB001	18" Reinforced Concrete End Section	4.000	EA	350.00	650.00	
0230	603-CB002	24" Reinforced Concrete End Section	15.000	EA	430.00	700.00	
0240	603-CB003	30" Reinforced Concrete End Section	1.000	EA	550.00	1,300.00	
0250	603-CE001	22" x 13" Concrete Arch Pipe, Class A III	56.000	LF	73.00	45.00	
0260	603-CE040	51" x 31" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	192.000	LF	100.00	90.00	

Reconstruction of SR 43 between Picayune and Henleyfield, known as Federal Aid Project No. HSIP-0032-01(025) / 102186301 in Pearl River County.					Huey P Stockstill LLC	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,762,144.10					\$4,880,764.30	\$5,658,693.42	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	603-CE045	36" x 23" Concrete Arch Pipe, Class A III, Flexible Plastic Gaskets	100.000	LF	81.00	62.00	
0280	603-CF003	36" x 23" Concrete Arch Pipe End Section	3.000	EA	580.00	750.00	
0290	603-CF005	51" x 31" Concrete Arch Pipe End Section	4.000	EA	1,600.00	1,425.00	
0300	604-B001	Gratings	397.000	LBS	6.75	3.00	
0310	609-D002	Combination Concrete Curb and Gutter Type 2	730.000	LF	17.00	23.00	
0320	616-A001	Concrete Median and/or Island Pavement, 4-inch	220.000	SY	63.00	43.00	
0330	616-A003	Concrete Median and/or Island Pavement, 10-inch	17.000	SY	107.00	170.00	
0340	619-A1003	Temporary Traffic Stripe, Continuous White, Paint	49,360.000	LF	0.25	0.30	
0350	619-A2003	Temporary Traffic Stripe, Continuous Yellow, Paint	2,160.000	LF	0.25	0.30	
0360	619-A4002	Temporary Traffic Stripe, Skip Yellow, Paint	25,076.000	LF	0.25	0.30	
0370	619-A5002	Temporary Traffic Stripe, Detail, Paint	2,806.000	LF	0.50	0.55	
0380	619-A6001	Temporary Traffic Stripe, Legend	640.000	LF	2.00	2.20	
0390	619-C7001	Two-Way Yellow Reflective High Performance Raised Marker	528.000	EA	5.50	5.50	
0400	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	52.000	SF	15.00	6.50	
0410	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	983.000	SF	15.00	6.50	
0420	619-G4001	Barricades, Type III, Single Faced	564.000	LF	28.00	15.00	
0430	619-G4004	Barricades, Type III, Single Faced, Permanent, Red/White	24.000	LF	50.00	47.00	
0440	619-G4005	Barricades, Type III, Double Faced	96.000	LF	30.00	15.00	
0450	619-G5001	Free Standing Plastic Drums	222.000	EA	57.00	40.00	
0460	620-A001	Mobilization	1.000	LS	268,000.00	425,000.00	
0470	627-J001	Two-Way Clear Reflective High Performance Raised Markers	234.000	EA	5.50	5.40	
0480	627-K001	Red-Clear Reflective High Performance Raised Markers	12.000	EA	5.50	5.40	
0490	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	654.000	EA	5.50	5.40	
0500	630-A001	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness	137.000	SF	21.00	20.00	
0510	630-A002	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	96.000	SF	22.00	21.00	
0520	630-C001	Steel U-Section Posts, 2.0 lb/ft	9.000	LF	9.00	8.50	

Reconstruction of SR 43 between Picayune and Henleyfield, known as Federal Aid Project No. HSIP-0032-01(025) / 102186301 in Pearl River County.					Huey P Stockstill LLC	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,762,144.10					\$4,880,764.30	\$5,658,693.42	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	630-C003	Steel U-Section Posts, 3.0 lb/ft	268.000	LF	12.00	112.00	
0540	630-E004	Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar	18.000	LBS	2.00	2.25	
0550	630-K001	Welded & Seamless Steel Pipe Posts, 3"	17.000	LF	51.00	55.00	
0560	630-K003	Welded & Seamless Steel Pipe Posts, 4"	31.000	LF	61.00	65.00	
0570	815-A009	Loose Riprap, Size 300	256.000	TON	76.00	95.00	
0580	907-225-A001	Grassing	36.000	ACRE	1,300.00	975.00	
0590	907-225-B001	Agricultural Limestone	18.000	TON	150.00	65.00	
0600	907-225-C001	Mulch, Vegetative Mulch	71.000	TON	205.00	220.00	
0610	907-226-A001	Temporary Grassing	36.000	ACRE	700.00	920.00	
0620	907-234-D001	Inlet Siltation Guard	1.000	EA	600.00	350.00	
0630	907-236-PP001	Silt Basin, Per Plans	4.000	EA	2,500.00	2,500.00	
0640	907-237-A003	Wattles, 20"	1,750.000	LF	6.00	4.25	
0650	907-246-A002	Sandbags	350.000	EA	4.00	5.50	
0660	907-249-A001	Riprap for Erosion Control	100.000	TON	60.00	95.00	
0680	907-403-A022	9.5-mm, MT, Asphalt Pavement	3,938.000	TON	78.00	93.20	
0690	907-403-A023	12.5-mm, MT, Asphalt Pavement	5,211.000	TON	69.00	83.93	
0700	907-403-A024	19-mm, MT, Asphalt Pavement	5,064.000	TON	62.00	75.21	
0710	907-403-A019	19-mm, ST, Asphalt Pavement	6,077.000	TON	57.00	69.76	
0720	907-403-C011	19-mm, MT, Asphalt Pavement, Trench Widening	227.000	TON	135.00	163.50	
0730	907-406-A001	Cold Milling of Bituminous Pavement, All Depths	1,600.000	SY	8.30	9.27	
0740	907-407-A001	Asphalt for Tack Coat	9,310.000	GAL	4.00	3.60	
0750	907-601-B003	Class "B" Structural Concrete, Minor Structures	8.000	CY	1,400.00	1,450.00	
0760	907-603-ALT01	18" Type A Alternate Pipe	1,336.000	LF	39.00	26.00	
0770	907-603-ALT02	24" Type A Alternate Pipe	96.000	LF	53.00	35.00	
0780	907-617-A001	Right-of-Way Marker	83.000	EA	250.00	275.00	
0790	907-618-A001	Maintenance of Traffic	1.000	LS	50,000.00	85,000.00	

Reconstruction of SR 43 between Picayune and Henleyfield, known as Federal Aid Project No. HSIP-0032-01(025) / 102186301 in Pearl River County.					Huey P Stockstill LLC	T. L. Wallace Construction, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,762,144.10					\$4,880,764.30	\$5,658,693.42	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0800	907-622-A001	Engineer's Field Office Building, Type 2	1.000	EA	26,000.00	45,000.00	
0810	907-626-B003	6" Thermoplastic Traffic Stripe, Continuous White	143.000	LF	1.00	1.10	
0820	907-626-C003	6" Thermoplastic Double Drop Edge Stripe, Continuous White	5.000	MI	3,100.00	3,250.00	
0830	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	3.000	MI	1,600.00	1,600.00	
0840	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	3.000	MI	3,100.00	3,250.00	
0850	907-626-G004	Thermoplastic Detail Stripe, White	3,075.000	LF	1.00	1.10	
0860	907-626-G005	Thermoplastic Detail Stripe, Yellow	741.000	LF	1.00	1.10	
0870	907-626-H004	Thermoplastic Legend, White	425.000	LF	1.50	1.70	
0880	907-699-A002	Roadway Construction Stakes	1.000	LS	48,000.00	85,000.00	
0890	907-815-F001	Sediment Control Stone	100.000	TON	45.00	85.00	
0900	907-304-F003	3/4" and Down Crushed Stone Base	29,500.000	TON			
0910	907-304-F004	Size 825B Crushed Stone Base	29,500.000	TON			
0920	907-304-F002	Size 610 Crushed Stone Base	29,500.000	TON	38.00	35.00	