

**Call 06 Replace Bridge 15.4 on SR 309 Between SR 4 and US 78, known as State Project No. EXB-0914-00(009) / 100299303 in Marshall County.**

Q1. Can the test piles be spliced in the middle of the driving operation? (Two 70' pieces spliced after the first 70' is driven)

A1. Yes

Q2. Plans show a total of 4 test piles: 2- 14x89 and 2-36" Pipe Piles. The bid quantities in the proposal only show 3 test piles: 2- 14x89 and 1-36" Pipe Pile. How is the second pipe pile to be paid?

A2. See the addendum to the project.