

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | L & A Contracting Company | Dement Construction Company, LLC | W. G. Yates & Son Construction Company |
|--|-----------|--|-------------|-------|---------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$33,957,797.43 | \$33,998,295.75 | \$34,402,695.85 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0010 | 201-A001 | Clearing and Grubbing | 1.000 | LS | 1,500,000.00 | 100,000.00 | 750,000.00 |
| 0020 | 201-B001 | Clearing and Grubbing | 16.000 | ACRE | 4,000.00 | 3,150.00 | 7,500.00 |
| 0030 | 202-A001 | Removal of Obstructions | 1.000 | LS | 800,000.00 | 200,000.00 | 750,000.00 |
| 0040 | 202-B018 | Removal of Concrete Driveways, All Depths | 951.000 | SY | 41.66 | 10.00 | 18.00 |
| 0050 | 202-B024 | Removal of Concrete Median & Island Pavement, All Depths | 460.000 | SY | 22.67 | 10.00 | 18.00 |
| 0060 | 202-B064 | Removal of Pipe, 8" And Above | 596.000 | LF | 38.00 | 20.00 | 20.00 |
| 0070 | 202-B069 | Removal of Sign | 46.000 | EA | 76.50 | 200.00 | 75.00 |
| 0080 | 202-B093 | Removal of Curb & Gutter, All Types | 1,306.000 | LF | 20.23 | 7.00 | 15.00 |
| 0090 | 202-B097 | Removal of Concrete Overlaid w/ Asphalt Pavement, All Depths | 28,393.000 | SY | 29.00 | 7.50 | 8.50 |
| 0100 | 202-B102 | Removal of Guard Rail | 1,153.000 | LF | 5.10 | 5.00 | 5.00 |
| 0110 | 203-A003 | Unclassified Excavation, FM, AH | 91,267.000 | CY | 6.28 | 4.25 | 5.00 |
| 0120 | 203-EX017 | Borrow Excavation, AH, FME, Class B9 | 66,461.000 | CY | 9.80 | 8.00 | 9.00 |
| 0130 | 203-G003 | Excess Excavation, FM, AH | 100,121.000 | CY | 8.16 | 6.00 | 5.00 |
| 0140 | 206-A001 | Structure Excavation | 578.000 | CY | 3.71 | 15.00 | 30.00 |
| 0150 | 206-B001 | Select Material for Undercuts, Contractor Furnished, FM | 39.000 | CY | 65.36 | 45.00 | 100.00 |
| 0160 | 209-A004 | Geotextile Stabilization, Type V, Non-Woven | 28,811.000 | SY | 2.54 | 2.00 | 3.25 |
| 0170 | 211-B001 | Topsoil for Slope Treatment, Contractor Furnished | 8,977.000 | CY | 47.06 | 10.00 | 12.50 |
| 0180 | 213-C001 | Superphosphate | 11.000 | TON | 765.00 | 750.00 | 760.00 |
| 0190 | 217-A001 | Ditch Liner | 669.000 | SY | 2.55 | 2.50 | 2.55 |
| 0200 | 219-A001 | Watering | 12.000 | KGAL | 20.00 | 20.00 | 20.00 |
| 0210 | 220-A001 | Insect Pest Control | 11.000 | ACRE | 30.00 | 30.00 | 30.00 |
| 0220 | 221-A001 | Portland Cement Concrete Paved Ditch | 78.000 | CY | 561.00 | 400.00 | 475.00 |
| 0230 | 223-A001 | Mowing | 44.000 | ACRE | 50.00 | 50.00 | 50.00 |
| 0240 | 224-A001 | Soil Reinforcing Mat | 3,594.000 | SY | 3.57 | 3.50 | 3.55 |
| 0250 | 234-A001 | Temporary Silt Fence | 31,050.000 | LF | 3.06 | 3.00 | 3.25 |
| 0260 | 239-A001 | Temporary Slope Drains | 1,150.000 | LF | 7.14 | 7.00 | 8.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | L & A Contracting Company | Dement Construction Company, LLC | W. G. Yates & Son Construction Company |
|--|-----------|---|-----------|-------|---------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$33,957,797.43 | \$33,998,295.75 | \$34,402,695.85 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0270 | 423-A001 | Rumble Strips, Ground In | 2.000 | MI | 408.00 | 400.00 | 1,200.00 |
| 0280 | 502-A001 | Reinforced Cement Concrete Bridge End Pavement | 202.000 | SY | 235.00 | 200.00 | 250.00 |
| 0290 | 602-A001 | Reinforcing Steel | 869.000 | LBS | 1.90 | 1.00 | 1.50 |
| 0300 | 603-A040 | 48" Steel Pipe, Jacked or Bored, Wall Thickness 0.625" | 88.000 | LF | 1,020.00 | 785.00 | 875.00 |
| 0310 | 603-CA004 | 30" Reinforced Concrete Pipe, Class III | 88.000 | LF | 78.84 | 54.00 | 90.00 |
| 0320 | 603-CB002 | 24" Reinforced Concrete End Section | 2.000 | EA | 1,570.00 | 1,500.00 | 1,500.00 |
| 0330 | 603-CB003 | 30" Reinforced Concrete End Section | 2.000 | EA | 1,649.00 | 1,500.00 | 2,400.00 |
| 0340 | 603-CE006 | 58" x 36" Concrete Arch Pipe, Class A III | 288.000 | LF | 154.70 | 120.00 | 170.00 |
| 0350 | 603-CF002 | 29" x 18" Concrete Arch Pipe End Section | 4.000 | EA | 1,592.26 | 1,500.00 | 2,150.00 |
| 0360 | 603-CF006 | 58" x 36" Concrete Arch Pipe End Section | 2.000 | EA | 2,665.76 | 2,500.00 | 5,750.00 |
| 0370 | 606-B001 | Guard Rail, Class A, Type 1 | 325.000 | LF | 18.36 | 18.00 | 18.25 |
| 0380 | 606-D012 | Guard Rail, Bridge End Section, Type 1 | 4.000 | EA | 1,938.00 | 1,900.00 | 1,925.00 |
| 0390 | 606-E002 | Guard Rail, Terminal End Section, Flared | 4.000 | EA | 2,295.00 | 2,250.00 | 2,300.00 |
| 0400 | 609-D007 | Combination Concrete Curb and Gutter Type 2 Modified | 1,475.000 | LF | 30.60 | 30.00 | 23.00 |
| 0410 | 609-D008 | Combination Concrete Curb and Gutter Type 3A | 76.000 | LF | 51.00 | 35.00 | 33.00 |
| 0420 | 614-A001 | Concrete Driveway, Without Reinforcement | 357.000 | SY | 61.20 | 15.00 | 85.00 |
| 0430 | 615-A018 | Concrete Bridge End Barrier, 33.5" | 40.000 | LF | 43.41 | 90.00 | 38.00 |
| 0440 | 616-A001 | Concrete Median and/or Island Pavement, 4-inch | 410.000 | SY | 43.35 | 40.00 | 45.00 |
| 0450 | 616-A003 | Concrete Median and/or Island Pavement, 10-inch | 70.000 | SY | 102.00 | 100.00 | 86.00 |
| 0460 | 619-A1002 | Temporary Traffic Stripe, Continuous White | 3.000 | MI | 612.00 | 600.00 | 610.00 |
| 0470 | 619-A1007 | Temporary Traffic Stripe, Continuous White, Type 1 Tape | 6,644.000 | LF | 1.79 | 1.75 | 1.80 |
| 0480 | 619-A2002 | Temporary Traffic Stripe, Continuous Yellow | 1.000 | MI | 612.00 | 600.00 | 610.00 |
| 0490 | 619-A4004 | Temporary Traffic Stripe, Skip Yellow, Type 1 Tape | 3,322.000 | LF | 1.28 | 1.25 | 1.30 |
| 0500 | 619-A4006 | Temporary Traffic Stripe, Skip Yellow | 2.000 | MI | 612.00 | 600.00 | 610.00 |
| 0510 | 619-A5001 | Temporary Traffic Stripe, Detail | 4,112.000 | LF | 0.20 | 0.20 | 0.20 |
| 0520 | 619-A6001 | Temporary Traffic Stripe, Legend | 191.000 | LF | 1.02 | 1.00 | 1.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | L & A Contracting Company | Dement Construction Company, LLC | W. G. Yates & Son Construction Company |
|--|---------------|--|------------|-------|---------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$33,957,797.43 | \$33,998,295.75 | \$34,402,695.85 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0530 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 32.000 | SF | 8.42 | 8.00 | 8.50 |
| 0540 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 823.000 | SF | 8.42 | 8.00 | 8.50 |
| 0550 | 619-D3001 | Remove and Reset Signs, All Sizes | 59.000 | EA | 229.50 | 250.00 | 230.00 |
| 0560 | 619-G4001 | Barricades, Type III, Single Faced | 432.000 | LF | 12.75 | 18.00 | 13.00 |
| 0570 | 619-G4005 | Barricades, Type III, Double Faced | 54.000 | LF | 14.28 | 22.00 | 15.00 |
| 0580 | 619-G5001 | Free Standing Plastic Drums | 38.000 | EA | 41.82 | 75.00 | 42.00 |
| 0590 | 619-G7001 | Warning Lights, Type "B" | 6.000 | EA | 158.10 | 250.00 | 160.00 |
| 0600 | 620-A001 | Mobilization | 1.000 | LS | 5,500,000.00 | 2,993,000.00 | 1,000,000.00 |
| 0610 | 621-A001 | Field Laboratory | 1.000 | EA | 95,000.00 | 25,000.00 | 40,000.00 |
| 0620 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 214.000 | EA | 5.10 | 5.00 | 5.00 |
| 0630 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 61.000 | SF | 19.38 | 19.00 | 19.25 |
| 0640 | 630-A002 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 185.000 | SF | 20.40 | 20.00 | 20.00 |
| 0650 | 630-E004 | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar | 69.000 | LBS | 2.55 | 2.50 | 2.55 |
| 0660 | 630-F001 | Delineators, Guard Rail, White | 22.000 | EA | 18.36 | 18.00 | 18.25 |
| 0670 | 630-G001 | Type 3 Object Markers, OM-3R, Post Mounted | 2.000 | EA | 76.50 | 75.00 | 76.00 |
| 0680 | 630-G003 | Type 3 Object Markers, OM-3L, Post Mounted | 2.000 | EA | 76.50 | 75.00 | 76.00 |
| 0690 | 630-K002 | Welded & Seamless Steel Pipe Posts, 3 1/2" | 55.000 | LF | 40.80 | 40.00 | 41.00 |
| 0700 | 815-A009 | Loose Riprap, Size 300 | 4,500.000 | TON | 41.38 | 48.50 | 55.00 |
| 0710 | 815-E001 | Geotextile under Riprap | 4,253.000 | SY | 2.35 | 2.00 | 4.00 |
| 0720 | 907-203-EX002 | Borrow Excavation, AH, FME, Class B9-10 Modified | 51,400.000 | CY | 15.00 | 8.00 | 9.00 |
| 0730 | 907-216-A001 | Solid Sodding | 582.000 | SY | 5.10 | 5.00 | 5.00 |
| 0740 | 907-225-A001 | Grassing | 22.000 | ACRE | 918.00 | 900.00 | 910.00 |
| 0750 | 907-225-B001 | Agricultural Limestone | 11.000 | TON | 102.00 | 100.00 | 100.00 |
| 0760 | 907-225-C001 | Mulch, Vegetative Mulch | 45.000 | TON | 255.00 | 250.00 | 255.00 |
| 0770 | 907-226-A001 | Temporary Grassing | 22.000 | ACRE | 816.00 | 800.00 | 810.00 |
| 0780 | 907-237-A003 | Wattles, 20" | 30,250.000 | LF | 4.08 | 4.00 | 4.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | L & A Contracting Company | Dement Construction Company, LLC | W. G. Yates & Son Construction Company |
|--|---------------|--|------------|-------|---------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$33,957,797.43 | \$33,998,295.75 | \$34,402,695.85 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 0790 | 907-245-A001 | Triangular Silt Dike | 760.000 | LF | 7.14 | 7.00 | 7.00 |
| 0800 | 907-246-A001 | Sandbags | 3,800.000 | LF | 5.10 | 5.00 | 5.00 |
| 0810 | 907-249-A001 | Riprap for Erosion Control | 1,420.000 | TON | 41.56 | 48.00 | 56.00 |
| 0820 | 907-249-B001 | Remove and Reset Riprap | 710.000 | CY | 18.63 | 15.00 | 30.00 |
| 0830 | 907-304-B009 | Granular Material, Class 3, Group D | 17,800.000 | TON | 13.48 | 20.00 | 21.00 |
| 0840 | 907-304-F002 | Size 610 Crushed Stone Base | 1,750.000 | TON | 40.51 | 46.00 | 45.00 |
| 0850 | 907-310-B001 | Size III Stabilizer Aggregate, Coarse | 3,300.000 | TON | 47.84 | 42.00 | 45.00 |
| 0860 | 907-403-A017 | 9.5-mm, ST, Asphalt Pavement | 277.000 | TON | 96.90 | 95.00 | 100.00 |
| 0870 | 907-403-A018 | 12.5-mm, ST, Asphalt Pavement | 481.000 | TON | 112.20 | 110.00 | 115.00 |
| 0880 | 907-403-A019 | 19-mm, ST, Asphalt Pavement | 2,673.000 | TON | 98.94 | 97.00 | 100.00 |
| 0890 | 907-403-A022 | 9.5-mm, MT, Asphalt Pavement | 2,284.000 | TON | 102.00 | 100.00 | 105.00 |
| 0900 | 907-403-A023 | 12.5-mm, MT, Asphalt Pavement | 2,483.000 | TON | 93.33 | 91.50 | 97.00 |
| 0910 | 907-403-A024 | 19-mm, MT, Asphalt Pavement | 2,525.000 | TON | 91.80 | 90.00 | 95.00 |
| 0920 | 907-403-B013 | 12.5-mm, ST, Asphalt Pavement, Leveling | 66.000 | TON | 112.70 | 110.00 | 115.00 |
| 0930 | 907-403-B017 | 12.5-mm, MT, Asphalt Pavement, Leveling | 617.000 | TON | 93.33 | 91.50 | 97.00 |
| 0940 | 907-403-C011 | 19-mm, MT, Asphalt Pavement, Trench Widening | 33.000 | TON | 255.00 | 250.00 | 265.00 |
| 0950 | 907-406-A001 | Cold Milling of Bituminous Pavement, All Depths | 5,729.000 | SY | 16.51 | 5.00 | 2.60 |
| 0960 | 907-407-A001 | Asphalt for Tack Coat | 3,826.000 | GAL | 2.81 | 2.75 | 3.00 |
| 0970 | 907-413-E001 | Sawing and Sealing Transverse Joints in Asphalt Pavement | 100.000 | LF | 20.40 | 20.00 | 20.00 |
| 0980 | 907-601-B003 | Class "B" Structural Concrete, Minor Structures | 12.000 | CY | 556.62 | 1,000.00 | 1,000.00 |
| 0990 | 907-603-ALT01 | 18" Type A Alternate Pipe | 444.000 | LF | 37.55 | 35.00 | 40.00 |
| 1000 | 907-603-ALT02 | 24" Type A Alternate Pipe | 240.000 | LF | 48.60 | 48.00 | 50.00 |
| 1010 | 907-603-ALT03 | 30" Type A Alternate Pipe | 112.000 | LF | 50.49 | 60.00 | 70.00 |
| 1020 | 907-603-ALT12 | 36" x 23" Type A Alternate Pipe | 196.000 | LF | 58.96 | 73.00 | 85.00 |
| 1030 | 907-603-ALT15 | 29" x 18" Type A Alternate Pipe | 176.000 | LF | 54.82 | 62.00 | 65.00 |
| 1040 | 907-617-A001 | Right-of-Way Marker | 45.000 | EA | 127.05 | 190.00 | 210.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | L & A Contracting Company | Dement Construction Company, LLC | W. G. Yates & Son Construction Company |
|--|--------------|--|---------------|-------|---------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$33,957,797.43 | \$33,998,295.75 | \$34,402,695.85 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 1050 | 907-618-A001 | Maintenance of Traffic | 1.000 | LS | 69,200.00 | 100,000.00 | 250,000.00 |
| 1060 | 907-626-C003 | 6" Thermoplastic Double Drop Edge Stripe, Continuous White | 4.000 | MI | 3,060.00 | 2,600.00 | 2,650.00 |
| 1070 | 907-626-D006 | 6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow | 2.000 | MI | 1,224.00 | 900.00 | 910.00 |
| 1080 | 907-626-E006 | 6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow | 1.000 | MI | 1,224.00 | 2,600.00 | 2,650.00 |
| 1090 | 907-626-G004 | Thermoplastic Detail Stripe, White | 4,637.000 | LF | 0.82 | 0.80 | 0.80 |
| 1100 | 907-626-H004 | Thermoplastic Legend, White | 316.000 | LF | 4.08 | 2.00 | 2.00 |
| 1110 | 907-626-H005 | Thermoplastic Legend, White | 39.000 | SF | 0.26 | 10.00 | 10.00 |
| 1120 | 907-630-C001 | Steel U-Section Posts, 2.0 lb/ft | 28.000 | LF | 7.65 | 7.50 | 8.00 |
| 1130 | 907-630-C003 | Steel U-Section Posts, 3.0 lb/ft | 428.000 | LF | 8.67 | 8.50 | 8.60 |
| 1140 | 907-699-A002 | Roadway Construction Stakes | 1.000 | LS | 400,000.00 | 300,000.00 | 400,000.00 |
| 1150 | 907-815-F001 | Sediment Control Stone | 59.000 | TON | 44.39 | 57.00 | 55.00 |
| 1160 | 907-906001 | Trainees | 1,040.000 | HRS | 5.00 | 5.00 | 5.00 |
| 1170 | 907-304-F002 | Size 610 Crushed Stone Base | 12,200.000 | TON | 44.28 | 45.00 | 45.00 |
| 1180 | 907-304-F003 | 3/4" and Down Crushed Stone Base | 12,200.000 | TON | | | |
| 1190 | 907-304-F004 | Size 825B Crushed Stone Base | 12,200.000 | TON | | | |
| 1200 | 501-K001 | Transverse Grooving | 14,756.000 | SY | 2.19 | 2.15 | 2.50 |
| 1210 | 803-B002 | Conventional Static Pile Load Test | 1.000 | EA | 5,000.00 | 5,000.00 | 5,000.00 |
| 1220 | 803-D007 | HP 14 x 89 Steel Piling | 1,485.000 | LF | 53.30 | 50.00 | 75.00 |
| 1230 | 803-D008 | HP 16 x 121 Steel Piling | 1,540.000 | LF | 83.00 | 84.00 | 105.00 |
| 1240 | 803-I003 | PDA Test Pile, HP Steel Pile | 4.000 | EA | 12,760.00 | 6,000.00 | 8,500.00 |
| 1250 | 803-J001 | Pile Restrike | 2.000 | EA | 3,130.00 | 1,500.00 | 1,000.00 |
| 1260 | 803-N001 | Exploration | 560.000 | LF | 12.00 | 200.00 | 1.00 |
| 1270 | 803-O018 | Permanent Casing, 72" Diameter | 2,365.000 | LF | 318.24 | 300.00 | 325.00 |
| 1280 | 803-O024 | Permanent Casing, 102" Diameter | 960.000 | LF | 420.24 | 500.00 | 510.00 |
| 1290 | 805-A001 | Reinforcement | 1,616,359.000 | LBS | 0.95 | 0.85 | 0.80 |
| 1300 | 813-A002 | Concrete Railing, 32" | 6,644.000 | LF | 43.41 | 65.00 | 38.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | L & A Contracting Company | Dement Construction Company, LLC | W. G. Yates & Son Construction Company |
|--|--------------|--|---------------|-------|---------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$33,957,797.43 | \$33,998,295.75 | \$34,402,695.85 |
| Ref# | Item | Item Description | Item Qty | Units | 1 | 2 | 3 |
| 1310 | 815-A009 | Loose Riprap, Size 300 | 1,887.000 | TON | 40.68 | 45.00 | 55.00 |
| 1320 | 815-E001 | Geotextile under Riprap | 1,649.000 | SY | 5.16 | 2.00 | 4.00 |
| 1330 | 907-803-K001 | Drilled Shaft, 48" Diameter | 330.000 | LF | 157.90 | 500.00 | 800.00 |
| 1340 | 907-803-K010 | Drilled Shaft, 72" Diameter | 4,230.000 | LF | 417.90 | 1,200.00 | 940.00 |
| 1350 | 907-803-K013 | Drilled Shaft, 102" Diameter | 1,740.000 | LF | 462.53 | 2,000.00 | 1,875.00 |
| 1360 | 907-803-L006 | Test Shaft, 72" Diameter | 1.000 | EA | 239,010.00 | 300,000.00 | 300,000.00 |
| 1370 | 907-803-M011 | Trial Shaft, 102" Diameter | 172.000 | LF | 1,900.00 | 2,500.00 | 2,100.00 |
| 1380 | 907-804-A018 | Bridge Concrete, Substructure, Class AA | 2,480.000 | CY | 350.00 | 500.00 | 625.00 |
| 1390 | 907-804-A019 | Bridge Concrete, Superstructure, Class AA | 4,366.000 | CY | 693.50 | 675.00 | 675.00 |
| 1400 | 907-804-C010 | 125' Prestressed Concrete Beam, Type BT-72 | 11,934.000 | LF | 160.00 | 160.00 | 185.00 |
| 1410 | 907-804-C016 | 40' Prestressed Concrete Beam, Type I+2 | 239.000 | LF | 82.17 | 85.00 | 100.00 |
| 1420 | 907-804-C019 | 60' Prestressed Concrete Beam, Type II+2 | 1,782.000 | LF | 102.15 | 100.00 | 115.00 |
| 1430 | 907-804-C030 | 80' Prestressed Concrete Beam, Type III | 479.000 | LF | 114.34 | 85.00 | 135.00 |
| 1440 | 907-810-A001 | Structural Steel, A 709, Grade 50W | 3,137,110.000 | LBS | 1.50 | 1.45 | 1.80 |
| 1450 | 907-810-A002 | Structural Steel, A 709, Grade HPS 70W | 260,441.000 | LBS | 1.50 | 1.45 | 1.80 |
| 1460 | 907-811-D001 | Disc Bearing Device | 20.000 | EA | 5,054.43 | 5,000.00 | 7,000.00 |
| 1470 | 907-822-A007 | 8 1/8" Neoprene Expansion Joint | 149.000 | LF | 322.21 | 750.00 | 1,000.00 |
| 1480 | 907-822-A008 | 12 1/4" Neoprene Expansion Joint | 100.000 | LF | 494.69 | 1,250.00 | 1,350.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | Tanner Construction Company, Inc. | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Joe McGee Construction Company, Inc. |
|--|-----------|--|-------------|-------|-----------------------------------|--|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$34,900,478.80 | \$34,977,607.77 | \$36,381,906.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0010 | 201-A001 | Clearing and Grubbing | 1.000 | LS | 1,135,000.00 | 500,000.00 | 2,550,000.00 |
| 0020 | 201-B001 | Clearing and Grubbing | 16.000 | ACRE | 100.00 | 6,000.00 | 2,860.00 |
| 0030 | 202-A001 | Removal of Obstructions | 1.000 | LS | 250,000.00 | 1,000,000.00 | 825,000.00 |
| 0040 | 202-B018 | Removal of Concrete Driveways, All Depths | 951.000 | SY | 8.00 | 10.00 | 7.35 |
| 0050 | 202-B024 | Removal of Concrete Median & Island Pavement, All Depths | 460.000 | SY | 8.00 | 10.00 | 8.50 |
| 0060 | 202-B064 | Removal of Pipe, 8" And Above | 596.000 | LF | 10.00 | 10.00 | 13.00 |
| 0070 | 202-B069 | Removal of Sign | 46.000 | EA | 75.00 | 75.00 | 95.00 |
| 0080 | 202-B093 | Removal of Curb & Gutter, All Types | 1,306.000 | LF | 8.65 | 6.00 | 9.80 |
| 0090 | 202-B097 | Removal of Concrete Overlaid w/ Asphalt Pavement, All Depths | 28,393.000 | SY | 7.60 | 10.00 | 12.00 |
| 0100 | 202-B102 | Removal of Guard Rail | 1,153.000 | LF | 4.90 | 5.00 | 6.00 |
| 0110 | 203-A003 | Unclassified Excavation, FM, AH | 91,267.000 | CY | 4.65 | 5.00 | 4.95 |
| 0120 | 203-EX017 | Borrow Excavation, AH, FME, Class B9 | 66,461.000 | CY | 8.40 | 9.00 | 8.65 |
| 0130 | 203-G003 | Excess Excavation, FM, AH | 100,121.000 | CY | 5.10 | 6.25 | 7.65 |
| 0140 | 206-A001 | Structure Excavation | 578.000 | CY | 12.25 | 10.00 | 6.00 |
| 0150 | 206-B001 | Select Material for Undercuts, Contractor Furnished, FM | 39.000 | CY | 44.50 | 50.00 | 52.00 |
| 0160 | 209-A004 | Geotextile Stabilization, Type V, Non-Woven | 28,811.000 | SY | 1.75 | 2.50 | 2.15 |
| 0170 | 211-B001 | Topsoil for Slope Treatment, Contractor Furnished | 8,977.000 | CY | 0.10 | 9.00 | 7.00 |
| 0180 | 213-C001 | Superphosphate | 11.000 | TON | 750.00 | 750.00 | 725.00 |
| 0190 | 217-A001 | Ditch Liner | 669.000 | SY | 3.50 | 2.50 | 3.15 |
| 0200 | 219-A001 | Watering | 12.000 | KGAL | 20.00 | 20.00 | 20.00 |
| 0210 | 220-A001 | Insect Pest Control | 11.000 | ACRE | 30.00 | 30.00 | 30.00 |
| 0220 | 221-A001 | Portland Cement Concrete Paved Ditch | 78.000 | CY | 550.00 | 465.00 | 600.00 |
| 0230 | 223-A001 | Mowing | 44.000 | ACRE | 50.00 | 50.00 | 50.00 |
| 0240 | 224-A001 | Soil Reinforcing Mat | 3,594.000 | SY | 3.50 | 3.50 | 5.00 |
| 0250 | 234-A001 | Temporary Silt Fence | 31,050.000 | LF | 3.00 | 3.00 | 4.00 |
| 0260 | 239-A001 | Temporary Slope Drains | 1,150.000 | LF | 7.00 | 7.00 | 9.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | Tanner Construction Company, Inc. | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Joe McGee Construction Company, Inc. |
|--|-----------|---|-----------|-------|-----------------------------------|--|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$34,900,478.80 | \$34,977,607.77 | \$36,381,906.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0270 | 423-A001 | Rumble Strips, Ground In | 2.000 | MI | 400.00 | 1,000.00 | 420.00 |
| 0280 | 502-A001 | Reinforced Cement Concrete Bridge End Pavement | 202.000 | SY | 260.00 | 235.00 | 312.00 |
| 0290 | 602-A001 | Reinforcing Steel | 869.000 | LBS | 2.55 | 1.25 | 1.25 |
| 0300 | 603-A040 | 48" Steel Pipe, Jacked or Bored, Wall Thickness 0.625" | 88.000 | LF | 845.00 | 1,050.00 | 985.00 |
| 0310 | 603-CA004 | 30" Reinforced Concrete Pipe, Class III | 88.000 | LF | 92.00 | 56.28 | 50.00 |
| 0320 | 603-CB002 | 24" Reinforced Concrete End Section | 2.000 | EA | 1,050.00 | 980.00 | 790.00 |
| 0330 | 603-CB003 | 30" Reinforced Concrete End Section | 2.000 | EA | 1,165.00 | 1,120.00 | 915.00 |
| 0340 | 603-CE006 | 58" x 36" Concrete Arch Pipe, Class A III | 288.000 | LF | 120.00 | 159.30 | 113.00 |
| 0350 | 603-CF002 | 29" x 18" Concrete Arch Pipe End Section | 4.000 | EA | 1,100.00 | 1,020.00 | 855.00 |
| 0360 | 603-CF006 | 58" x 36" Concrete Arch Pipe End Section | 2.000 | EA | 2,250.00 | 2,920.00 | 1,686.00 |
| 0370 | 606-B001 | Guard Rail, Class A, Type 1 | 325.000 | LF | 18.00 | 18.00 | 22.00 |
| 0380 | 606-D012 | Guard Rail, Bridge End Section, Type I | 4.000 | EA | 1,900.00 | 1,900.00 | 2,342.00 |
| 0390 | 606-E002 | Guard Rail, Terminal End Section, Flared | 4.000 | EA | 2,250.00 | 2,250.00 | 2,772.00 |
| 0400 | 609-D007 | Combination Concrete Curb and Gutter Type 2 Modified | 1,475.000 | LF | 30.00 | 22.60 | 31.50 |
| 0410 | 609-D008 | Combination Concrete Curb and Gutter Type 3A | 76.000 | LF | 50.00 | 32.40 | 52.50 |
| 0420 | 614-A001 | Concrete Driveway, Without Reinforcement | 357.000 | SY | 60.00 | 84.00 | 65.00 |
| 0430 | 615-A018 | Concrete Bridge End Barrier, 33.5" | 40.000 | LF | 40.00 | 41.30 | 43.00 |
| 0440 | 616-A001 | Concrete Median and/or Island Pavement, 4-inch | 410.000 | SY | 42.50 | 44.75 | 45.00 |
| 0450 | 616-A003 | Concrete Median and/or Island Pavement, 10-inch | 70.000 | SY | 100.00 | 85.15 | 105.00 |
| 0460 | 619-A1002 | Temporary Traffic Stripe, Continuous White | 3.000 | MI | 600.00 | 600.00 | 630.00 |
| 0470 | 619-A1007 | Temporary Traffic Stripe, Continuous White, Type 1 Tape | 6,644.000 | LF | 1.75 | 1.75 | 1.85 |
| 0480 | 619-A2002 | Temporary Traffic Stripe, Continuous Yellow | 1.000 | MI | 600.00 | 600.00 | 630.00 |
| 0490 | 619-A4004 | Temporary Traffic Stripe, Skip Yellow, Type 1 Tape | 3,322.000 | LF | 1.25 | 1.25 | 1.35 |
| 0500 | 619-A4006 | Temporary Traffic Stripe, Skip Yellow | 2.000 | MI | 600.00 | 600.00 | 630.00 |
| 0510 | 619-A5001 | Temporary Traffic Stripe, Detail | 4,112.000 | LF | 0.20 | 0.20 | 0.25 |
| 0520 | 619-A6001 | Temporary Traffic Stripe, Legend | 191.000 | LF | 1.00 | 1.00 | 1.05 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | Tanner Construction Company, Inc. | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Joe McGee Construction Company, Inc. |
|--|---------------|--|------------|-------|-----------------------------------|--|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$34,900,478.80 | \$34,977,607.77 | \$36,381,906.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0530 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 32.000 | SF | 8.25 | 8.25 | 10.00 |
| 0540 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 823.000 | SF | 8.25 | 8.25 | 10.00 |
| 0550 | 619-D3001 | Remove and Reset Signs, All Sizes | 59.000 | EA | 225.00 | 225.00 | 235.00 |
| 0560 | 619-G4001 | Barricades, Type III, Single Faced | 432.000 | LF | 12.50 | 12.50 | 15.00 |
| 0570 | 619-G4005 | Barricades, Type III, Double Faced | 54.000 | LF | 14.00 | 14.00 | 15.00 |
| 0580 | 619-G5001 | Free Standing Plastic Drums | 38.000 | EA | 41.00 | 41.00 | 50.00 |
| 0590 | 619-G7001 | Warning Lights, Type "B" | 6.000 | EA | 155.00 | 155.00 | 165.00 |
| 0600 | 620-A001 | Mobilization | 1.000 | LS | 2,900,000.00 | 3,237,450.00 | 3,000,000.00 |
| 0610 | 621-A001 | Field Laboratory | 1.000 | EA | 50,000.00 | 25,000.00 | 31,500.00 |
| 0620 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 214.000 | EA | 5.00 | 5.00 | 5.25 |
| 0630 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 61.000 | SF | 19.00 | 19.00 | 20.00 |
| 0640 | 630-A002 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 185.000 | SF | 20.00 | 20.00 | 20.00 |
| 0650 | 630-E004 | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar | 69.000 | LBS | 2.50 | 2.50 | 2.65 |
| 0660 | 630-F001 | Delineators, Guard Rail, White | 22.000 | EA | 18.00 | 18.00 | 20.00 |
| 0670 | 630-G001 | Type 3 Object Markers, OM-3R, Post Mounted | 2.000 | EA | 75.00 | 75.00 | 75.00 |
| 0680 | 630-G003 | Type 3 Object Markers, OM-3L, Post Mounted | 2.000 | EA | 75.00 | 75.00 | 75.00 |
| 0690 | 630-K002 | Welded & Seamless Steel Pipe Posts, 3 1/2" | 55.000 | LF | 40.00 | 40.00 | 42.00 |
| 0700 | 815-A009 | Loose Riprap, Size 300 | 4,500.000 | TON | 53.70 | 51.00 | 54.00 |
| 0710 | 815-E001 | Geotextile under Riprap | 4,253.000 | SY | 1.80 | 2.50 | 3.15 |
| 0720 | 907-203-EX002 | Borrow Excavation, AH, FME, Class B9-10 Modified | 51,400.000 | CY | 9.90 | 9.00 | 8.65 |
| 0730 | 907-216-A001 | Solid Sodding | 582.000 | SY | 5.00 | 5.00 | 6.00 |
| 0740 | 907-225-A001 | Grassing | 22.000 | ACRE | 900.00 | 900.00 | 1,000.00 |
| 0750 | 907-225-B001 | Agricultural Limestone | 11.000 | TON | 100.00 | 100.00 | 100.00 |
| 0760 | 907-225-C001 | Mulch, Vegetative Mulch | 45.000 | TON | 250.00 | 250.00 | 200.00 |
| 0770 | 907-226-A001 | Temporary Grassing | 22.000 | ACRE | 800.00 | 800.00 | 1,000.00 |
| 0780 | 907-237-A003 | Wattles, 20" | 30,250.000 | LF | 3.00 | 4.00 | 5.50 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | Tanner Construction Company, Inc. | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Joe McGee Construction Company, Inc. |
|--|---------------|--|------------|-------|-----------------------------------|--|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$34,900,478.80 | \$34,977,607.77 | \$36,381,906.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 0790 | 907-245-A001 | Triangular Silt Dike | 760.000 | LF | 7.00 | 7.00 | 12.00 |
| 0800 | 907-246-A001 | Sandbags | 3,800.000 | LF | 5.00 | 5.00 | 7.00 |
| 0810 | 907-249-A001 | Riprap for Erosion Control | 1,420.000 | TON | 53.70 | 75.00 | 54.00 |
| 0820 | 907-249-B001 | Remove and Reset Riprap | 710.000 | CY | 15.00 | 35.00 | 27.00 |
| 0830 | 907-304-B009 | Granular Material, Class 3, Group D | 17,800.000 | TON | 18.90 | 22.00 | 22.00 |
| 0840 | 907-304-F002 | Size 610 Crushed Stone Base | 1,750.000 | TON | 45.75 | 51.00 | 43.00 |
| 0850 | 907-310-B001 | Size III Stabilizer Aggregate, Coarse | 3,300.000 | TON | 50.00 | 49.00 | 43.00 |
| 0860 | 907-403-A017 | 9.5-mm, ST, Asphalt Pavement | 277.000 | TON | 99.30 | 119.80 | 100.00 |
| 0870 | 907-403-A018 | 12.5-mm, ST, Asphalt Pavement | 481.000 | TON | 114.95 | 116.25 | 115.00 |
| 0880 | 907-403-A019 | 19-mm, ST, Asphalt Pavement | 2,673.000 | TON | 101.35 | 100.43 | 100.00 |
| 0890 | 907-403-A022 | 9.5-mm, MT, Asphalt Pavement | 2,284.000 | TON | 104.50 | 113.40 | 100.00 |
| 0900 | 907-403-A023 | 12.5-mm, MT, Asphalt Pavement | 2,483.000 | TON | 95.65 | 105.25 | 90.00 |
| 0910 | 907-403-A024 | 19-mm, MT, Asphalt Pavement | 2,525.000 | TON | 94.05 | 101.21 | 90.00 |
| 0920 | 907-403-B013 | 12.5-mm, ST, Asphalt Pavement, Leveling | 66.000 | TON | 114.95 | 155.05 | 110.00 |
| 0930 | 907-403-B017 | 12.5-mm, MT, Asphalt Pavement, Leveling | 617.000 | TON | 95.65 | 123.23 | 90.00 |
| 0940 | 907-403-C011 | 19-mm, MT, Asphalt Pavement, Trench Widening | 33.000 | TON | 261.25 | 196.73 | 250.00 |
| 0950 | 907-406-A001 | Cold Milling of Bituminous Pavement, All Depths | 5,729.000 | SY | 5.30 | 8.00 | 5.00 |
| 0960 | 907-407-A001 | Asphalt for Tack Coat | 3,826.000 | GAL | 2.90 | 3.25 | 3.00 |
| 0970 | 907-413-E001 | Sawing and Sealing Transverse Joints in Asphalt Pavement | 100.000 | LF | 20.00 | 10.00 | 25.00 |
| 0980 | 907-601-B003 | Class "B" Structural Concrete, Minor Structures | 12.000 | CY | 1,400.00 | 2,000.00 | 2,500.00 |
| 0990 | 907-603-ALT01 | 18" Type A Alternate Pipe | 444.000 | LF | 35.00 | 22.00 | 27.00 |
| 1000 | 907-603-ALT02 | 24" Type A Alternate Pipe | 240.000 | LF | 44.00 | 30.00 | 37.00 |
| 1010 | 907-603-ALT03 | 30" Type A Alternate Pipe | 112.000 | LF | 55.00 | 38.00 | 48.00 |
| 1020 | 907-603-ALT12 | 36" x 23" Type A Alternate Pipe | 196.000 | LF | 65.00 | 38.00 | 73.00 |
| 1030 | 907-603-ALT15 | 29" x 18" Type A Alternate Pipe | 176.000 | LF | 55.00 | 31.00 | 55.00 |
| 1040 | 907-617-A001 | Right-of-Way Marker | 45.000 | EA | 100.00 | 250.00 | 200.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | Tanner Construction Company, Inc. | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Joe McGee Construction Company, Inc. |
|--|--------------|--|---------------|-------|-----------------------------------|--|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$34,900,478.80 | \$34,977,607.77 | \$36,381,906.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 1050 | 907-618-A001 | Maintenance of Traffic | 1.000 | LS | 100,000.00 | 105,000.00 | 50,000.00 |
| 1060 | 907-626-C003 | 6" Thermoplastic Double Drop Edge Stripe, Continuous White | 4.000 | MI | 2,600.00 | 2,600.00 | 2,700.00 |
| 1070 | 907-626-D006 | 6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow | 2.000 | MI | 900.00 | 900.00 | 950.00 |
| 1080 | 907-626-E006 | 6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow | 1.000 | MI | 2,600.00 | 2,600.00 | 2,700.00 |
| 1090 | 907-626-G004 | Thermoplastic Detail Stripe, White | 4,637.000 | LF | 0.80 | 0.80 | 0.75 |
| 1100 | 907-626-H004 | Thermoplastic Legend, White | 316.000 | LF | 2.00 | 2.00 | 2.10 |
| 1110 | 907-626-H005 | Thermoplastic Legend, White | 39.000 | SF | 10.00 | 10.00 | 10.00 |
| 1120 | 907-630-C001 | Steel U-Section Posts, 2.0 lb/ft | 28.000 | LF | 7.50 | 7.50 | 8.00 |
| 1130 | 907-630-C003 | Steel U-Section Posts, 3.0 lb/ft | 428.000 | LF | 8.50 | 8.50 | 9.00 |
| 1140 | 907-699-A002 | Roadway Construction Stakes | 1.000 | LS | 175,000.00 | 250,000.00 | 300,000.00 |
| 1150 | 907-815-F001 | Sediment Control Stone | 59.000 | TON | 60.00 | 100.00 | 52.00 |
| 1160 | 907-906001 | Trainees | 1,040.000 | HRS | 5.00 | 5.00 | 5.00 |
| 1170 | 907-304-F002 | Size 610 Crushed Stone Base | 12,200.000 | TON | 45.75 | | 42.00 |
| 1180 | 907-304-F003 | 3/4" and Down Crushed Stone Base | 12,200.000 | TON | | 51.00 | |
| 1190 | 907-304-F004 | Size 825B Crushed Stone Base | 12,200.000 | TON | | | |
| 1200 | 501-K001 | Transverse Grooving | 14,756.000 | SY | 2.15 | 2.15 | 2.65 |
| 1210 | 803-B002 | Conventional Static Pile Load Test | 1.000 | EA | 5,000.00 | 5,000.00 | 5,000.00 |
| 1220 | 803-D007 | HP 14 x 89 Steel Piling | 1,485.000 | LF | 60.00 | 54.00 | 75.00 |
| 1230 | 803-D008 | HP 16 x 121 Steel Piling | 1,540.000 | LF | 95.00 | 90.50 | 95.00 |
| 1240 | 803-I003 | PDA Test Pile, HP Steel Pile | 4.000 | EA | 15,000.00 | 15,000.00 | 7,800.00 |
| 1250 | 803-J001 | Pile Restrike | 2.000 | EA | 2,000.00 | 800.00 | 400.00 |
| 1260 | 803-N001 | Exploration | 560.000 | LF | 1.00 | 10.00 | 10.00 |
| 1270 | 803-O018 | Permanent Casing, 72" Diameter | 2,365.000 | LF | 331.00 | 326.00 | 385.00 |
| 1280 | 803-O024 | Permanent Casing, 102" Diameter | 960.000 | LF | 435.50 | 517.00 | 500.00 |
| 1290 | 805-A001 | Reinforcement | 1,616,359.000 | LBS | 1.20 | 0.77 | 1.00 |
| 1300 | 813-A002 | Concrete Railing, 32" | 6,644.000 | LF | 40.00 | 41.30 | 50.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | Tanner Construction Company, Inc. | Talbot Bros Contr Co, Inc & Talbot Bros Grading Co, Inc, AJV | Joe McGee Construction Company, Inc. |
|--|--------------|--|---------------|-------|-----------------------------------|--|--------------------------------------|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$34,900,478.80 | \$34,977,607.77 | \$36,381,906.65 |
| Ref# | Item | Item Description | Item Qty | Units | 4 | 5 | 6 |
| 1310 | 815-A009 | Loose Riprap, Size 300 | 1,887.000 | TON | 54.00 | 51.00 | 55.00 |
| 1320 | 815-E001 | Geotextile under Riprap | 1,649.000 | SY | 1.80 | 2.50 | 3.00 |
| 1330 | 907-803-K001 | Drilled Shaft, 48" Diameter | 330.000 | LF | 385.00 | 545.55 | 345.00 |
| 1340 | 907-803-K010 | Drilled Shaft, 72" Diameter | 4,230.000 | LF | 505.00 | 892.73 | 525.00 |
| 1350 | 907-803-K013 | Drilled Shaft, 102" Diameter | 1,740.000 | LF | 725.00 | 1,780.17 | 1,130.00 |
| 1360 | 907-803-L006 | Test Shaft, 72" Diameter | 1.000 | EA | 445,000.00 | 305,000.00 | 580,000.00 |
| 1370 | 907-803-M011 | Trial Shaft, 102" Diameter | 172.000 | LF | 1,885.00 | 1,992.85 | 2,500.00 |
| 1380 | 907-804-A018 | Bridge Concrete, Substructure, Class AA | 2,480.000 | CY | 1,145.00 | 507.00 | 460.00 |
| 1390 | 907-804-A019 | Bridge Concrete, Superstructure, Class AA | 4,366.000 | CY | 705.00 | 700.00 | 700.00 |
| 1400 | 907-804-C010 | 125' Prestressed Concrete Beam, Type BT-72 | 11,934.000 | LF | 245.00 | 172.50 | 320.00 |
| 1410 | 907-804-C016 | 40' Prestressed Concrete Beam, Type I+2 | 239.000 | LF | 155.00 | 86.00 | 90.00 |
| 1420 | 907-804-C019 | 60' Prestressed Concrete Beam, Type II+2 | 1,782.000 | LF | 180.00 | 111.65 | 112.00 |
| 1430 | 907-804-C030 | 80' Prestressed Concrete Beam, Type III | 479.000 | LF | 200.00 | 115.40 | 130.00 |
| 1440 | 907-810-A001 | Structural Steel, A 709, Grade 50W | 3,137,110.000 | LBS | 2.00 | 1.61 | 1.60 |
| 1450 | 907-810-A002 | Structural Steel, A 709, Grade HPS 70W | 260,441.000 | LBS | 2.00 | 1.61 | 1.60 |
| 1460 | 907-811-D001 | Disc Bearing Device | 20.000 | EA | 5,830.00 | 6,000.00 | 6,000.00 |
| 1470 | 907-822-A007 | 8 1/8" Neoprene Expansion Joint | 149.000 | LF | 545.00 | 750.00 | 925.00 |
| 1480 | 907-822-A008 | 12 1/4" Neoprene Expansion Joint | 100.000 | LF | 735.00 | 1,125.00 | 1,365.00 |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | T. L. Wallace Construction, Inc. | Eutaw Construction Company, Inc. | |
|--|-----------|--|-------------|-------|----------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$36,721,141.98 | \$38,490,108.76 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0010 | 201-A001 | Clearing and Grubbing | 1.000 | LS | 3,265,000.00 | 1,100,000.00 | |
| 0020 | 201-B001 | Clearing and Grubbing | 16.000 | ACRE | 62,000.00 | 1,700.00 | |
| 0030 | 202-A001 | Removal of Obstructions | 1.000 | LS | 750,000.00 | 953,000.00 | |
| 0040 | 202-B018 | Removal of Concrete Driveways, All Depths | 951.000 | SY | 11.00 | 10.00 | |
| 0050 | 202-B024 | Removal of Concrete Median & Island Pavement, All Depths | 460.000 | SY | 11.00 | 11.00 | |
| 0060 | 202-B064 | Removal of Pipe, 8" And Above | 596.000 | LF | 22.00 | 12.00 | |
| 0070 | 202-B069 | Removal of Sign | 46.000 | EA | 83.00 | 72.00 | |
| 0080 | 202-B093 | Removal of Curb & Gutter, All Types | 1,306.000 | LF | 7.80 | 9.00 | |
| 0090 | 202-B097 | Removal of Concrete Overlaid w/ Asphalt Pavement, All Depths | 28,393.000 | SY | 7.80 | 10.00 | |
| 0100 | 202-B102 | Removal of Guard Rail | 1,153.000 | LF | 5.55 | 4.83 | |
| 0110 | 203-A003 | Unclassified Excavation, FM, AH | 91,267.000 | CY | 4.75 | 4.75 | |
| 0120 | 203-EX017 | Borrow Excavation, AH, FME, Class B9 | 66,461.000 | CY | 8.90 | 11.00 | |
| 0130 | 203-G003 | Excess Excavation, FM, AH | 100,121.000 | CY | 6.65 | 6.00 | |
| 0140 | 206-A001 | Structure Excavation | 578.000 | CY | 17.00 | 8.00 | |
| 0150 | 206-B001 | Select Material for Undercuts, Contractor Furnished, FM | 39.000 | CY | 50.00 | 72.00 | |
| 0160 | 209-A004 | Geotextile Stabilization, Type V, Non-Woven | 28,811.000 | SY | 2.20 | 1.50 | |
| 0170 | 211-B001 | Topsoil for Slope Treatment, Contractor Furnished | 8,977.000 | CY | 11.00 | 10.00 | |
| 0180 | 213-C001 | Superphosphate | 11.000 | TON | 560.00 | 632.00 | |
| 0190 | 217-A001 | Ditch Liner | 669.000 | SY | 2.50 | 1.05 | |
| 0200 | 219-A001 | Watering | 12.000 | KGAL | 20.00 | 20.00 | |
| 0210 | 220-A001 | Insect Pest Control | 11.000 | ACRE | 30.00 | 30.00 | |
| 0220 | 221-A001 | Portland Cement Concrete Paved Ditch | 78.000 | CY | 520.00 | 450.00 | |
| 0230 | 223-A001 | Mowing | 44.000 | ACRE | 50.00 | 50.00 | |
| 0240 | 224-A001 | Soil Reinforcing Mat | 3,594.000 | SY | 2.20 | 1.50 | |
| 0250 | 234-A001 | Temporary Silt Fence | 31,050.000 | LF | 2.65 | 3.30 | |
| 0260 | 239-A001 | Temporary Slope Drains | 1,150.000 | LF | 5.55 | 6.00 | |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | T. L. Wallace Construction, Inc. | Eutaw Construction Company, Inc. | |
|--|-----------|---|-----------|-------|----------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$36,721,141.98 | \$38,490,108.76 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0270 | 423-A001 | Rumble Strips, Ground In | 2.000 | MI | 440.00 | 390.00 | |
| 0280 | 502-A001 | Reinforced Cement Concrete Bridge End Pavement | 202.000 | SY | 280.00 | 350.00 | |
| 0290 | 602-A001 | Reinforcing Steel | 869.000 | LBS | 3.35 | 0.80 | |
| 0300 | 603-A040 | 48" Steel Pipe, Jacked or Bored, Wall Thickness 0.625" | 88.000 | LF | 870.00 | 840.00 | |
| 0310 | 603-CA004 | 30" Reinforced Concrete Pipe, Class III | 88.000 | LF | 60.00 | 65.00 | |
| 0320 | 603-CB002 | 24" Reinforced Concrete End Section | 2.000 | EA | 1,700.00 | 1,000.00 | |
| 0330 | 603-CB003 | 30" Reinforced Concrete End Section | 2.000 | EA | 1,700.00 | 1,100.00 | |
| 0340 | 603-CE006 | 58" x 36" Concrete Arch Pipe, Class A III | 288.000 | LF | 130.00 | 150.00 | |
| 0350 | 603-CF002 | 29" x 18" Concrete Arch Pipe End Section | 4.000 | EA | 1,700.00 | 1,000.00 | |
| 0360 | 603-CF006 | 58" x 36" Concrete Arch Pipe End Section | 2.000 | EA | 2,800.00 | 2,000.00 | |
| 0370 | 606-B001 | Guard Rail, Class A, Type 1 | 325.000 | LF | 20.00 | 17.37 | |
| 0380 | 606-D012 | Guard Rail, Bridge End Section, Type 1 | 4.000 | EA | 2,100.00 | 1,833.50 | |
| 0390 | 606-E002 | Guard Rail, Terminal End Section, Flared | 4.000 | EA | 2,500.00 | 2,171.25 | |
| 0400 | 609-D007 | Combination Concrete Curb and Gutter Type 2 Modified | 1,475.000 | LF | 25.00 | 21.81 | |
| 0410 | 609-D008 | Combination Concrete Curb and Gutter Type 3A | 76.000 | LF | 36.00 | 31.27 | |
| 0420 | 614-A001 | Concrete Driveway, Without Reinforcement | 357.000 | SY | 93.00 | 81.06 | |
| 0430 | 615-A018 | Concrete Bridge End Barrier, 33.5" | 40.000 | LF | 43.00 | 36.00 | |
| 0440 | 616-A001 | Concrete Median and/or Island Pavement, 4-inch | 410.000 | SY | 50.00 | 43.00 | |
| 0450 | 616-A003 | Concrete Median and/or Island Pavement, 10-inch | 70.000 | SY | 95.00 | 82.00 | |
| 0460 | 619-A1002 | Temporary Traffic Stripe, Continuous White | 3.000 | MI | 890.00 | 579.00 | |
| 0470 | 619-A1007 | Temporary Traffic Stripe, Continuous White, Type 1 Tape | 6,644.000 | LF | 3.35 | 1.70 | |
| 0480 | 619-A2002 | Temporary Traffic Stripe, Continuous Yellow | 1.000 | MI | 890.00 | 579.00 | |
| 0490 | 619-A4004 | Temporary Traffic Stripe, Skip Yellow, Type 1 Tape | 3,322.000 | LF | 3.35 | 1.20 | |
| 0500 | 619-A4006 | Temporary Traffic Stripe, Skip Yellow | 2.000 | MI | 890.00 | 579.00 | |
| 0510 | 619-A5001 | Temporary Traffic Stripe, Detail | 4,112.000 | LF | 0.20 | 0.20 | |
| 0520 | 619-A6001 | Temporary Traffic Stripe, Legend | 191.000 | LF | 1.10 | 1.00 | |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | T. L. Wallace Construction, Inc. | Eutaw Construction Company, Inc. | |
|--|---------------|--|------------|-------|----------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$36,721,141.98 | \$38,490,108.76 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0530 | 619-D1001 | Standard Roadside Construction Signs, Less than 10 Square Feet | 32.000 | SF | 9.15 | 7.75 | |
| 0540 | 619-D2001 | Standard Roadside Construction Signs, 10 Square Feet or More | 823.000 | SF | 9.15 | 7.75 | |
| 0550 | 619-D3001 | Remove and Reset Signs, All Sizes | 59.000 | EA | 250.00 | 220.00 | |
| 0560 | 619-G4001 | Barricades, Type III, Single Faced | 432.000 | LF | 14.00 | 17.50 | |
| 0570 | 619-G4005 | Barricades, Type III, Double Faced | 54.000 | LF | 16.00 | 21.25 | |
| 0580 | 619-G5001 | Free Standing Plastic Drums | 38.000 | EA | 46.00 | 72.50 | |
| 0590 | 619-G7001 | Warning Lights, Type "B" | 6.000 | EA | 170.00 | 242.00 | |
| 0600 | 620-A001 | Mobilization | 1.000 | LS | 3,600,000.00 | 3,800,000.00 | |
| 0610 | 621-A001 | Field Laboratory | 1.000 | EA | 93,000.00 | 25,000.00 | |
| 0620 | 627-L001 | Two-Way Yellow Reflective High Performance Raised Markers | 214.000 | EA | 6.10 | 4.85 | |
| 0630 | 630-A001 | Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness | 61.000 | SF | 21.00 | 18.35 | |
| 0640 | 630-A002 | Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness | 185.000 | SF | 22.00 | 19.30 | |
| 0650 | 630-E004 | Structural Steel Angles & Bars, 7/16" x 2 1/2" Flat Bar | 69.000 | LBS | 2.80 | 2.45 | |
| 0660 | 630-F001 | Delineators, Guard Rail, White | 22.000 | EA | 20.00 | 17.50 | |
| 0670 | 630-G001 | Type 3 Object Markers, OM-3R, Post Mounted | 2.000 | EA | 83.00 | 72.50 | |
| 0680 | 630-G003 | Type 3 Object Markers, OM-3L, Post Mounted | 2.000 | EA | 83.00 | 72.50 | |
| 0690 | 630-K002 | Welded & Seamless Steel Pipe Posts, 3 1/2" | 55.000 | LF | 44.00 | 38.60 | |
| 0700 | 815-A009 | Loose Riprap, Size 300 | 4,500.000 | TON | 54.00 | 62.00 | |
| 0710 | 815-E001 | Geotextile under Riprap | 4,253.000 | SY | 2.20 | 3.25 | |
| 0720 | 907-203-EX002 | Borrow Excavation, AH, FME, Class B9-10 Modified | 51,400.000 | CY | 8.90 | 10.25 | |
| 0730 | 907-216-A001 | Solid Sodding | 582.000 | SY | 11.00 | 5.60 | |
| 0740 | 907-225-A001 | Grassing | 22.000 | ACRE | 1,100.00 | 865.00 | |
| 0750 | 907-225-B001 | Agricultural Limestone | 11.000 | TON | 110.00 | 85.85 | |
| 0760 | 907-225-C001 | Mulch, Vegetative Mulch | 45.000 | TON | 180.00 | 161.50 | |
| 0770 | 907-226-A001 | Temporary Grassing | 22.000 | ACRE | 1,200.00 | 707.00 | |
| 0780 | 907-237-A003 | Wattles, 20" | 30,250.000 | LF | 4.25 | 3.50 | |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | T. L. Wallace Construction, Inc. | Eutaw Construction Company, Inc. | |
|--|---------------|--|------------|-------|----------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$36,721,141.98 | \$38,490,108.76 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 0790 | 907-245-A001 | Triangular Silt Dike | 760.000 | LF | 12.00 | 9.00 | |
| 0800 | 907-246-A001 | Sandbags | 3,800.000 | LF | 4.45 | 4.50 | |
| 0810 | 907-249-A001 | Riprap for Erosion Control | 1,420.000 | TON | 53.00 | 62.00 | |
| 0820 | 907-249-B001 | Remove and Reset Riprap | 710.000 | CY | 17.00 | 20.00 | |
| 0830 | 907-304-B009 | Granular Material, Class 3, Group D | 17,800.000 | TON | 22.00 | 26.00 | |
| 0840 | 907-304-F002 | Size 610 Crushed Stone Base | 1,750.000 | TON | 51.00 | 55.00 | |
| 0850 | 907-310-B001 | Size III Stabilizer Aggregate, Coarse | 3,300.000 | TON | 47.00 | 46.00 | |
| 0860 | 907-403-A017 | 9.5-mm, ST, Asphalt Pavement | 277.000 | TON | 110.00 | 95.57 | |
| 0870 | 907-403-A018 | 12.5-mm, ST, Asphalt Pavement | 481.000 | TON | 120.00 | 110.66 | |
| 0880 | 907-403-A019 | 19-mm, ST, Asphalt Pavement | 2,673.000 | TON | 110.00 | 97.59 | |
| 0890 | 907-403-A022 | 9.5-mm, MT, Asphalt Pavement | 2,284.000 | TON | 110.00 | 100.60 | |
| 0900 | 907-403-A023 | 12.5-mm, MT, Asphalt Pavement | 2,483.000 | TON | 100.00 | 92.05 | |
| 0910 | 907-403-A024 | 19-mm, MT, Asphalt Pavement | 2,525.000 | TON | 100.00 | 90.54 | |
| 0920 | 907-403-B013 | 12.5-mm, ST, Asphalt Pavement, Leveling | 66.000 | TON | 120.00 | 110.66 | |
| 0930 | 907-403-B017 | 12.5-mm, MT, Asphalt Pavement, Leveling | 617.000 | TON | 100.00 | 92.05 | |
| 0940 | 907-403-C011 | 19-mm, MT, Asphalt Pavement, Trench Widening | 33.000 | TON | 280.00 | 251.51 | |
| 0950 | 907-406-A001 | Cold Milling of Bituminous Pavement, All Depths | 5,729.000 | SY | 2.70 | 2.35 | |
| 0960 | 907-407-A001 | Asphalt for Tack Coat | 3,826.000 | GAL | 3.05 | 2.77 | |
| 0970 | 907-413-E001 | Sawing and Sealing Transverse Joints in Asphalt Pavement | 100.000 | LF | 22.00 | 19.49 | |
| 0980 | 907-601-B003 | Class "B" Structural Concrete, Minor Structures | 12.000 | CY | 1,100.00 | 2,300.00 | |
| 0990 | 907-603-ALT01 | 18" Type A Alternate Pipe | 444.000 | LF | 39.00 | 30.00 | |
| 1000 | 907-603-ALT02 | 24" Type A Alternate Pipe | 240.000 | LF | 460.00 | 33.00 | |
| 1010 | 907-603-ALT03 | 30" Type A Alternate Pipe | 112.000 | LF | 67.00 | 35.00 | |
| 1020 | 907-603-ALT12 | 36" x 23" Type A Alternate Pipe | 196.000 | LF | 81.00 | 42.00 | |
| 1030 | 907-603-ALT15 | 29" x 18" Type A Alternate Pipe | 176.000 | LF | 69.00 | 36.00 | |
| 1040 | 907-617-A001 | Right-of-Way Marker | 45.000 | EA | 280.00 | 195.00 | |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | T. L. Wallace Construction, Inc. | Eutaw Construction Company, Inc. | |
|--|--------------|--|---------------|-------|----------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$36,721,141.98 | \$38,490,108.76 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 1050 | 907-618-A001 | Maintenance of Traffic | 1.000 | LS | 1,300.00 | 670,000.00 | |
| 1060 | 907-626-C003 | 6" Thermoplastic Double Drop Edge Stripe, Continuous White | 4.000 | MI | 3,100.00 | 2,509.00 | |
| 1070 | 907-626-D006 | 6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow | 2.000 | MI | 1,600.00 | 868.50 | |
| 1080 | 907-626-E006 | 6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow | 1.000 | MI | 3,000.00 | 2,509.00 | |
| 1090 | 907-626-G004 | Thermoplastic Detail Stripe, White | 4,637.000 | LF | 0.90 | 0.77 | |
| 1100 | 907-626-H004 | Thermoplastic Legend, White | 316.000 | LF | 3.35 | 1.93 | |
| 1110 | 907-626-H005 | Thermoplastic Legend, White | 39.000 | SF | 6.65 | 9.65 | |
| 1120 | 907-630-C001 | Steel U-Section Posts, 2.0 lb/ft | 28.000 | LF | 8.35 | 7.24 | |
| 1130 | 907-630-C003 | Steel U-Section Posts, 3.0 lb/ft | 428.000 | LF | 9.45 | 8.20 | |
| 1140 | 907-699-A002 | Roadway Construction Stakes | 1.000 | LS | 236,000.00 | 350,000.00 | |
| 1150 | 907-815-F001 | Sediment Control Stone | 59.000 | TON | 63.00 | 50.00 | |
| 1160 | 907-906001 | Trainees | 1,040.000 | HRS | 5.00 | 5.00 | |
| 1170 | 907-304-F002 | Size 610 Crushed Stone Base | 12,200.000 | TON | 50.00 | 55.00 | |
| 1180 | 907-304-F003 | 3/4" and Down Crushed Stone Base | 12,200.000 | TON | | | |
| 1190 | 907-304-F004 | Size 825B Crushed Stone Base | 12,200.000 | TON | | | |
| 1200 | 501-K001 | Transverse Grooving | 14,756.000 | SY | 2.40 | 2.10 | |
| 1210 | 803-B002 | Conventional Static Pile Load Test | 1.000 | EA | 5,000.00 | 5,000.00 | |
| 1220 | 803-D007 | HP 14 x 89 Steel Piling | 1,485.000 | LF | 64.00 | 61.00 | |
| 1230 | 803-D008 | HP 16 x 121 Steel Piling | 1,540.000 | LF | 93.00 | 122.00 | |
| 1240 | 803-I003 | PDA Test Pile, HP Steel Pile | 4.000 | EA | 13,000.00 | 15,500.00 | |
| 1250 | 803-J001 | Pile Restrike | 2.000 | EA | 2,900.00 | 1,100.00 | |
| 1260 | 803-N001 | Exploration | 560.000 | LF | 24.00 | 10.00 | |
| 1270 | 803-O018 | Permanent Casing, 72" Diameter | 2,365.000 | LF | 350.00 | 312.00 | |
| 1280 | 803-O024 | Permanent Casing, 102" Diameter | 960.000 | LF | 460.00 | 412.00 | |
| 1290 | 805-A001 | Reinforcement | 1,616,359.000 | LBS | 1.05 | 0.90 | |
| 1300 | 813-A002 | Concrete Railing, 32" | 6,644.000 | LF | 43.00 | 39.00 | |

| Bridge Replacement on SR 6 Over Tallahatchie River & Relief Bridge Nos. 44.3 & 44.7, known as Federal Aid Project No. STP/EXB-0070-03(022) / 103164301 in Panola County. | | | | | T. L. Wallace Construction, Inc. | Eutaw Construction Company, Inc. | |
|--|--------------|--|---------------|-------|----------------------------------|----------------------------------|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$30,514,815.24 | | | | | \$36,721,141.98 | \$38,490,108.76 | |
| Ref# | Item | Item Description | Item Qty | Units | 7 | 8 | |
| 1310 | 815-A009 | Loose Riprap, Size 300 | 1,887.000 | TON | 57.00 | 62.00 | |
| 1320 | 815-E001 | Geotextile under Riprap | 1,649.000 | SY | 2.90 | 3.00 | |
| 1330 | 907-803-K001 | Drilled Shaft, 48" Diameter | 330.000 | LF | 380.00 | 507.87 | |
| 1340 | 907-803-K010 | Drilled Shaft, 72" Diameter | 4,230.000 | LF | 650.00 | 780.19 | |
| 1350 | 907-803-K013 | Drilled Shaft, 102" Diameter | 1,740.000 | LF | 1,100.00 | 1,240.66 | |
| 1360 | 907-803-L006 | Test Shaft, 72" Diameter | 1.000 | EA | 350,000.00 | 755,587.24 | |
| 1370 | 907-803-M011 | Trial Shaft, 102" Diameter | 172.000 | LF | 2,100.00 | 6,080.67 | |
| 1380 | 907-804-A018 | Bridge Concrete, Substructure, Class AA | 2,480.000 | CY | 670.00 | 605.00 | |
| 1390 | 907-804-A019 | Bridge Concrete, Superstructure, Class AA | 4,366.000 | CY | 710.00 | 900.00 | |
| 1400 | 907-804-C010 | 125' Prestressed Concrete Beam, Type BT-72 | 11,934.000 | LF | 156.50 | 200.00 | |
| 1410 | 907-804-C016 | 40' Prestressed Concrete Beam, Type I+2 | 239.000 | LF | 95.00 | 97.00 | |
| 1420 | 907-804-C019 | 60' Prestressed Concrete Beam, Type II+2 | 1,782.000 | LF | 113.00 | 130.00 | |
| 1430 | 907-804-C030 | 80' Prestressed Concrete Beam, Type III | 479.000 | LF | 117.00 | 151.00 | |
| 1440 | 907-810-A001 | Structural Steel, A 709, Grade 50W | 3,137,110.000 | LBS | 1.42 | 1.68 | |
| 1450 | 907-810-A002 | Structural Steel, A 709, Grade HPS 70W | 260,441.000 | LBS | 1.53 | 1.68 | |
| 1460 | 907-811-D001 | Disc Bearing Device | 20.000 | EA | 6,200.00 | 7,000.00 | |
| 1470 | 907-822-A007 | 8 1/8" Neoprene Expansion Joint | 149.000 | LF | 870.00 | 1,000.00 | |
| 1480 | 907-822-A008 | 12 1/4" Neoprene Expansion Joint | 100.000 | LF | 1,300.00 | 1,600.00 | |