

Bridge Repair on I-20 West to US 61 South Ramp, known as Federal Aid Project No. BR-0020-01(241) / 107398301000 Warren County.					Gibson & Associates, Inc.	Key, LLC	Century Construction & Realty, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$281,111.75					\$263,734.60	\$317,835.00	\$451,029.72
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	96.000	SF	9.50	7.50	7.59
0020	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	386.000	SF	9.10	7.50	7.59
0030	619-E1001	Flashing Arrow Panel, Type C	1.000	EA	4,000.00	3,800.00	2,006.33
0040	619-F1001	Concrete Median Barrier, Precast	1,400.000	LF	25.00	10.00	70.76
0042	619-F2001	Remove and Reset Concrete Median Barrier, Precast	1,400.000	LF	9.00	10.00	24.93
0050	619-G4001	Barricades, Type III, Single Faced	48.000	LF	24.50	15.00	15.18
0060	619-G5001	Free Standing Plastic Drums	50.000	EA	38.50	35.00	43.38
0070	619-G7001	Warning Lights, Type "B"	8.000	EA	83.00	230.00	200.63
0080	620-A001	Mobilization	1.000	LS	26,500.00	30,000.00	45,000.00
0090	907-618-A001	Maintenance of Traffic	1.000	LS	11,600.00	32,500.00	77,000.00
0100	907-619-E3001	Changeable Message Sign	2.000	EA	1,375.00	1,650.00	5,964.75
0110	907-304-F002	Size 610 Crushed Stone Base	80.000	TON	72.00	105.00	57.25
0120	907-304-F003	3/4" and Down Crushed Stone Base	80.000	TON			
0130	907-304-F004	Size 825B Crushed Stone Base	80.000	TON			
0140	202-B036	Removal of Concrete Slope Paving	42.000	SY	90.00	55.00	55.87
0150	808-A001	Joint Preparation	170.000	LF	33.00	30.00	16.01
0160	815-D001	Concrete Slope Paving	7.000	CY	1,280.00	1,250.00	1,946.83
0170	907-823-A002	Preformed Joint Seal, Type II	85.000	LF	44.00	95.00	72.38
0180	907-823-B002	Saw Cut, Type II	85.000	LF	11.00	25.00	14.01
0190	907-824-PP095	Bridge Repair, Masonry Plate Removal and Replacment	12.000	EA	6,200.00	6,250.00	5,996.96
0200	907-824-PP097	Bridge Repair, End Wall Removal and Repair	84.000	LF	215.00	575.00	482.79
0210	907-824-PP098	Bridge Repair, Painting of Steel Structure	775.000	SF	54.00	70.00	38.49