

Mill & Overlay approximately 4 miles US 49 East from Pelucia Creek to US 82, known as Federal Aid Project No. STP-0008-05(030) /107502301 in Leflore County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,241,693.58					\$1,351,228.85		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B033	Removal of Concrete Pavement w/ Variable Depth Overlay	430.000	SY	230.00		
0020	202-B076	Removal of Traffic Stripe	276.000	LF	1.00		
0030	203-G003	Excess Excavation, FM, AH	100.000	CY	5.25		
0040	423-A001	Rumble Strips, Ground In	7.000	MI	390.00		
0050	503-C007	Saw Cut, Full Depth	1,200.000	LF	18.80		
0060	606-B025	Guard Rail, Replace Metal Blockout	69.000	EA	55.00		
0070	609-D002	Combination Concrete Curb and Gutter Type 2	164.000	LF	48.75		
0080	616-A001	Concrete Median and/or Island Pavement, 4-inch	57.000	SY	65.50		
0090	619-A1002	Temporary Traffic Stripe, Continuous White	12.000	MI	390.00		
0100	619-A2002	Temporary Traffic Stripe, Continuous Yellow	6.000	MI	500.00		
0110	619-A3006	Temporary Traffic Stripe, Skip White	2.000	MI	500.00		
0120	619-A4006	Temporary Traffic Stripe, Skip Yellow	6.000	MI	500.00		
0130	619-A5001	Temporary Traffic Stripe, Detail	18,634.000	LF	0.15		
0140	619-A6001	Temporary Traffic Stripe, Legend	2,009.000	LF	0.50		
0150	620-A001	Mobilization	1.000	LS	90,000.00		
0160	627-K001	Red-Clear Reflective High Performance Raised Markers	200.000	EA	4.00		
0170	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	1,023.000	EA	4.00		
0180	907-304-B009	Granular Material, Class 3, Group D	1,500.000	TON	34.00		
0190	907-403-A017	9.5-mm, ST, Asphalt Pavement	5,920.000	TON	98.00		
0200	907-403-A019	19-mm, ST, Asphalt Pavement	150.000	TON	137.70		
0210	907-403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	350.000	TON	130.00		
0220	907-406-D001	Fine Milling of Bituminous Pavement, All Depths	67,900.000	SY	2.50		
0230	907-407-A001	Asphalt for Tack Coat	5,100.000	GAL	2.00		
0240	907-413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	15,000.000	LF	2.25		
0250	907-618-A001	Maintenance of Traffic	1.000	LS	100,000.00		
0260	907-618-B001	Additional Construction Signs	1.000	SF	10.00		

Mill & Overlay approximately 4 miles US 49 East from Pelucia Creek to US 82, known as Federal Aid Project No. STP-0008-05(030) /107502301 in Leflore County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,241,693.58					\$1,351,228.85		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	907-626-A003	6" Thermoplastic Traffic Stripe, Skip White	1.000	MI	1,000.00		
0280	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White	6.000	MI	2,100.00		
0290	907-626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	3.000	MI	1,000.00		
0300	907-626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	3.000	MI	2,000.00		
0310	907-626-G004	Thermoplastic Detail Stripe, White	9,317.000	LF	0.75		
0320	907-626-G005	Thermoplastic Detail Stripe, Yellow	8,900.000	LF	0.70		
0330	907-626-H004	Thermoplastic Legend, White	1,900.000	LF	2.50		
0340	907-304-F002	Size 610 Crushed Stone Base	650.000	TON	75.00		
0350	907-304-F003	3/4" and Down Crushed Stone Base	650.000	TON			
0360	907-304-F004	Size 825B Crushed Stone Base	650.000	TON			