

Call 02 OGFC Lift on I-55 from Louisiana State Line to SR 568, known as Federal Aid Project No. IM-0055-01(113) / 107554301 in Pike County.

- Q1. Was bid item 619-D2002, Std Roadside Const. Signs 10 SF or more, Permanent meant to be 619-D2001 instead? What purpose would be served by requiring the 10 SF + signs to be left in place and not the under 10' signs? I will be happy to bid D2002 if that is what you intended but there is a large difference in pricing from D2001.
- A1. Bidders are advised to bid the pay item as shown in the plans.
- Q2. On sheet TRS-1 detail for conduit placement. Note #4 states buried cable to power source and communication source. **1.** Where is the power source and the communication source? **2.** What size and type cable do we install for the power and communication?
- A2. **1.** An existing power and communication source is located on the west side of the interstate at the location shown in the plans. **2.** Cable size and type shall meet the requirements of Special Provision 907-688-1, the appropriate sections in the 2017 Standard Specifications, and the manufacturer's recommendations.
- Q3. In NTB 185 it states that traffic will be able to ride on a milled surface for 5 days. Can this be extended for this project since only the OGFC is being milled?
- A3. Yes, for this project the Department will allow traffic to ride on a milled surface for up to ten (10) days. NTB 185 will be revised to reflect this change in an upcoming Class IV Supplemental Agreement with the successful bidder at a later date.