

Call 05 Construction of Colony Park Blvd. from Sunnybrook Rd. to U.S. 51, known as Federal Aid Project No. ACNH-9204-00(003) / 100486303 in Madison County.

Q1. We would like to request a copy of the centerline soil boring report.

A1. It can be downloaded from the link below:

<https://file-exchange.mdot.state.ms.us/dl/?f=ae7834bfcd642221f8733cbebd31f74dc51ac5b0>

Q2. Since the bike/walking trail will not be chemically treated, what will the density requirements be on the 12' bike/walking trail?

A2. The density requirements for asphalt will be the same as for the chemically treated areas.

Q3. Are pre-cast drainage structures allowed with cast in place tops?

A3. Yes, in accordance with Subsection 601.02.3 of the 2017 Standard Specifications and Sheets PCU-1 and PCU-2 in the plans.

Q4. Is burning of trees and stumps within the limits of the ROW acceptable?

A4. Burning of trees and stumps shall be in accordance with Subsection 107.22.2 of the 2017 Standard Specifications.

Q5. **1.** Where is the 665-A002 Video Encoder, Type A to be deployed? **2.** What camera will it be transmitting? The PTZ camera on TSI-1 isn't indicated to be analog; hence, by requirement it is an IP camera.

A5. See addendum.

Q6. Item 307-S001 in the plans has a quantity of 8893 gallons; however, the EBS file for this item has a quantity of 26,678 gallons which appears to be an error.

A6. See addendum.

Q7. Item 603-A023 36" Steel Pipe Jacked or Bored and Item 603-A018 30" Steel Pipe Jacked or Bored both have a wall thickness of 0.500" specified; however, note 32 on sheet GN-2 states that the wall thickness should be 0.875". Please clarify.

A7. See addendum.

Q8. Can traffic run on a milled surface?

A8. Traffic will be permitted on the milled surface at tie-in locations; however, traffic will not be permitted on the milled surface on mainline areas.