

**Call 03 Bridge Painting on SR 35 & SR 8, Nos. 153.1, 176.7, & 43.4, known as Federal Aid Project Nos. BR-0016-02(038) / 107570301, 302, & 303 in Attala, Carroll, & Leflore Counties.**

Q1. Unable to locate working hours for this project. Are there any time restrictions on work days/hours?

A1. There are no restrictions other than those outlined in the 2017 Standard Specifications for Road and Bridge Construction.

Q2. According to SP 907-845-1, page 106; 907-845.02.6 speaks of a Class 3 rust preventative compound, hot applied. We are not familiar with this material and since it's a special provision, information cannot be found on this material. Also, unable to locate a rust preventative compound on the approved materials list. Can you please elaborate on the compound, who produces it, location of application, and application process? Thank you.

A2. The rust preventative compound shall meet the requirements of Military Specifications MIL-C-11796C. Technical data sheets for the Contractor's elected product shall provide the application process. Please refer the section 907-845.03.8.1 of proposal for locations the rust preventative compound is to be used.

Q3. Thank you for your response in regards to the rust preventative compound. However, it is still unclear what locations will be needing this material applied. The proposal states to be applied to all machine finished or similar surfaces not to be coated as directed by Engineer. Can you specify exact locations? We are uncertain how much material will be needed for the project. This could greatly affect the pricing in estimate for this project.

A3. The application of rust preventative compound is not required on these bridges.

Q4. Are there any plans or as-builts available for this project?

A4. See the link below:

<https://file-exchange.mdot.state.ms.us/dl/?f=19e2d7b0f674332780d246583c6dd558871e15e3>