

Call 04 Slide Repair on SR 28 nine miles East of Fayette, known as Federal Aid Project No. STP-0013-01(015) / 107338301 in Jefferson County.

- Q1. In the traffic control plan you show the temp traffic signals going on both sides of the road on each end is this correct?
- A1. No, there should be one at each end, for a total of two (2) temporary signals. The Summary of Quantities sheet is correct.
- Q2. The Plans show two CMS but there is no pay item for them and I don't see a note that says they are absorbed. How will they be paid?
- A2. See upcoming addendum.
- Q3. In reference to the following on the above mentioned project, we have these questions regarding the normal underdrain type 2, Item#UD-2, Plan Sheet 6332. **1.** Will this detail be used on this project? **2.** If so, what is the estimated amount of type B material needed for project? **3.** Will the type B material be wrapped in geotextile? **4.** Will type B material be an absorbed item, or should it be listed in bid quantities? **5.** Will the geotextile have to be stitched? **6.** Is geotextile already in bid quantities?
- A3. **1.** No. Details regarding the underdrain can be found on Plan Sheet Number 17. See upcoming addendum regarding Type B Filter Material. **2.** See upcoming addendum. **3.** No. **4.** See upcoming addendum. **5.** No. **6.** Yes.
- Q4. Why are there are two separate pay items for Type V Geotextile fabric?
- A4. Pay item 209-A, Geotextile Stabilization, Type V, Non-Woven will be used to pay for geotextile as shown on TS-2, Plan Sheet Number 6. Pay item 605-AA, Geotextile for Subsurface Drainage, Type V, Non-Woven shall be used to pay for the remainder of the fabric used in the slide repair.