

Pavement Restoration on I-10 at the State Line, known as Federal Aid Project No. IM-0010-01(151) / 107074301 in Jackson County.					Mallette Brothers Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$776,032.72					\$1,168,570.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B068	Removal of Concrete Pavement Punchouts, 9" Depth	111.000	SY	325.00		
0020	202-B136	Removal of Guard Rail	982.000	LF	8.00		
0030	402-A002	Open Graded Friction Course, 9.5-mm Mixture	664.000	TON	150.00		
0040	402-B001	Bituminous Tack Coat	1,106.000	GAL	20.00		
0050	403-A003	12.5-mm, ST, Asphalt Pavement	381.000	TON	125.00		
0060	403-A015	9.5-mm, ST, Asphalt Pavement	599.000	TON	125.00		
0070	403-S001	Joint Sealant	2.000	MI	2,000.00		
0080	405-A001	Stone Matrix Asphalt, 12.5 mm Mixture	1,334.000	TON	150.00		
0090	405-A002	Stone Matrix Asphalt, 9.5 mm Mixture	1,199.000	TON	150.00		
0100	406-D001	Fine Milling of Bituminous Pavement, All Depths	3,547.000	SY	10.00		
0110	407-A001	Asphalt for Tack Coat	2,057.000	GAL	6.00		
0120	413-D002	Cleaning and Filling Joints	828.000	LF	15.00		
0130	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	924.000	LF	12.00		
0140	423-A001	Rumble Strips, Ground In	1.000	MI	4,000.00		
0150	501-D001	Expansion Joints, With Dowels	36.000	LF	65.00		
0160	501-G001	Dowels, Drilled and Installed	108.000	EA	65.00		
0170	503-A003	9" and Variable Reinforced Concrete Pavement, Broom Finish	111.000	SY	415.00		
0180	503-B001	Saw Cut, Longitudinal Joints	83.000	LF	37.00		
0190	503-C009	Saw Cut, 9-inch	108.000	LF	100.00		
0200	503-D001	Concrete for Base Repair	10.000	CY	515.00		
0210	503-E002	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted	42.000	EA	75.00		
0220	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	919.000	LF	25.00		
0230	606-E007	Guard Rail, Terminal End Section, Non-Flared	3.000	EA	2,500.00		
0240	618-A001	Maintenance of Traffic	1.000	LS	100,000.00		
0250	619-A1002	Temporary Traffic Stripe, Continuous White	10,890.000	LF	0.25		
0260	619-A2002	Temporary Traffic Stripe, Continuous Yellow	10,983.000	LF	0.25		

Pavement Restoration on I-10 at the State Line, known as Federal Aid Project No. IM-0010-01(151) / 107074301 in Jackson County.					Mallette Brothers Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$776,032.72					\$1,168,570.00		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	619-A3002	Temporary Traffic Stripe, Skip White	10,359.000	LF	0.25		
0280	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	32.000	SF	10.00		
0290	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	256.000	SF	10.00		
0300	619-E3001	Changeable Message Sign	2.000	EA	5,000.00		
0310	619-G4005	Barricades, Type III, Single Faced	48.000	LF	40.00		
0320	620-A001	Mobilization	1.000	LS	150,000.00		
0330	626-A003	6" Thermoplastic Traffic Stripe, Skip White	3,453.000	LF	1.00		
0340	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	3,630.000	LF	1.00		
0350	626-F002	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	3,661.000	LF	1.00		
0360	626-G002	Thermoplastic Detail Stripe, White	543.000	LF	2.00		
0370	627-K001	Red-Clear Reflective High Performance Raised Markers	69.000	EA	10.00		
0380	630-F006	Delineators, Guard Rail, White	24.000	EA	20.00		
0390	630-F007	Delineators, Guard Rail, Yellow	11.000	EA	20.00		
0400	907-420-A002	Undersealing Concrete Pavement	1,500.000	LBS	10.00		
0410	304-F001	3/4" and Down Crushed Stone Base	240.000	TON			
0420	304-F002	Size 610 Crushed Stone Base	240.000	TON			
0430	304-F003	Size 825B Crushed Stone Base	240.000	TON	50.00		