



Intersection Improvements at Highway 389 & South Jackson Street, known as Federal Aid Project No. STP-0116-00(014) / 106625301 in Chickasaw County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
<b>Roadway Items</b>					
0010	201-A001		1	Lump Sum	Clearing and Grubbing
0020	202-A001		1	Lump Sum	Removal of Obstructions
0030	202-B004		63	Square Yard	Removal of Asphalt Driveways, All Depths
0040	202-B007		748	Square Yard	Removal of Asphalt Pavement, All Depths
0050	202-B018		1	Each	Removal of Box Culvert
0060	202-B052		140	Square Yard	Removal of Concrete Driveways, All Depths
0070	202-B080		20	Square Yard	Removal of Concrete Sidewalk
0080	202-B092		551	Linear Feet	Removal of Curb, All Types
0090	202-B191		113	Linear Feet	Removal of Pipe, 8" And Above
0100	202-B240		1,000	Linear Feet	Removal of Traffic Stripe
0110	203-A001	(E)	1,270	Cubic Yard	Unclassified Excavation, FM, AH
0120	203-EX020	(E)	1,823	Cubic Yard	Borrow Excavation, AH, FME, Class B9
0130	203-G001	(E)	2,269	Cubic Yard	Excess Excavation, FM, AH
0140	206-A001	(S)	245	Cubic Yard	Structure Excavation
0150	206-B001	(E)	26	Cubic Yard	Select Material for Undercuts, Contractor Furnished, FM
0160	209-A005		4,129	Square Yard	Geotextile Stabilization, Type V, Non-Woven
0170	211-B001	(E)	1,076	Cubic Yard	Topsoil for Slope Treatment, Contractor Furnished
0180	213-C001		1	Ton	Superphosphate
0190	216-A001		2,486	Square Yard	Solid Sodding
0200	219-A001		60	Thousand Gallon	Watering [\$20.00]
0210	220-A001		1	Acre	Insect Pest Control [\$30.00]
0220	223-A001		2	Acre	Mowing [\$50.00]
0230	225-A001		2	Acre	Grassing
0240	225-B001		1	Ton	Agricultural Limestone
0250	225-C001		4	Ton	Mulch, Vegetative Mulch
0260	226-A001		2	Acre	Temporary Grassing
0270	230-B038		8	Each	Tree Planting, Flameleaf Sumac
0280	233-A003		32	Cubic Yard	Tree Bark Mulch, Type III
0290	234-A001		1,400	Linear Feet	Temporary Silt Fence
0300	234-D001		1	Each	Inlet Siltation Guard
0310	235-A001		60	Each	Temporary Erosion Checks
0320	237-A001		150	Linear Feet	Wattles, 12"

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0330	237-A002		150	Linear Feet	Wattles, 20"
0340	245-A001		18	Linear Feet	Silt Dike
0350	246-A001		52	Linear Feet	Sandbags
0360	247-A001		1	Each	Temporary Stream Diversion
0370	249-A001		8	Ton	Riprap for Erosion Control
0380	304-A002	(GY)	762	Cubic Yard	Granular Material, LVM, Class 3, Group C
0390	403-A003	(BA1)	414	Ton	12.5-mm, ST, Asphalt Pavement
0400	403-A006	(BA1)	386	Ton	19-mm, ST, Asphalt Pavement
0410	403-A015	(BA1)	658	Ton	9.5-mm, ST, Asphalt Pavement
0420	406-D001		5,835	Square Yard	Fine Milling of Bituminous Pavement, All Depths
0430	407-A001	(A2)	545	Gallon	Asphalt for Tack Coat
0440	503-C010		482	Linear Feet	Saw Cut, Full Depth
0450	601-A001	(S)	73	Cubic Yard	Class "B" Structural Concrete
0460	601-B001	(S)	26	Cubic Yard	Class "B" Structural Concrete, Minor Structures
0470	602-A001	(S)	13,057	Pounds	Reinforcing Steel
0480	603-CA011	(S)	256	Linear Feet	18" Reinforced Concrete Pipe, Class III
0490	603-CA026	(S)	352	Linear Feet	24" Reinforced Concrete Pipe, Class III
0500	603-CB003	(S)	4	Each	18" Reinforced Concrete End Section
0510	603-CB004	(S)	7	Each	24" Reinforced Concrete End Section
0520	603-CE008	(S)	40	Linear Feet	29" x 18" Concrete Arch Pipe, Class A III
0530	603-CF003	(S)	2	Each	29" x 18" Concrete Arch Pipe End Section
0540	604-A001		553	Pounds	Castings
0550	604-B001		127	Pounds	Gratings
0560	608-A001	(S)	7	Square Yard	Concrete Sidewalk, Without Reinforcement
0570	609-D012	(S)	1,690	Linear Feet	Combination Concrete Curb and Gutter Type 3A Modified
0580	614-A001	(S)	206	Square Yard	Concrete Driveway, Without Reinforcement
0590	617-A001		16	Each	Right-of-Way Marker
0600	618-A001		1	Lump Sum	Maintenance of Traffic
0610	619-A1001		1	Mile	Temporary Traffic Stripe, Continuous White
0620	619-A2001		1	Mile	Temporary Traffic Stripe, Continuous Yellow
0630	619-A4001		907	Linear Feet	Temporary Traffic Stripe, Skip Yellow
0640	619-A5001		2,370	Linear Feet	Temporary Traffic Stripe, Detail
0650	619-A6002		154	Linear Feet	Temporary Traffic Stripe, Legend
0660	619-D1001		24	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0670	619-D2001		581	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0680	619-G4001		162	Linear Feet	Barricades, Type III, Double Faced
0690	619-G5001		53	Each	Free Standing Plastic Drums
0700	619-G7001		3	Each	Warning Lights, Type "B"
0710	620-A001		1	Lump Sum	Mobilization
0720	626-C004		1	Mile	6" Thermoplastic Edge Stripe, Continuous White
0730	626-D004		907	Linear Feet	6" Thermoplastic Traffic Stripe, Skip Yellow
0740	626-E004		1	Mile	6" Thermoplastic Traffic Stripe, Continuous Yellow
0750	626-G002		1,028	Linear Feet	Thermoplastic Detail Stripe, White
0760	626-G003		2,057	Linear Feet	Thermoplastic Detail Stripe, Yellow
0770	626-H004		181	Square Feet	Thermoplastic Legend, White
0780	626-H005		416	Linear Feet	Thermoplastic Legend, White
0790	627-J001		95	Each	Two-Way Clear Reflective High Performance Raised Markers
0800	627-K001		13	Each	Red-Clear Reflective High Performance Raised Markers
0810	627-L001		236	Each	Two-Way Yellow Reflective High Performance Raised Markers
0820	630-A001		122	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.080" Thickness
0830	630-A003		150	Square Feet	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness
0840	630-B002		42	Square Feet	Interstate Directional Signs, Bolted Extruded Aluminum Panels, Ground Mounted
0850	630-C002		10	Linear Feet	Steel U-Section Posts, 2.0 lb/ft
0860	630-C003		230	Linear Feet	Steel U-Section Posts, 3.0 lb/ft
0870	630-D008		89	Linear Feet	Structural Steel Beams, W6 x 9
0880	630-E002		52	Pounds	Structural Steel Angles & Bars, 3" x 3" x 1/4" Angles
0890	630-G001		6	Each	End-Of-Roadway Markers, OM4-3, Post Mounted, Red
0900	630-G005		8	Each	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted
0910	630-K002		75	Linear Feet	Welded & Seamless Steel Pipe Posts, 3"
0920	699-A001		1	Lump Sum	Roadway Construction Stakes
0930	815-A002	(S)	197	Ton	Loose Riprap, Size 100
0940	815-E001	(S)	103	Square Yard	Geotextile under Riprap
<b>ALTERNATE GROUP AA NUMBER 1</b>					
0950	304-F001	(GT)	1,221	Ton	3/4" and Down Crushed Stone Base
<b>ALTERNATE GROUP AA NUMBER 2</b>					
0960	304-F002	(GT)	1,221	Ton	Size 610 Crushed Stone Base
<b>ALTERNATE GROUP AA NUMBER 3</b>					
0970	304-F003	(GT)	1,221	Ton	Size 825B Crushed Stone Base

<b>Line No.</b>	<b>Item Code</b>	<b>Adj Code</b>	<b>Quantity</b>	<b>Units</b>	<b>Description [Fixed Unit Price]</b>
-----------------	------------------	-----------------	-----------------	--------------	---------------------------------------