

Call 02 Work necessary to install Median Barrier on MS 12 from West of Eckford Drive to Russell Street, known as Federal Aid Project No. HSIP-0018-03(024) / 106863303 in Oktibbeha County.

- Q1. 1. Pay item 637-A013 shows a quantity of 5 pull box enclosures. Sheet No. 26 shows a quantity of 1 for the same pay item. On Sheet No. 3004 and Sheet No. 3007, one type 4 pull box enclosure per page. Please clarify. 2. Sheet No. 3004 shows a Type 5 pull box enclosure on the east side of Highway 12 at the intersection of Highway 12 and Russell Street. On Sheet No. 3007 at the same intersection in the same location of the Type 5, a Type 4 is shown to be installed. Which type of pull box is to be installed at this location?
- A1. 1. Pay Item 637-A013, Type 4 Pullbox has a quantity of 5. This quantity is correct. There are 4 signalized intersections for this project. Due to space constraints, we are using Type 4 pullboxes for the signals on this project, plus 1 Type 4 pullbox for ITS cable. The Signal pullboxes are noted on the signal sheets TSI-1, TSI-2, TSI-3, and TSI-4, The Type 4 pullbox for ITS cable is shown on ITS 2 between Montgomery and Blackjack/Spring St. 2. Pay Item 637-A015, Type 5 Pullbox has a quantity of 7. This quantity is correct. There are 2 new Type Pullboxes shown on ITS-1 (p. 3003) (plus one existing pullbox installed on Phase 1). There are 5 Type 5 pullboxes to be installed on ITS-2 (p. 3004). There is an error on ITS 5 (p. 3007). The pullbox shown on this sheet in the southeast quadrant of the Intersection of MS 12 at Stone Blvd. nearest the MSU campus, is shown as a Type 4 pullbox. This is an error, and will be clarified in an upcoming addendum. This should be a Type 5 pullbox—the same as shown on ITS-2 (p. 3004). It does not affect the summary of quantities, which is correct.
- Q2. How does the 3,053 LF of 18" Milling for the Slotted curb as shown in addendum 1 get paid?
- A2. It will be paid under pay item 406-A002.
- Q3. Drawing TS-5 shows the asphalt to be removed 18" wide and down to the concrete pavement under the special curb. Is this the intent?
- A3. No, it will be removed to a depth of approximately 2 inches.