

**SECTION 905 -- PROPOSAL (CONTINUED)**

I (We) hereby certify by execution of the Section 905 proposal below, that all certifications, disclosures and affidavits incorporated herein are deemed to be duly executed in the aggregate, fully enforceable and binding upon delivery of the bid proposal. I (We) further acknowledge that this certification shall not extend to the bid bond or alternate security which must be separately executed for the benefit of the Commission. This signature does not cure deficiencies in any required certifications, disclosures and/or affidavits. I (We) also acknowledge the right of the Commission to require full and final execution on any certification, disclosure or affidavit contained in the proposal at the Commission's election upon award. Failure to so execute at the Commission's request within the time allowed in the Standard Specifications for execution of all contract documents will result in forfeiture of the bid bond or alternate security.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO.   1   DATED   10/18/2017   ADDENDUM NO.   3   DATED   11/21/2017    
 ADDENDUM NO.   2   DATED   11/7/2017   ADDENDUM NO.            DATED           

Number	Description
1	Postponed; Amendment EBS Download Required.
2	Revised Advertisement; Revised NTB No. 416; Documents in SP 907-242-1 has been Revised; Revised or Added Plan Sheet Nos.1-2, 28-30, 32-35, 39-40, 43, 57, & 77; Amendment EBS Download Required.
3	Revise Sections 00 91 13, 10 56 13, and 10 56 30 of 907-242-1; Revise Plan Sheet Nos.2 and 33; Amendment EBS Download Required.

TOTAL ADDENDA:   3    
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE \_\_\_\_\_

\_\_\_\_\_  
 Contractor

BY \_\_\_\_\_

Signature

TITLE \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY, STATE, ZIP \_\_\_\_\_

PHONE \_\_\_\_\_

FAX \_\_\_\_\_

E-MAIL \_\_\_\_\_

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of \_\_\_\_\_ and the names, titles and business addresses of the executives are as follows:

\_\_\_\_\_  
 President Address

\_\_\_\_\_  
 Secretary Address

\_\_\_\_\_  
 Treasurer Address

The following is my (our) itemized proposal.

BWO-5231-51(001)/ 503006301000 & LWO-5001-51(008)/ 503006302000

Newton County(ies)

**MISSISSIPPI DEPARTMENT OF TRANSPORTATION**

**ADDENDUM No. 3  
DOCUMENT 00 91 13-C**

**DATE:** NOVEMBER 17, 2017

**PROJECT:** DISTRICT FIVE WAREHOUSE AT NEWTON, NEWTON COUNTY,  
MISSISSIPPI

**PROJECT NUMBERS:** BWO-5231-51(001) 503006  
LWO-5001-51(008) 503006

PART 1 - GENERAL

1.01 DESCRIPTION

- A. Bidders are hereby advised that the following changes are to be made to this Contract. Addendum No. Three contains 1 page plus 4 pages for a total of 5 pages and attached 1 Drawing as listed below.

1.02 SPECIFICATIONS

- A. Section 10 56 13 – Metal Storage Shelving, has been revised to remove specific shelving width from Parts Room 105 shelving, to remove model prefixes from bin storage, and to revise battery rack model number. Delete Section 10 56 13 – Metal Storage Shelving and replace with attached Section 10 56 13 – Metal Storage Shelving with Revised date of 11-17-2017 (2 pages).
- B. Section 10 56 30 – Pallet Storage System, dimensions of pallet storage system components have been revised, pallet supports have been removed, and single entry tire rack model has been revised. Delete Section 10 56 30 – Pallet Storage System and replace with Section 10 56 30 – Pallet Storage System with Revised date of 11-17-2017 (2 pages).

1.03 DRAWINGS

- A. Working No. A400, revised reference to metal rebounding bollard specification section. Delete Working No. A400 and replace with Working No. A400 with Revision 2 dated 11-17-2017.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION

SECTION 10 56 13

METAL STORAGE SHELVING

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Metal Shelving, Bin Storage, Axle Racks, Battery Racks and Safety Cabinets as show on the Drawings.

1.02 SUBMITTALS

- A. Submit manufacturer's technical data and installation instructions for each material and component part, including data substantiating that materials comply with requirements.

PART 2 - PRODUCTS

2.01 ACCEPTABLE MANUFACTURERS

- A. Equivalent products by the following manufacturers are acceptable:
  - 1. Lyon Metal Products, Aurora, IL. Tel. (603) 892-8941.
  - 2. Eagle Manufacturing Company, Wellsburg, WV. Tel. (304) 737-3171.
  - 3. Penco Products Inc., Oaks, PA. Tel. (610) 666-0500.
  - 4. Stanley Storage Systems, Allentown, PA. Tel. (800) 523-9462.
  - 5. Global Industrial Suppliers
- B. Substitutions shall fully meet or exceed the specified requirements may be considered under provisions of Section 01 25 00 - Substitution Procedures and Section 01 60 00 - Product Requirements. .

2.02 STORAGE SHELVING,

- A. Storage Shelving: Equal to Penco Products Closed Clip Heavy Duty Steel Shelving Unit variable widths, 24 inches deep, and 87 inches high with 6 shelves (e.g. Item# 652110 from Global Industrial Suppliers). Quantity: Supply units of varying widths to align all walls in Parts Room 105 as show on Drawings.
- B. Bin Storage: Equal to Western Pacific Bin Storage Racks as supplied by Global Industrial Suppliers. Shelves to be 36 inches W by 18 inches D by 39 inches H (e.g. Item# 603436 per Global Industrial Suppliers). Color of bins to be selected from full range of colors. Units located as shown on Drawings in Warehouse area. Quantities:
  - 1. 603436 24(G4) and 12(I4) 10 units
  - 2. 603438 48(G4) 5 units
  - 3. 603435 30(H4) 5 units
- C. Axle Racks: Equal to Jarke Brand model CR-7, height 7 feet, arm length 16 inches, capacity per arm 1000 pounds, number of arms: 24, base length: 45 inches, capacity per unit: 24,000 pounds.. Quantity (8) required 4 pair back to back as indicated on the Drawings.
- D. Battery Racks: Equal to Western Pacific, 64 capacity per rack, as supplied by Global Industrial Suppliers (#B485961). Quantity of two (2) racks.

E. Finish: Manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.

1. Color: Color to be selected from standard color chart by Project Engineer / MDOT Architect. Refer to Section 09 05 15 – Color Design for color selected.

## 2.03 SAFETY CABINET

A. Safety Cabinet: Equal to Eagle Manufacturing 90 Gallon Tower™ Safety Cabinet model 1992LEGS. Cabinets shall meet OSHA, NFPA Code 30 and FM approval. Part of Secure Storage on drawings. Quantity of two (2) cabinets.

1. Shelves: 2 shelves 30 inches deep.
2. Legs: 4 inches high.
3. Finish Color: Yellow.
4. Dimensions: 43 inches wide by 34 inches deep by 69 inches high.
5. Door Style: 2 manual close.

## PART 3 - EXECUTION

### 3.01 INSTALLATION

- A. Install units plumb and level, in locations and with mountings as shown.
- B. Securely attach all components together in accordance with manufacturer's installation instructions.
- C. Securely attach units to adjacent units and to wall as required to not move or fall.

### 3.02 CLEANING AND PROTECTION

- A. At completion of installation, clean surfaces in accordance with manufacturer's instructions. Protect units from damage until acceptance by Owner.

END OF SECTION

SECTION 10 56 30 PALLET STORAGE SYSTEM

PART 1 - GENERAL

1.01 SUMMARY

- A. Section Includes: Metal pallet storage system and tire storage racks as shown on the Drawings.
- B. Related Sections: Section 09 05 15 – Color Design.

1.02 ACTION SUBMITTALS

- A. Product Data: Manufacturer's technical data and installation instructions for each material and component part, including data substantiating that materials comply with requirements.
- B. Color Charts: For (3 copies) each exposed product.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

- A. Drawings and Specifications are based on products manufactured by Interlake Material Handling and Nashville Wire Products. Local supplier is MSC Industrial Supply Co., Jackson, MS. Tel. (800) 844-3971.
- B. Equivalent products by the following manufacturers are acceptable:
  - 1. C & H Distributors, LLC, Milwaukee, WI Tel. (800) 558-9966.
  - 2. Penco Products Inc., Oaks, PA. Tel. (610) 666-0500.
  - 3. Wireway / Husky, Denver, NC. Tel. (800) 438-5629.
  - 4. Western Pacific (Tire Rack Manufacturer)
  - 5. Ohio Tire Racks (Tire Rack Manufacturer)
  - 6. Ridg-U-Racks (Tire Rack Manufacturer)
- C. Substitutions that fully meet or exceed the specified requirements may be considered under provisions of Section 01 25 00 - Substitution Procedures and Section 01 60 00 - Product Requirements.

2.02 PALLET STORAGE SYSTEM

- A. Pallet Rack Upright: Pre-finished metal columns and braces complete with required accessories and hardware, Product No. SF4-4214, 45,000 lbs. capacity, 14'-0" high, by 42 inches deep.
- B. Pallet Rack Beam: Pre-finished metal beams complete with required accessories and hardware, Product No, 2SB4-120-242, 7,000 lbs. capacity, 10'-0" wide by 42 inches deep.
- C. Welded Wire Decking: Galvanized metal welded wire decking complete with required accessories and hardware, 3000 lbs. capacity (min), 42 inches by 58 inches.

- D. Quantity: Furnish sixty-eight (68) 14'-0" H by 10'-0" W by 42 inches D units as specified. Each unit will have two (2) uprights, six (6) beams, and wire decking complete with all accessories and hardware for each of the 68 units.
- E. Finish: Manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.
  - 1. Color will be selected from standard color chart by Project Engineer / MDOT Architect. Refer to Section 09 05 15 – Color Design for color selected.

### 2.03 TIRE RACK STORAGE

- A. Two (2) Tier Double Entry Tire Racks, 60 inches W by 42 inches D by 60 inches H, Base Unit R2-2DES (B486014) with Add On Units R2-2DEA (B486018) as manufactured by Western Pacific and supplied by Global Industries. Quantity of ten (10) double entry units as shown on Drawings.
- B. Two (2) Tier Single Entry Truck Tire Racks, 60 inches W by 33 inches D by 96 inches H, 2-SEST-5 (B486023) as manufactured by Western Pacific and supplied by Global Industries. Quantity of eleven (11) single entry units as shown on the Drawings.

## PART 3 - EXECUTION

### 3.01 INSTALLATION

- A. Install units plumb and level, in locations and with mountings as indicated or as directed by the Project Engineer.
- B. Securely attach all components together in accordance with manufacturer's installation instructions.
  - 1. Securely fasten units to adjacent units and to wall or floor as required so that units will not move or fall.
- C. Repair and refinish damaged products. Restore finishes so there is no evidence of corrective Work. Return items to shop that cannot be satisfactorily repaired or refinished in field, make required alterations and refinish entire unit, or provide new units, at Contractor's option.

### 3.02 CLEANING AND PROTECTION

- A. At completion of installation, clean surfaces in accordance with manufacturer's instructions.
- B. Protect units from damage until acceptance by Owner.

END OF SECTION

STATE	PROJECT NO.
MISS.	BWO-5231-51(001)
MISS.	LWO-5001-51(008)

**Symbols Legend**

**Index of Drawings**

- GENERAL -		
A000	Cover Sheet	1
A001	Index of Drawings/ Materials Referencing	2
A002	Construction Types	3
- CIVIL -		
C00.1	General Notes & Index of Drawings	4
C00.2	Summary of Quantities	5
C01.0	Existing Conditions	6
C02.0	Site Demolition Plan	7
C03.0	Site Demolition Plan	8
C04.0	Site Grading & Drainage Plan	9
C05.0	Site Erosion Control Plan	10
C06.0	Site Utility Plan	11
C06.1	Site Utility Plan	12
C07.0	Site Paving Plan	13
C08.0	Concrete Joint Layout Plan	14
C09.0	Site Striping & Signage Plan	15
C10.0	Erosion Control Details	16
C11.0	Sanitary Sewer Details	17
C11.1	Sanitary Sewer Details	18
C12.0	Water Details	19
C13.0	Pavement Details & Typical Section Details	20
ECD-1	Typical Temporary Erosion/ Sediment Control Applications	21
ECD-2	Details of Sediment Barrier Applications	22
ECD-3	Details of Silt Fence Installation	23
ECD-4	Ditch Check Structures, Typical Applications and Details	24
ECD-6	Details of Erosion Control - Wattle Ditch Check	25
ECD-16	Stabilized Construction Entrance	26
ECD-21	Details of Erosion Control Sandbag Ditch Check	27
- ARCHITECTURAL -		
A200	Floor Plan	28
A201	Large Scale Plans	29
A210	Reflected Ceiling Plan	30
A220	Roof Plan	31
A300	Exterior Elevations	32
A400	Building Sections	33
A401	Section Details	34
A600	Doors & Windows	35
A610	Interior Elevations	36
- STRUCTURAL -		
S001	Structural Notes and Drawing Index	37
S002	Structural Quality Assurance Plan	38
S200	Foundation Plan	39
S210	Mezzanine Framing Plan	40
S220	Roof Framing Plan	41
S300	Foundation Sections and Details	42
S301	Foundation Sections and Details	43
S302	Foundation Sections and Details	44
S303	Foundation Sections and Details	45
S400	Mezzanine Sections and Details	46
S401	Mezzanine Sections and Details	47
- PLUMBING -		
P100	Overall First Level Plumbing Plan	48
P200	Partial First Level Plumbing Plan	49
P300	Plumbing Schedules, Notes, and Legend	50
P400	Plumbing Details	51
- MECHANICAL -		
M100	Overall First Level HVAC Plan	52
M200	Partial Large Scale HVAC Plan	53
M300	Mechanical Schedules, Notes & Legend	54
M400	Mechanical Details	55
- ELECTRICAL -		
E100	Electrical Site Plan	56
E101	Underground Telecommunications Service Entrance Riser Diagram	57
E200	Main Level Lighting Floor Plan	58
E201	Main Level Electrical Floor Plan, Power & Telecommunications	59
E202	Main Level Electrical Floor Plan, Special Systems	60
E203	Mezzanine Level Plan, Lighting, Telecom & Special Systems	61
E300	Power Riser Diagram Details	62
E301	Service Entrance Equipment Grounding & Exterior Lighting Control	63
E302	Lighting Details and Typical Condensing Unit Power Connections	64
E303	Circuitry Details	65
E304	Circuitry Notes and Typical Panel Details	66
E305	Door Access Control System Provisions	67
E306	Low Voltage Switching Schematic Wiring Diagram Type 1	68
E307	Low Voltage Switching Schematic Wiring Diagram Type 2	69
E308	Low Voltage Switching Schematic Wiring Diagram Type 3	70
E309	Low Voltage Switching Schematic Wiring Diagram Type 4	71
E310	Site Work Detail, Typical Ductbanks	72
E311	Site Work Detail, Flush with Grade Telecommunications Pull Box	73
E312	Typical Communications Systems Provisions	74
E313	Typical Communications Systems Provisions	75
E400	Panels Schedules	76
E401	Power Connections Schedule	77
E402	Lighting Fixtures Schedule	78
E403	Lighting Fixtures Schedule	79
E404	Lighting Fixtures Schedule	80
E405	Symbols	81
E406	Symbols	82
- CIVIL / MDOT STANDARDS -		
CL-1	Chain Link Fence Class I	6162
CLG-1	Chain Link Fence Gate	6168

**PROJECT TEAM**

**OWNER**  
Mississippi Department of Transportation

**CIVIL**  
**Neel-Schaffer, Inc**  
Project Manager: Danny Ryals, P.E., P.L.S.  
1022 Highland Colony Parkway, Suite 202  
Ridgeland, MS 39157  
Ph: (601) 898-3358  
Fax: (601) 898-8454  
Email : danny.ryals@neel-schaffer.com

**ARCHITECTURAL**  
**JBHM Architects**  
Project Manager: Mark Pipper  
308 E Pearl St Suite 300  
Jackson MS 39201  
Ph: 601 352 2699 x-1308  
Fax: 601 352 2693  
Email : mpipper@bhm.com

**STRUCTURAL**  
**Structural Design Group**  
Project Manager: Tom Schaeffer, PE  
220 Great Circle Road  
Nashville, TN 37228  
Ph: 615.255.5537  
Fax: 615.255.1486  
Email: toms@sdg-structure.com

**PLUMBING & MECHANICAL**  
**GSK Mechanical, Inc.**  
Project Mgr: Jason Kackley  
201 Park Court, Suite A  
Ridgeland, MS 39157  
Ph: 601.605.2930  
Fax: 844.483.3111  
Email: jkackley@gskmech.com

**ELECTRICAL**  
**Shultz & Wynne, P.A.**  
Project Mgr: Mike Wynne  
4523 Office Park Drive  
Jackson, MS 39206  
Ph: 601.982.3313  
Fax: 601.982.7685  
Email: mwynne@sweems.com

PS & E PLANS-DATE. 08/11/2017		
FMS CON. # 503006/ 301000		
503006/ 302000		
REVISIONS		
DATE	SHEET NO.	BY
8/29/17	28,29,35	CDJ
9/27/17	5,15,20	DMR
10/25/17	1-2,28-30,32-35,39-40,43,57,77	CJ/MW/TS
11/17/17	33	CDJ

C:\Users\jones\Documents\16051.00 MDOT Newton Central R16\_chip\_local\_test.rvt








MISSISSIPPI DEPARTMENT OF TRANSPORTATION  
DISTRICT 5 WAREHOUSE  
NEWTON  
Index of Drawings/ Materials  
Referencing


BWO-5231-51(001) &  
LWO-5001-51(008)  
COUNTY: NEWTON

FILENAME: JBHM P.N. 16051.00  
DESIGN TEAM CJ/ NW/ MP CHECKED NW DATE 08/11/2017




WORKING NUMBER	<b>A001</b>
SHEET NUMBER	<b>2</b>


STATE	PROJECT NO.
MISS.	BWO-5231-51(001)
MISS.	LWO-5001-51(008)




1 Building Section  
1/8" = 1'-0"




2 Building Section  
3/16" = 1'-0"




3 Building Section  
3/16" = 1'-0"




4 Dock Section  
1/4" = 1'-0"



5 Building Section  
1/8" = 1'-0"



6 Stair Section  
1/4" = 1'-0"



7 Exit Stair Section  
1/4" = 1'-0"



**JBHM**  
Architecture

MISSISSIPPI DEPARTMENT OF TRANSPORTATION DISTRICT 5 WAREHOUSE NEWTON Building Sections		
BWO-5231-51(001) & LWO-5001-51(008) COUNTY: NEWTON		
WORKING NUMBER <b>A400</b>	SHEET NUMBER <b>33</b>	DESIGN TEAM: C/J/NW/MP CHECKED: NW DATE: 08/11/2017