

Overlay approximately 5 miles of US 84 from the Chickasawhay River Bridge to Robbie Lane, known as Federal Aid Project No. NH-0015-02(120) / 107649301 in Wayne County.					Dunn Roadbuilders, LLC	Walters Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,615,034.00					\$3,665,394.00	\$4,086,949.25	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B050	Removal of Concrete Combination Curb & Gutter	225.000	LF	17.00	11.50	
0020	202-B059	Removal of Concrete Median & Island Pavement, All Depths	100.000	SY	17.00	57.00	
0030	202-B188	Removal of Pavement, All Types and Depths	3,345.000	SY	11.00	11.85	
0040	202-B240	Removal of Traffic Stripe	15,800.000	LF	1.00	1.15	
0050	304-F003	Size 825B Crushed Stone Base	6,100.000	TON	50.00	48.90	
0060	403-A004	19-mm, HT, Asphalt Pavement	1,200.000	TON	95.00	106.00	
0070	403-A013	9.5-mm, HT, Asphalt Pavement	19,100.000	TON	90.00	97.00	
0080	403-A015	9.5-mm, ST, Asphalt Pavement	1,820.000	TON	112.00	98.95	
0090	403-B010	9.5-mm, HT, Asphalt Pavement, Leveling	6,450.000	TON	91.00	100.00	
0100	406-A002	Cold Milling of Bituminous Pavement, All Depths	58,000.000	SY	1.45	6.75	
0110	407-A001	Asphalt for Tack Coat	44,500.000	GAL	3.65	3.00	
0120	423-A001	Rumble Strips, Ground In	17.000	MI	273.00	290.00	
0130	503-C010	Saw Cut, Full Depth	50.000	LF	22.00	11.50	
0140	503-E001	Tie Bars, No. 4 Deformed Drilled and Epoxied or Grouted	25.000	EA	22.00	20.80	
0150	609-D008	Combination Concrete Curb and Gutter Type 3A	225.000	LF	52.00	46.30	
0160	616-A004	Concrete Median and/or Island Pavement, 4-inch	100.000	SY	59.00	63.65	
0170	618-A001	Maintenance of Traffic	1.000	LS	79,000.00	61,000.00	
0180	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	
0190	619-A1001	Temporary Traffic Stripe, Continuous White	22.000	MI	654.00	695.00	
0200	619-A2001	Temporary Traffic Stripe, Continuous Yellow	26.000	MI	654.00	695.00	
0210	619-A3001	Temporary Traffic Stripe, Skip White	20.000	MI	654.00	695.00	
0220	619-A5001	Temporary Traffic Stripe, Detail	36,200.000	LF	0.11	0.12	
0230	619-A6002	Temporary Traffic Stripe, Legend	460.000	LF	0.30	0.30	
0240	620-A001	Mobilization	1.000	LS	96,000.00	62,000.00	
0250	626-A004	6" Thermoplastic Traffic Stripe, Skip White	11.000	MI	1,635.00	1,735.00	
0260	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	15.000	MI	3,270.00	3,470.00	

Overlay approximately 5 miles of US 84 from the Chickasawhay River Bridge to Robbie Lane, known as Federal Aid Project No. NH-0015-02(120) / 107649301 in Wayne County.					Dunn Roadbuilders, LLC	Walters Construction Co., Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$3,615,034.00					\$3,665,394.00	\$4,086,949.25	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	3,250.000	LF	0.80	0.85	
0280	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	18.000	MI	3,270.00	3,470.00	
0290	626-G002	Thermoplastic Detail Stripe, White	29,950.000	LF	1.10	1.15	
0300	626-G003	Thermoplastic Detail Stripe, Yellow	8,500.000	LF	1.10	1.15	
0310	626-H005	Thermoplastic Legend, White	280.000	LF	1.70	1.75	
0320	627-J001	Two-Way Clear Reflective High Performance Raised Markers	90.000	EA	4.40	4.65	
0330	627-K001	Red-Clear Reflective High Performance Raised Markers	2,360.000	EA	4.40	4.65	
0340	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	550.000	EA	4.40	4.65	