

Call 14 Bridge Preservation of Bridge No. 153.0B on SR 145, known as Federal Aid Project No. BR-0059-03(093) / 107399301 in Lauderdale County.

Q1. Could removal of the existing bridge deck by milling, up to 1 1/2" but no closer than 1/2" of existing reinforcing, be allowed prior to the hydrodemolition?

A1. According to subsection 907-202.01 of Special Provision, 907-202-1 Removal of Bridge Deck, "Rotomilling of the existing concrete deck prior to hydrodemolition will not be allowed."

Q2. There is a note in the plans calling for the drop slabs to be repaired to the dimensions in the original plans, but the For Information Only Plans in the plans set do not include the drop slab details. Could MDOT please provide the full superstructure details for the existing bridge?

A2. The information can be found at the link below:

<https://file-exchange.mdot.state.ms.us/dl/?f=bf6872ae485609378c776855e730f4da77ea7927>