

Overlay approximately 4 miles of US 90 from the Singing River Bridge to 14th Street, known as Federal Aid Project No. NH-0003-01 (195) / 107650301 in Jackson County.					Mallette Brothers Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,012,584.90					\$3,730,330.30		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	23.000	SY	100.00		
0020	202-B191	Removal of Pipe, 8" And Above	224.000	LF	20.00		
0030	202-B240	Removal of Traffic Stripe	29,195.000	LF	1.50		
0040	216-A001	Solid Sodding	107.000	SY	20.00		
0050	219-A001	Watering	2.000	KGAL	20.00		
0060	304-F003	Size 825B Crushed Stone Base	2,616.000	TON	45.00		
0070	403-A014	9.5-mm, MT, Asphalt Pavement	16,903.000	TON	91.50		
0080	403-B011	9.5-mm, MT, Asphalt Pavement, Leveling	9,245.000	TON	90.00		
0090	406-A002	Cold Milling of Bituminous Pavement, All Depths	221,225.000	SY	2.50		
0100	407-A001	Asphalt for Tack Coat	23,425.000	GAL	5.00		
0110	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	9,500.000	LF	8.00		
0120	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	224.000	LF	65.00		
0130	603-CB004	24" Reinforced Concrete End Section	2.000	EA	1,500.00		
0140	618-A001	Maintenance of Traffic	1.000	LS	150,000.00		
0150	618-B001	Additional Construction Signs	1.000	SF	10.00		
0160	619-A1001	Temporary Traffic Stripe, Continuous White	16.000	MI	750.00		
0170	619-A2001	Temporary Traffic Stripe, Continuous Yellow	16.000	MI	750.00		
0180	619-A3001	Temporary Traffic Stripe, Skip White	36.000	MI	750.00		
0190	619-A5001	Temporary Traffic Stripe, Detail	46,990.000	LF	0.10		
0200	619-A6001	Temporary Traffic Stripe, Legend	3,368.000	SF	0.20		
0210	619-A6002	Temporary Traffic Stripe, Legend	5,416.000	LF	0.20		
0220	626-A004	6" Thermoplastic Traffic Stripe, Skip White	18.000	MI	1,500.00		
0230	626-C004	6" Thermoplastic Edge Stripe, Continuous White	8.000	MI	3,000.00		
0240	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	8.000	MI	3,000.00		
0250	626-G002	Thermoplastic Detail Stripe, White	21,185.000	LF	1.00		
0260	626-G003	Thermoplastic Detail Stripe, Yellow	6,865.000	LF	1.00		

Overlay approximately 4 miles of US 90 from the Singing River Bridge to 14th Street, known as Federal Aid Project No. NH-0003-01 (195) / 107650301 in Jackson County.					Mallette Brothers Construction Company, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,012,584.90					\$3,730,330.30		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	626-H004	Thermoplastic Legend, White	1,904.000	SF	5.00		
0280	626-H005	Thermoplastic Legend, White	2,708.000	LF	1.50		
0290	627-K001	Red-Clear Reflective High Performance Raised Markers	2,986.000	EA	5.00		
0300	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	200.000	EA	5.00		
0310	640-A001	Vehicle Loop Assemblies	4,784.000	LF	12.00		
0320	907-899-A001	Railway-Highway Provisions	1.000	LS	20,000.00		