

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Tanner Construction Company, Inc.	N. L. Carson Construction Company, Inc.	Joe McGee Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,122,374.50	\$4,382,699.72	\$4,880,430.65
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	115,000.00	286,560.00	425,000.00
0020	201-B001	Clearing and Grubbing	1.000	ACRE	2,900.00	2,500.00	3,900.00
0030	202-B007	Removal of Asphalt Pavement, All Depths	5,138.000	SY	5.00	5.00	6.00
0040	202-B023	Removal of Bridge	3.000	EA	20,000.00	23,900.00	35,000.00
0050	202-B136	Removal of Guard Rail	870.000	LF	3.15	4.00	6.00
0060	202-B191	Removal of Pipe, 8" And Above	207.000	LF	8.45	8.00	17.00
0070	202-B226	Removal of Soil Cement Treated Base, All Depths	5,138.000	SY	1.75	4.00	6.70
0080	203-A001	Unclassified Excavation, FM, AH	10,786.000	CY	3.90	4.50	5.50
0090	203-EX010	Borrow Excavation, AH, FME, Class B17	16,731.000	CY	8.75	11.00	8.25
0100	203-G002	Excess Excavation, LVM, AH	5,193.000	CY	6.60	4.50	6.00
0110	206-A001	Structure Excavation	57.000	CY	17.00	15.00	22.00
0120	206-B001	Select Material for Undercuts, Contractor Furnished, FM	100.000	CY	41.50	40.00	90.00
0130	209-A005	Geotextile Stabilization, Type V, Non-Woven	4,550.000	SY	2.00	2.16	2.50
0140	213-C001	Superphosphate	3.000	TON	865.00	865.00	865.00
0150	216-A001	Solid Sodding	160.000	SY	4.00	4.50	4.50
0160	217-A001	Ditch Liner	2,000.000	SY	1.50	1.65	1.65
0170	219-A001	Watering	4.000	KGAL	20.00	20.00	20.00
0180	220-A001	Insect Pest Control	6.000	ACRE	30.00	30.00	30.00
0190	221-A001	Concrete Paved Ditch	10.000	CY	500.00	776.00	500.00
0200	223-A001	Mowing	6.000	ACRE	50.00	50.00	50.00
0210	225-A001	Grassing	6.000	ACRE	1,000.00	1,150.00	1,150.00
0220	225-B001	Agricultural Limestone	3.000	TON	100.00	100.00	100.00
0230	225-C001	Mulch, Vegetative Mulch	12.000	TON	200.00	225.00	225.00
0240	234-A001	Temporary Silt Fence	8,000.000	LF	2.75	3.50	3.50
0250	234-C001	Super Silt Fence	1,000.000	LF	9.35	10.00	12.00
0260	236-A008	Silt Basin, Type D	4.000	EA	1,700.00	2,700.00	4,000.00

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Tanner Construction Company, Inc.	N. L. Carson Construction Company, Inc.	Joe McGee Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,122,374.50	\$4,382,699.72	\$4,880,430.65
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	237-A002	Wattles, 20"	4,000.000	LF	3.75	4.00	5.50
0280	245-A001	Silt Dike	1,000.000	LF	8.50	8.50	10.00
0290	246-B001	Rockbags	200.000	EA	13.50	13.50	20.00
0300	249-A001	Riprap for Erosion Control	2,180.000	TON	61.70	70.00	65.00
0310	304-A006	Granular Material, LVM, Class 5, Group E	1,150.000	CY	32.80	42.25	55.00
0320	304-A011	Granular Material, LVM, Class 9, Group C	2,150.000	CY	8.40	16.50	15.00
0330	307-C004	6" Soil-Lime-Water Mixing, Class C	2,889.000	SY	4.20	3.50	3.50
0340	307-D001	Lime	39.000	TON	270.00	340.00	340.00
0350	307-S001	Bituminous Curing Seal	722.000	GAL	4.20	5.15	5.15
0360	403-A003	12.5-mm, ST, Asphalt Pavement	941.000	TON	112.00	114.00	115.00
0370	403-A006	19-mm, ST, Asphalt Pavement	954.000	TON	112.00	105.00	105.00
0380	406-A002	Cold Milling of Bituminous Pavement, All Depths	1,316.000	SY	12.80	14.88	15.00
0390	407-A001	Asphalt for Tack Coat	435.000	GAL	3.50	3.75	3.70
0400	408-A001	Asphalt for Prime Coat, Cut-Back MC-70	694.000	GAL	3.50	5.00	5.25
0410	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	360.000	LF	10.00	12.00	10.00
0420	501-E001	Expansion Joints, Without Dowels	172.000	LF	10.00	11.70	10.00
0430	502-A001	Reinforced Cement Concrete Bridge End Pavement	373.000	SY	195.00	180.00	250.00
0440	601-B001	Class "B" Structural Concrete, Minor Structures	3.000	CY	1,600.00	1,898.50	4,000.00
0450	601-B002	Class "C" Structural Concrete, Minor Structures	1.000	CY	1,600.00	2,398.50	3,850.00
0460	602-A001	Reinforcing Steel	88.000	LBS	13.00	1.74	1.00
0470	603-ALT006	24" Type A Alternate Pipe	48.000	LF	45.00	36.00	40.00
0480	603-CA026	24" Reinforced Concrete Pipe, Class III	8.000	LF	45.00	113.50	75.00
0490	603-CB004	24" Reinforced Concrete End Section	2.000	EA	850.00	797.00	800.00
0500	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	96.000	LF	45.00	53.60	45.00
0510	603-PA004	10' x 8' Precast Concrete Box Culvert	40.000	LF	2,250.00	1,422.00	1,500.00
0520	603-PB004	10' x 8' Precast Concrete Box Culvert End Section	2.000	EA	10,000.00	14,320.00	10,500.00

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Tanner Construction Company, Inc.	N. L. Carson Construction Company, Inc.	Joe McGee Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,122,374.50	\$4,382,699.72	\$4,880,430.65
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0530	605-AA001	Geotextile for Subsurface Drainage, Type III	98.000	SY	2.00	2.50	5.75
0540	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	176.000	LF	15.00	15.00	11.50
0550	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	10.000	LF	15.00	20.11	18.50
0560	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	6.000	CY	110.00	85.00	120.00
0570	606-B001	Guard Rail, Class A, Type 1	800.000	LF	19.00	19.00	19.00
0580	606-D022	Guard Rail, Bridge End Section, Type 1	8.000	EA	2,150.00	2,150.00	2,150.00
0590	606-E001	Guard Rail, Terminal End Section	8.000	EA	2,250.00	2,250.00	2,250.00
0600	615-A002	Concrete Bridge End Barrier, 33.5"	80.000	LF	45.00	45.00	46.00
0610	618-A001	Maintenance of Traffic	1.000	LS	25,000.00	23,762.00	90,000.00
0620	619-A1002	Temporary Traffic Stripe, Continuous White	11,800.000	LF	0.25	0.25	0.25
0630	619-A2002	Temporary Traffic Stripe, Continuous Yellow	6,600.000	LF	0.25	0.25	0.25
0640	619-A4001	Temporary Traffic Stripe, Skip Yellow	5,200.000	LF	0.25	0.25	0.25
0650	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	120.000	SF	7.50	12.54	12.00
0660	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	205.000	SF	7.50	6.27	6.00
0670	619-E3001	Changeable Message Sign	4.000	EA	5,000.00	7,524.00	7,200.00
0680	619-G4001	Barricades, Type III, Double Faced	96.000	LF	14.00	15.00	14.00
0690	619-G7001	Warning Lights, Type "B"	4.000	EA	135.00	131.00	125.00
0700	620-A001	Mobilization	1.000	LS	355,000.00	177,915.00	400,000.00
0710	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	5,900.000	LF	0.80	0.80	0.80
0720	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	2,600.000	LF	0.75	0.75	0.75
0730	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	3,300.000	LF	0.75	0.75	0.75
0740	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	40.000	EA	8.00	8.00	8.00
0750	630-F006	Delineators, Guard Rail, White	44.000	EA	18.00	18.00	18.00
0760	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	4.000	EA	75.00	75.00	75.00
0770	699-B001	Bridge Construction Stakes	1.000	LS	32,500.00	33,888.00	75,000.00
0780	815-A007	Loose Riprap, Size 300	2,921.000	TON	61.70	65.00	65.00

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Tanner Construction Company, Inc.	N. L. Carson Construction Company, Inc.	Joe McGee Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,122,374.50	\$4,382,699.72	\$4,880,430.65
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0790	815-E001	Geotextile under Riprap	3,501.000	SY	2.00	2.56	4.00
0800	815-F002	Sediment Control Stone	137.000	TON	58.60	80.00	70.00
0810	907-253-A001	Coir Fiber Baffle	206.000	LF	10.00	10.00	10.50
0820	304-F001	3/4" and Down Crushed Stone Base	450.000	TON			
0830	304-F002	Size 610 Crushed Stone Base	450.000	TON	59.20	51.00	55.00
0840	304-F003	Size 825B Crushed Stone Base	450.000	TON			
0850	308-A001	Cement	91.000	TON	195.00	225.00	225.00
0860	308-B002	Soil-Cement-Water Mixing, Optional Mixers, Base	8,561.000	SY	4.20	3.50	3.50
0870	308-S001	Bituminous Curing Seal	2,140.000	GAL	4.20	5.15	5.15
0880	311-A003	6" Processing Lime and Fly Ash Treated Course	8,561.000	SY			
0890	311-B001	Lime	64.000	TON			
0900	311-C002	Fly Ash, Class C or F	253.000	TON			
0910	311-S001	Bituminous Curing Seal	2,140.000	GAL			
0920	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	35.000	CY			80.00
0930	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	35.000	CY	57.50	45.00	
0940	501-K001	Transverse Grooving	2,420.000	SY	2.20	2.20	2.20
0950	803-B001	Conventional Static Pile Load Test	2.000	EA	5,000.00	5,000.00	5,000.00
0960	803-C003	16" x 16" Prestressed Concrete Piling	3,450.000	LF	45.00	52.50	45.00
0970	803-C004	18" x 18" Prestressed Concrete Piling	3,105.000	LF	55.00	62.00	52.50
0980	803-I002	PDA Test Pile, Concrete Pile	5.000	EA	10,000.00	7,690.00	7,500.00
0990	803-J001	Pile Restrike	4.000	EA	1,300.00	750.00	800.00
1000	804-A001	Bridge Concrete, Class AA	213.000	CY	800.00	802.00	1,000.00
1010	804-A004	Bridge Concrete, Class BD	718.000	CY	850.00	828.50	950.00
1020	804-C055	135' Prestressed Concrete Beam, Type BT-72	2,418.000	LF	140.00	183.00	135.00
1030	804-C084	60' Prestressed Concrete Beam, Type II+2	717.000	LF	95.00	125.00	96.00
1040	804-C121	80' Prestressed Concrete Beam, Type III	479.000	LF	115.00	129.00	113.00

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Tanner Construction Company, Inc.	N. L. Carson Construction Company, Inc.	Joe McGee Construction Company, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,122,374.50	\$4,382,699.72	\$4,880,430.65
Ref#	Item	Item Description	Item Qty	Units	1	2	3
1050	805-A001	Reinforcement	215,824.000	LBS	1.00	0.95	1.00
1060	813-A002	Concrete Railing, 32"	1,219.000	LF	45.00	45.00	46.00
1070	815-A007	Loose Riprap, Size 300	3,479.000	TON	61.70	65.00	65.00
1080	815-E001	Geotextile under Riprap	3,231.000	SY	2.00	2.56	4.00

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.				Century Construction Group, Inc.	Key, LLC		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51				\$4,898,970.46	\$5,164,108.69		
Ref#	Item	Item Description	Item Qty	Units	4	5	
0010	201-A001	Clearing and Grubbing	1.000	LS	82,004.49	29,700.00	
0020	201-B001	Clearing and Grubbing	1.000	ACRE	4,243.61	4,500.00	
0030	202-B007	Removal of Asphalt Pavement, All Depths	5,138.000	SY	7.81	3.30	
0040	202-B023	Removal of Bridge	3.000	EA	48,271.65	27,800.00	
0050	202-B136	Removal of Guard Rail	870.000	LF	6.48	6.00	
0060	202-B191	Removal of Pipe, 8" And Above	207.000	LF	12.40	16.80	
0070	202-B226	Removal of Soil Cement Treated Base, All Depths	5,138.000	SY	3.06	5.40	
0080	203-A001	Unclassified Excavation, FM, AH	10,786.000	CY	5.94	4.55	
0090	203-EX010	Borrow Excavation, AH, FME, Class B17	16,731.000	CY	13.96	11.00	
0100	203-G002	Excess Excavation, LVM, AH	5,193.000	CY	6.19	5.00	
0110	206-A001	Structure Excavation	57.000	CY	19.66	27.10	
0120	206-B001	Select Material for Undercuts, Contractor Furnished, FM	100.000	CY	109.52	64.70	
0130	209-A005	Geotextile Stabilization, Type V, Non-Woven	4,550.000	SY	2.16	2.15	
0140	213-C001	Superphosphate	3.000	TON	934.20	575.00	
0150	216-A001	Solid Sodding	160.000	SY	4.86	575.00	
0160	217-A001	Ditch Liner	2,000.000	SY	1.78	1.50	
0170	219-A001	Watering	4.000	KGAL	20.00	20.00	
0180	220-A001	Insect Pest Control	6.000	ACRE	30.00	30.00	
0190	221-A001	Concrete Paved Ditch	10.000	CY	859.68	783.75	
0200	223-A001	Mowing	6.000	ACRE	50.00	50.00	
0210	225-A001	Grassing	6.000	ACRE	1,242.00	1,750.00	
0220	225-B001	Agricultural Limestone	3.000	TON	108.00	100.00	
0230	225-C001	Mulch, Vegetative Mulch	12.000	TON	243.00	200.00	
0240	234-A001	Temporary Silt Fence	8,000.000	LF	3.78	2.40	
0250	234-C001	Super Silt Fence	1,000.000	LF	10.80	10.35	
0260	236-A008	Silt Basin, Type D	4.000	EA	2,432.98	2,500.00	

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Century Construction Group, Inc.	Key, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,898,970.46	\$5,164,108.69	
Ref#	Item	Item Description	Item Qty	Units	4	5	
0270	237-A002	Wattles, 20"	4,000.000	LF	4.32	5.00	
0280	245-A001	Silt Dike	1,000.000	LF	9.18	9.00	
0290	246-B001	Rockbags	200.000	EA	14.58	13.50	
0300	249-A001	Riprap for Erosion Control	2,180.000	TON	60.74	82.50	
0310	304-A006	Granular Material, LVM, Class 5, Group E	1,150.000	CY	70.12	56.35	
0320	304-A011	Granular Material, LVM, Class 9, Group C	2,150.000	CY	64.89	11.15	
0330	307-C004	6" Soil-Lime-Water Mixing, Class C	2,889.000	SY	3.78	3.50	
0340	307-D001	Lime	39.000	TON	367.20	340.00	
0350	307-S001	Bituminous Curing Seal	722.000	GAL	9.88	5.15	
0360	403-A003	12.5-mm, ST, Asphalt Pavement	941.000	TON	117.72	108.80	
0370	403-A006	19-mm, ST, Asphalt Pavement	954.000	TON	109.08	100.15	
0380	406-A002	Cold Milling of Bituminous Pavement, All Depths	1,316.000	SY	13.91	12.88	
0390	407-A001	Asphalt for Tack Coat	435.000	GAL	3.78	3.50	
0400	408-A001	Asphalt for Prime Coat, Cut-Back MC-70	694.000	GAL	5.40	5.00	
0410	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	360.000	LF	10.80	10.00	
0420	501-E001	Expansion Joints, Without Dowels	172.000	LF	55.24	26.15	
0430	502-A001	Reinforced Cement Concrete Bridge End Pavement	373.000	SY	207.96	258.00	
0440	601-B001	Class "B" Structural Concrete, Minor Structures	3.000	CY	1,620.00	1,644.00	
0450	601-B002	Class "C" Structural Concrete, Minor Structures	1.000	CY	1,620.00	1,220.00	
0460	602-A001	Reinforcing Steel	88.000	LBS	1.09	9.00	
0470	603-ALT006	24" Type A Alternate Pipe	48.000	LF	56.29	111.15	
0480	603-CA026	24" Reinforced Concrete Pipe, Class III	8.000	LF	102.72	370.80	
0490	603-CB004	24" Reinforced Concrete End Section	2.000	EA	1,016.35	1,243.00	
0500	603-CE002	22" x 13" Concrete Arch Pipe, Class A III	96.000	LF	68.59	85.20	
0510	603-PA004	10' x 8' Precast Concrete Box Culvert	40.000	LF	1,773.22	1,635.00	
0520	603-PB004	10' x 8' Precast Concrete Box Culvert End Section	2.000	EA	34,693.82	16,026.50	

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Century Construction Group, Inc.	Key, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,898,970.46	\$5,164,108.69	
Ref#	Item	Item Description	Item Qty	Units	4	5	
0530	605-AA001	Geotextile for Subsurface Drainage, Type III	98.000	SY	2.39	2.77	
0540	605-O002	4" Perforated Sewer Pipe for Underdrains, SDR 23.5	176.000	LF	14.17	43.15	
0550	605-P002	4" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	10.000	LF	23.07	43.15	
0560	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	6.000	CY	68.79	184.80	
0570	606-B001	Guard Rail, Class A, Type 1	800.000	LF	20.52	19.00	
0580	606-D022	Guard Rail, Bridge End Section, Type 1	8.000	EA	2,322.00	2,150.00	
0590	606-E001	Guard Rail, Terminal End Section	8.000	EA	2,430.00	2,250.00	
0600	615-A002	Concrete Bridge End Barrier, 33.5"	80.000	LF	49.81	45.00	
0610	618-A001	Maintenance of Traffic	1.000	LS	46,244.07	16,315.50	
0620	619-A1002	Temporary Traffic Stripe, Continuous White	11,800.000	LF	1.08	0.25	
0630	619-A2002	Temporary Traffic Stripe, Continuous Yellow	6,600.000	LF	1.08	0.25	
0640	619-A4001	Temporary Traffic Stripe, Skip Yellow	5,200.000	LF	1.08	0.25	
0650	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	120.000	SF	8.64	7.50	
0660	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	205.000	SF	8.64	7.50	
0670	619-E3001	Changeable Message Sign	4.000	EA	11,232.00	5,000.00	
0680	619-G4001	Barricades, Type III, Double Faced	96.000	LF	21.60	14.00	
0690	619-G7001	Warning Lights, Type "B"	4.000	EA	205.20	135.00	
0700	620-A001	Mobilization	1.000	LS	490,000.00	500,000.00	
0710	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	5,900.000	LF	0.92	0.80	
0720	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	2,600.000	LF	0.92	0.75	
0730	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	3,300.000	LF	0.92	0.75	
0740	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	40.000	EA	27.00	8.00	
0750	630-F006	Delineators, Guard Rail, White	44.000	EA	19.44	18.00	
0760	630-G005	Type 3 Object Markers, OM-3R or OM-3L, Post Mounted	4.000	EA	81.00	75.00	
0770	699-B001	Bridge Construction Stakes	1.000	LS	79,054.80	105,000.00	
0780	815-A007	Loose Riprap, Size 300	2,921.000	TON	60.74	80.35	

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.					Century Construction Group, Inc.	Key, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51					\$4,898,970.46	\$5,164,108.69	
Ref#	Item	Item Description	Item Qty	Units	4	5	
0790	815-E001	Geotextile under Riprap	3,501.000	SY	2.23	2.00	
0800	815-F002	Sediment Control Stone	137.000	TON	71.19	90.00	
0810	907-253-A001	Coir Fiber Baffle	206.000	LF	10.80	11.00	
0820	304-F001	3/4" and Down Crushed Stone Base	450.000	TON			
0830	304-F002	Size 610 Crushed Stone Base	450.000	TON	73.33	77.31	
0840	304-F003	Size 825B Crushed Stone Base	450.000	TON			
0850	308-A001	Cement	91.000	TON	243.00	225.00	
0860	308-B002	Soil-Cement-Water Mixing, Optional Mixers, Base	8,561.000	SY	3.78	3.50	
0870	308-S001	Bituminous Curing Seal	2,140.000	GAL	5.56	5.15	
0880	311-A003	6" Processing Lime and Fly Ash Treated Course	8,561.000	SY			
0890	311-B001	Lime	64.000	TON			
0900	311-C002	Fly Ash, Class C or F	253.000	TON			
0910	311-S001	Bituminous Curing Seal	2,140.000	GAL			
0920	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	35.000	CY	130.89		
0930	605-W003	Filter Material for Combination Storm Drain and/or Underdrains, Type C, FM	35.000	CY		110.00	
0940	501-K001	Transverse Grooving	2,420.000	SY	4.32	2.20	
0950	803-B001	Conventional Static Pile Load Test	2.000	EA	5,000.00	5,000.00	
0960	803-C003	16" x 16" Prestressed Concrete Piling	3,450.000	LF	61.00	63.00	
0970	803-C004	18" x 18" Prestressed Concrete Piling	3,105.000	LF	70.00	82.11	
0980	803-I002	PDA Test Pile, Concrete Pile	5.000	EA	8,528.04	8,520.00	
0990	803-J001	Pile Restrike	4.000	EA	500.00	1,184.00	
1000	804-A001	Bridge Concrete, Class AA	213.000	CY	800.00	857.00	
1010	804-A004	Bridge Concrete, Class BD	718.000	CY	750.00	1,021.00	
1020	804-C055	135' Prestressed Concrete Beam, Type BT-72	2,418.000	LF	151.00	210.00	
1030	804-C084	60' Prestressed Concrete Beam, Type II+2	717.000	LF	102.00	120.00	
1040	804-C121	80' Prestressed Concrete Beam, Type III	479.000	LF	135.00	140.00	

Bridge Replacement on SR 488 from SR 35 to Neshoba County Line, Bridge Nos. 4.1 & 7.5, known as Federal Aid Project No. BR-0524-00(008) / 101707301 in Leake County.				Century Construction Group, Inc.	Key, LLC		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,367,944.51				\$4,898,970.46	\$5,164,108.69		
Ref#	Item	Item Description	Item Qty	Units	4	5	
1050	805-A001	Reinforcement	215,824.000	LBS	1.04	1.15	
1060	813-A002	Concrete Railing, 32"	1,219.000	LF	49.81	45.00	
1070	815-A007	Loose Riprap, Size 300	3,479.000	TON	59.50	80.35	
1080	815-E001	Geotextile under Riprap	3,231.000	SY	2.23	2.30	