

Slide Repair on SR 555 approximately 3 miles North of Intersection US 61, known as Federal Aid Project No. STP-0155-00(006) / 106655301 in Adams County.					Riverside Construction Company, Inc.	Midway Construction, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,274,740.50					\$958,489.00	\$1,017,973.55	\$2,503,470.30
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	201-A001	Clearing and Grubbing	1.000	LS	15,000.00	45,000.00	200,500.00
0020	201-B001	Clearing and Grubbing	1.000	ACRE	2,000.00	10.00	5,500.00
0030	202-B007	Removal of Asphalt Pavement, All Depths	343.000	SY	2.50	7.00	60.00
0040	202-B088	Removal of Curb & Gutter, All Types	188.000	LF	10.00	8.00	12.00
0050	202-B116	Removal of Debris, LVM	200.000	CY	40.00	0.01	45.00
0060	202-B165	Removal of Inlets, All Sizes	1.000	EA	600.00	500.00	1,125.00
0070	202-B191	Removal of Pipe, 8" And Above	36.000	LF	10.00	20.00	62.50
0080	203-EX041	Borrow Excavation, AH, LVM, Class B9-6	21,240.000	CY	12.10	12.00	25.00
0090	203-F002	Channel Excavation, LVM	680.000	CY	10.00	0.01	20.00
0100	203-G002	Excess Excavation, LVM, AH	200.000	CY	10.00	0.01	60.00
0110	206-A001	Structure Excavation	20.000	CY	12.00	1.00	100.00
0120	209-A005	Geotextile Stabilization, Type V, Non-Woven	581.000	SY	2.50	1.75	3.75
0130	216-A001	Solid Sodding	9,680.000	SY	5.00	2.00	4.50
0140	219-A001	Watering	194.000	KGAL	20.00	20.00	20.00
0150	225-C001	Mulch, Vegetative Mulch	4.000	TON	400.00	500.00	400.00
0160	226-A001	Temporary Grassing	2.000	ACRE	1,250.00	1.00	1,250.00
0170	229-A001	Erosion Mat	713.000	SY	50.00	58.00	70.00
0180	234-A001	Temporary Silt Fence	3,750.000	LF	2.50	1.00	6.75
0190	234-D001	Inlet Siltation Guard	2.000	EA	400.00	100.00	400.00
0200	237-A002	Wattles, 20"	1,150.000	LF	5.00	8.00	5.00
0210	246-B002	Rockbags	150.000	LF	50.00	2.00	50.00
0220	249-A001	Riprap for Erosion Control	200.000	TON	65.00	85.00	115.00
0230	304-E005	Granular Material, LVM, Size 57	1,444.000	CY	75.00	75.00	103.75
0240	403-A002	12.5-mm, MT, Asphalt Pavement	63.000	TON	150.00	165.00	230.00
0250	403-A014	9.5-mm, MT, Asphalt Pavement	95.000	TON	156.00	165.00	230.00
0260	406-D001	Fine Milling of Bituminous Pavement, All Depths	534.000	SY	10.00	2.00	16.50

Slide Repair on SR 555 approximately 3 miles North of Intersection US 61, known as Federal Aid Project No. STP-0155-00(006) / 106655301 in Adams County.					Riverside Construction Company, Inc.	Midway Construction, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,274,740.50					\$958,489.00	\$1,017,973.55	\$2,503,470.30
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	601-B001	Class "B" Structural Concrete, Minor Structures	27.000	CY	1,000.00	800.00	1,700.00
0280	602-A001	Reinforcing Steel	751.000	LBS	1.50	3.00	6.00
0290	603-CA011	18" Reinforced Concrete Pipe, Class III	16.000	LF	33.00	60.00	135.00
0300	603-CA012	18" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets , Class B Bedding	112.000	LF	33.00	60.00	150.00
0310	603-CA016	18" Reinforced Concrete Pipe, Class IV, Class B Bedding, Rubber Type Gaskets	48.000	LF	36.00	60.00	155.00
0320	603-CA034	24" Reinforced Concrete Pipe, Class IV, Rubber Type Gaskets , Class B Bedding	168.000	LF	55.00	90.00	210.00
0330	603-CA063	36" Reinforced Concrete Pipe, Class V, Class B Bedding , Rubber Type Gaskets	288.000	LF	100.00	150.00	275.00
0340	603-CB003	18" Reinforced Concrete End Section	6.000	EA	750.00	700.00	1,770.00
0350	603-CB004	24" Reinforced Concrete End Section	1.000	EA	1,000.00	1,000.00	2,500.00
0360	603-CB006	36" Reinforced Concrete End Section	1.000	EA	1,600.00	2,000.00	5,000.00
0370	604-A001	Castings	4,400.000	LBS	2.00	2.00	4.65
0380	604-B001	Gratings	147.000	LBS	3.00	2.50	8.25
0390	604-C001	Precast Manhole, 48" Diameter	170.000	LF	250.00	255.50	800.00
0400	605-AA003	Geotextile for Subsurface Drainage, Type V, Non-Woven	2,327.000	SY	2.50	1.75	4.40
0410	605-BB001	Prefabricated Sheet Drain	335.000	SY	12.00	25.00	120.00
0420	605-O001	12" Perforated Sewer Pipe for Underdrains, SDR 35	339.000	LF	30.00	30.00	58.00
0430	605-O004	6" Perforated Sewer Pipe for Underdrains, SDR 23.5	377.000	LF	13.00	20.00	40.00
0440	605-P004	6" Non-perforated Sewer Pipe for Underdrains, SDR 23.5	109.000	LF	12.50	20.00	38.75
0450	605-W001	Filter Material for Combination Storm Drain and/or Underdrains, Type A, FM	54.000	CY	50.00	100.00	150.00
0460	605-W002	Filter Material for Combination Storm Drain and/or Underdrains, Type B, FM	354.000	CY	30.00	40.00	58.50
0470	605-Z006	Underdrain Appurtenances, Small Animal Guard	6.000	EA	150.00	20.00	655.00
0480	609-D013	Combination Concrete Curb and Gutter Type 3B	129.000	LF	50.00	31.25	60.00
0490	614-B001	Concrete Driveway, With Reinforcement	75.000	SY	100.00	91.25	120.00
0500	617-A001	Right-of-Way Marker	7.000	EA	350.00	1,103.00	335.00
0510	618-A001	Maintenance of Traffic	1.000	LS	3,600.00	12,976.00	100,500.00
0520	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	44.000	SF	6.00	8.00	5.00

Slide Repair on SR 555 approximately 3 miles North of Intersection US 61, known as Federal Aid Project No. STP-0155-00(006) / 106655301 in Adams County.					Riverside Construction Company, Inc.	Midway Construction, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,274,740.50					\$958,489.00	\$1,017,973.55	\$2,503,470.30
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0530	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	248.000	SF	5.50	8.00	5.50
0540	619-E1001	Flashing Arrow Panel, Type C	1.000	EA	1,500.00	3,900.00	1,500.00
0550	619-G4001	Barricades, Type III, Double Faced	36.000	LF	12.50	16.00	12.50
0560	619-G5001	Free Standing Plastic Drums	18.000	EA	38.00	39.00	38.00
0570	619-G7001	Warning Lights, Type "B"	2.000	EA	125.00	160.00	125.00
0580	620-A001	Mobilization	1.000	LS	30,000.00	40,000.00	302,500.00
0590	626-C003	6" Thermoplastic Edge Stripe, Continuous White	200.000	LF	25.00	7.50	20.00
0600	699-A001	Roadway Construction Stakes	1.000	LS	15,000.00	27,760.00	90,000.00
0610	815-A002	Loose Riprap, Size 100	1,500.000	TON	53.00	60.00	115.00
0620	815-A007	Loose Riprap, Size 300	920.000	TON	53.00	60.00	115.00
0630	815-E001	Geotextile under Riprap	1,639.000	SY	2.50	1.75	3.25
0640	815-F002	Sediment Control Stone	53.000	TON	50.00	60.00	100.00
0650	304-H001	3/4" and Down Crushed Stone Base, LVM	176.000	CY			
0660	304-H002	Size 610 Crushed Stone Base, LVM	176.000	CY	85.00	85.00	250.00
0670	304-H003	Size 825B Crushed Stone Base, LVM	176.000	CY			