

Scrub Seal & Overlay of approximately 5 miles of SR 584 from the Amite County Line to the Jct. of US 51, known as State Project No. MP-7584-57(002) / 306409301 in Pike County.					Barriere Construction Company, LLC	Dickerson & Bowen, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$995,431.14					\$904,847.00	\$972,635.78	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B009	Removal of Asphalt Pavement, Failed Areas	881.000	SY	10.00	35.00	
0020	202-B136	Removal of Guard Rail	150.000	LF	9.00	8.00	
0030	202-B240	Removal of Traffic Stripe	916.000	LF	3.75	3.00	
0040	304-A008	Granular Material, LVM, Class 6, Group D	1,701.000	CY	10.00	20.00	
0050	403-A006	19-mm, ST, Asphalt Pavement	218.000	TON	83.00	160.00	
0060	403-B012	9.5-mm, ST, Asphalt Pavement, Leveling	451.000	TON	85.00	104.00	
0070	406-D001	Fine Milling of Bituminous Pavement, All Depths	3,064.000	SY	2.50	7.52	
0080	407-A001	Asphalt for Tack Coat	4,908.000	GAL	3.50	3.25	
0090	411-A001	Ultra Thin Asphalt Pavement	3,666.000	TON	88.00	82.15	
0100	412-A001	Pre-Grinding	6,492.000	SF	3.25	3.25	
0110	503-C010	Saw Cut, Full Depth	1,357.000	LF	1.25	1.00	
0120	606-E005	Guard Rail, Terminal End Section, Flared	4.000	EA	3,100.00	2,500.00	
0130	618-A001	Maintenance of Traffic	1.000	LS	42,000.00	58,000.00	
0140	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	
0150	619-A1001	Temporary Traffic Stripe, Continuous White	15.000	MI	645.00	600.00	
0160	619-A2001	Temporary Traffic Stripe, Continuous Yellow	11.000	MI	645.00	600.00	
0170	619-A4002	Temporary Traffic Stripe, Skip Yellow	8.000	MI	645.00	600.00	
0180	619-A5001	Temporary Traffic Stripe, Detail	2,283.000	LF	0.25	0.20	
0190	619-A6002	Temporary Traffic Stripe, Legend	932.000	LF	1.50	1.00	
0200	620-A001	Mobilization	1.000	LS	77,500.00	100,000.00	
0210	626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	3.000	MI	1,800.00	1,500.00	
0220	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	5.000	MI	3,400.00	2,700.00	
0230	626-G002	Thermoplastic Detail Stripe, White	1,457.000	LF	1.25	1.00	
0240	626-G003	Thermoplastic Detail Stripe, Yellow	826.000	LF	1.25	0.95	
0250	626-H005	Thermoplastic Legend, White	1,472.000	LF	1.75	1.50	
0260	627-H002	Chip Seal Reflective Raised Markers. Two-Way Yellow	416.000	EA	1.25	0.65	

Scrub Seal & Overlay of approximately 5 miles of SR 584 from the Amite County Line to the Jct. of US 51, known as State Project No. MP-7584-57(002) / 306409301 in Pike County.					Barriere Construction Company, LLC	Dickerson & Bowen, Inc.	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$995,431.14					\$904,847.00	\$972,635.78	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	627-J001	Two-Way Clear Reflective High Performance Raised Markers	342.000	EA	5.75	5.00	
0280	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	441.000	EA	5.75	5.00	
0290	627-P001	Two-Way Blue Reflective High Performance Raised Markers	5.000	EA	20.00	15.00	
0300	630-F006	Delineators, Guard Rail, White	17.000	EA	22.00	18.00	
0310	907-414-A001	Scrub Seal	60,956.000	SY	2.75	2.15	
0320	907-606-PP007	Remove and Replace Guard Rail Blockouts	56.000	EA	50.00	45.00	
0330	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	6.00	193.00	
0340	907-626-C003	Thermoplastic Audible Edge Stripe	9.000	MI	7,100.00	5,900.00	
0350	304-H001	3/4" and Down Crushed Stone Base, LVM	297.000	CY			
0360	304-H002	Size 610 Crushed Stone Base, LVM	297.000	CY		126.50	
0370	304-H003	Size 825B Crushed Stone Base, LVM	297.000	CY	58.00		
0380	907-624-B003	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White, High Contrast	564.000	LF			
0390	907-624-C003	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow, High Contrast	282.000	LF			
0400	907-624-D001	6" Inverted Profile Thermoplastic Traffic Stripe, Continous Yellow, High Contrast	282.000	LF			
0410	628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White	564.000	LF	5.75	5.00	
0420	628-I002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	282.000	LF	5.75	5.00	
0430	628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	282.000	LF	5.75	5.00	