

Overlay approximately 8 miles of SR 13 from JCT SR 35 in Columbia to Jefferson Davis County Line, known as State project No. MP-7013-46(008) / 306410301 in Marion County.					Barriere Construction Company, LLC	Dunn Roadbuilders, LLC	W. E. Blain & Sons, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,102,148.28					\$1,995,120.00	\$2,234,118.75	\$2,264,562.45
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	75.000	LF	6.75	7.00	6.00
0020	202-B240	Removal of Traffic Stripe	4,996.000	LF	2.25	2.00	2.00
0030	304-A008	Granular Material, LVM, Class 6, Group D	4,677.000	CY	10.00	22.00	23.00
0040	403-B011	9.5-mm, MT, Asphalt Pavement, Leveling	7,881.000	TON	87.00	99.00	92.00
0050	406-D001	Fine Milling of Bituminous Pavement, All Depths	13,394.000	SY	1.25	4.00	4.90
0060	407-A001	Asphalt for Tack Coat	18,931.000	GAL	3.25	4.00	2.25
0070	411-A001	Ultra Thin Asphalt Pavement	8,486.000	TON	100.00	98.00	98.00
0080	412-A001	Pre-Grinding	4,560.000	SF	3.25	3.25	3.25
0090	423-A001	Rumble Strips, Ground In	15.000	MI	282.00	300.00	450.00
0100	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	75.000	LF	21.00	21.25	19.00
0110	618-A001	Maintenance of Traffic	1.000	LS	56,000.00	65,000.00	75,000.00
0120	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	10.00
0130	619-A1001	Temporary Traffic Stripe, Continuous White	31.000	MI	650.00	654.00	600.00
0140	619-A2001	Temporary Traffic Stripe, Continuous Yellow	8.000	MI	650.00	654.00	600.00
0150	619-A4002	Temporary Traffic Stripe, Skip Yellow	16.000	MI	650.00	654.00	600.00
0160	619-A5001	Temporary Traffic Stripe, Detail	7,066.000	LF	0.25	1.00	0.15
0170	619-A6001	Temporary Traffic Stripe, Legend	35.000	SF	1.50	1.00	1.00
0180	619-A6002	Temporary Traffic Stripe, Legend	2,116.000	LF	0.50	1.00	0.50
0190	620-A001	Mobilization	1.000	LS	66,500.00	100,000.00	210,000.00
0200	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	15.000	MI	2,900.00	3,052.00	2,800.00
0210	626-D003	6" Thermoplastic Traffic Stripe, Skip Yellow	8.000	MI	1,600.00	1,526.00	1,400.00
0220	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	4.000	MI	2,800.00	2,943.00	2,700.00
0230	626-G002	Thermoplastic Detail Stripe, White	5,360.000	LF	1.00	1.00	1.00
0240	626-G003	Thermoplastic Detail Stripe, Yellow	1,636.000	LF	1.00	1.00	0.95
0250	626-H004	Thermoplastic Legend, White	35.000	SF	21.00	22.00	20.00
0260	626-H005	Thermoplastic Legend, White	2,116.000	LF	2.00	2.00	1.50

Overlay approximately 8 miles of SR 13 from JCT SR 35 in Columbia to Jefferson Davis County Line, known as State project No. MP-7013-46(008) / 306410301 in Marion County.					Barriere Construction Company, LLC	Dunn Roadbuilders, LLC	W. E. Blain & Sons, Inc.
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,102,148.28					\$1,995,120.00	\$2,234,118.75	\$2,264,562.45
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	627-J001	Two-Way Clear Reflective High Performance Raised Markers	586.000	EA	5.50	6.00	5.00
0280	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	806.000	EA	5.50	6.00	5.00
0290	630-F006	Delineators, Guard Rail, White	96.000	EA	21.00	20.00	18.00
0300	907-606-PP007	Remove and Replace Guard Rail Blockouts	506.000	EA	50.00	49.00	45.00
0310	907-619-B001	Temporary Portable Rumble Strips	66.000	LF	6.25	25.00	110.00
0320	907-624-B003	6" Inverted Profile Thermoplastic Traffic Stripe, Continuous White, High Contrast	2,944.000	LF			
0330	907-624-C003	6" Inverted Profile Thermoplastic Traffic Stripe, Skip Yellow, High Contrast	1,472.000	LF			
0340	907-624-D001	6" Inverted Profile Thermoplastic Traffic Stripe, Continous Yellow, High Contrast	580.000	LF			
0350	628-H001	6" High Performance Cold Plastic Traffic Stripe, Continuous White	2,944.000	LF	5.50	6.00	5.00
0360	628-I002	6" High Performance Cold Plastic Traffic Stripe, Skip Yellow	1,472.000	LF	5.50	6.00	5.00
0370	628-J001	6" High Performance Cold Plastic Traffic Stripe, Continuous Yellow	580.000	LF	5.50	6.00	5.00