

Call 20 Overlay approximately 6 miles of SR 15 from SR 42 to Jones County Line, & approximately 6 miles of SR 42 from Perry County Line East, & 8 miles from SR 57 West & SR 63 from Neely Road to SR 42, known as State Project Nos. MP-6015-56(007) / 306434301, MP-6042-21(010) / 306434302, & MP-6063-21(017) / 306434303 in Perry & Greene Counties.

Q1. 1. What is the depth of the base repairs? 2. Will guardrail pads be completely overlaid?

A1. 1. Depth repair quantities were calculated on a milling depth of three (3”) inches. This will be the typical depth, but could vary depending on the particular area of removal. 2. Guardrail will not be replaced on the bridges and as such, the guardrail pads will be paved only on the roadway side of the rail as close as practical to the guardrail.

Q2. Should the milling pay item be 13,250 TON or 13,250 SY?

A2. See upcoming addendum.