

Intersection Improvements on Hwy 43 at Texas Flat Road, Kiln-Delisle Road, Benville Road, & Kiln-Waveland Cutoff, known as State Project No. SP-0032-01(022) / 106247301 in Hancock County.					JLB Contractors, LLC	Huey P Stockstill LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,526,875.17					\$1,514,614.00	\$1,621,719.70	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	201-A001	Clearing and Grubbing	1.000	LS	25,000.00	50,000.00	
0020	202-B188	Removal of Pavement, All Types and Depths	454.000	SY	8.00	14.00	
0030	202-B191	Removal of Pipe, 8" And Above	295.000	LF	17.50	14.00	
0040	203-A001	Unclassified Excavation, FM, AH	1,942.000	CY	7.00	14.00	
0050	203-EX018	Borrow Excavation, AH, FME, Class B7-6	1,182.000	CY	15.00	25.00	
0060	203-G001	Excess Excavation, FM, AH	111.000	CY	12.00	14.00	
0070	209-A005	Geotextile Stabilization, Type V, Non-Woven	5,427.000	SY	4.50	5.00	
0080	211-A001	Topsoil for Slope Treatment, From Right-of-Way	1,620.000	SY	7.50	14.00	
0090	213-C001	Superphosphate	3.000	TON	1,200.00	800.00	
0100	217-A001	Ditch Liner	275.000	SY	6.00	4.00	
0110	225-A001	Grassing	5.000	ACRE	2,500.00	2,500.00	
0120	225-B001	Agricultural Limestone	12.000	TON	1,000.00	200.00	
0130	225-C001	Mulch, Vegetative Mulch	8.000	TON	1,000.00	200.00	
0140	226-A001	Temporary Grassing	5.000	ACRE	1,500.00	1,200.00	
0150	234-A001	Temporary Silt Fence	2,000.000	LF	4.50	5.00	
0160	237-A002	Wattles, 20"	650.000	LF	6.00	10.00	
0170	249-A001	Riprap for Erosion Control	105.000	TON	90.00	105.00	
0180	403-A002	12.5-mm, MT, Asphalt Pavement	615.000	TON	120.00	108.00	
0190	403-A005	19-mm, MT, Asphalt Pavement	651.000	TON	125.00	108.00	
0200	403-A006	19-mm, ST, Asphalt Pavement	651.000	TON	125.00	108.00	
0210	403-A014	9.5-mm, MT, Asphalt Pavement	1,912.000	TON	125.00	108.00	
0220	406-A002	Cold Milling of Bituminous Pavement, All Depths	17,587.000	SY	2.00	2.00	
0230	407-A001	Asphalt for Tack Coat	679.000	GAL	9.50	8.00	
0240	503-C010	Saw Cut, Full Depth	4,906.000	LF	5.00	8.00	
0250	601-B001	Class "B" Structural Concrete, Minor Structures	2.000	CY	3,300.00	3,500.00	
0260	603-ALT003	18" Type A Alternate Pipe	20.000	LF	50.00	50.00	

Intersection Improvements on Hwy 43 at Texas Flat Road, Kiln-Delisle Road, Bennville Road, & Kiln-Waveland Cutoff, known as State Project No. SP-0032-01(022) / 106247301 in Hancock County.					JLB Contractors, LLC	Huey P Stockstill LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,526,875.17					\$1,514,614.00	\$1,621,719.70	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	603-ALT006	24" Type A Alternate Pipe	264.000	LF	52.00	65.00	
0280	603-CA027	24" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	184.000	LF	55.00	90.00	
0290	603-CA056	36" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	8.000	LF	100.00	250.00	
0300	603-CA077	48" Reinforced Concrete Pipe, Class III, Rubber Type Gaskets	20.000	LF	135.00	300.00	
0310	603-CB004	24" Reinforced Concrete End Section	4.000	EA	1,500.00	1,000.00	
0320	603-CB006	36" Reinforced Concrete End Section	1.000	EA	2,100.00	2,000.00	
0330	603-CB008	48" Reinforced Concrete End Section	1.000	EA	2,500.00	3,000.00	
0340	609-D003	Combination Concrete Curb and Gutter Type 2	524.000	LF	37.00	35.00	
0350	618-A001	Maintenance of Traffic	1.000	LS	41,160.00	150,000.00	
0360	619-A1002	Temporary Traffic Stripe, Continuous White	10,346.000	LF	0.50	0.10	
0370	619-A2002	Temporary Traffic Stripe, Continuous Yellow	15,506.000	LF	0.50	0.10	
0380	619-A6001	Temporary Traffic Stripe, Legend	280.000	SF	3.50	2.00	
0390	619-A6002	Temporary Traffic Stripe, Legend	593.000	LF	1.50	1.00	
0400	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	148.000	SF	20.00	15.00	
0410	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	664.000	SF	20.00	15.00	
0420	619-G4001	Barricades, Type III, Double Faced	84.000	LF	47.00	35.00	
0430	619-G4005	Barricades, Type III, Single Faced	48.000	LF	47.00	35.00	
0440	619-G7001	Warning Lights, Type "B"	6.000	EA	450.00	200.00	
0450	620-A001	Mobilization	1.000	LS	160,000.00	150,000.00	
0460	626-B003	6" Thermoplastic Traffic Stripe, Continuous White	1,478.000	LF	1.50	1.00	
0470	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	8,868.000	LF	1.25	1.00	
0480	626-E003	6" Thermoplastic Traffic Stripe, Continuous Yellow	15,506.000	LF	1.25	1.00	
0490	626-G002	Thermoplastic Detail Stripe, White	2,308.000	LF	2.00	1.50	
0500	626-G003	Thermoplastic Detail Stripe, Yellow	3,870.000	LF	2.00	1.50	
0510	626-H004	Thermoplastic Legend, White	280.000	SF	8.25	6.00	
0520	626-H005	Thermoplastic Legend, White	593.000	LF	2.50	2.00	

Intersection Improvements on Hwy 43 at Texas Flat Road, Kiln-Delisle Road, Bennville Road, & Kiln-Waveland Cutoff, known as State Project No. SP-0032-01(022) / 106247301 in Hancock County.					JLB Contractors, LLC	Huey P Stockstill LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,526,875.17					\$1,514,614.00	\$1,621,719.70	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0530	627-B001	Two-Way Clear Reflective Raised Markers	55.000	EA	10.00	5.00	
0540	627-K001	Red-Clear Reflective High Performance Raised Markers	51.000	EA	10.00	5.00	
0550	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	661.000	EA	9.50	5.00	
0560	630-A003	Standard Roadside Signs, Sheet Aluminum, 0.125" Thickness	45.000	SF	65.00	45.00	
0570	630-C003	Steel U-Section Posts, 3.0 lb/ft	65.000	LF	25.00	15.00	
0580	632-A007	Solid State Traffic Cabinet Assembly, Type III Cabinet, Type I Controller	1.000	EA	21,000.00	18,000.00	
0590	634-A548	Traffic Signal Equipment Pole, Type III(L), 30' Shaft, 65' & 65' Arm	1.000	EA	49,000.00	45,000.00	
0600	634-A623	Traffic Signal Equipment Pole, Type III(L), 30' Shaft, 65' & 75' Arm	1.000	EA	51,000.00	55,000.00	
0610	634-C006	Pole Foundations, Class "DS" Concrete	8.000	CY	1,200.00	900.00	
0620	634-D003	Slip Casing, 36" Diameter	30.000	LF	76.00	70.00	
0630	635-A059	Traffic Signal Head, Type 1	4.000	EA	1,300.00	1,000.00	
0640	635-A065	Traffic Signal Head, Type 2 FYA	2.000	EA	1,600.00	1,500.00	
0650	635-A070	Traffic Signal Head, Type 3	2.000	EA	1,500.00	1,500.00	
0660	635-A073	Traffic Signal Head, Type 4	2.000	EA	1,500.00	1,500.00	
0670	636-B018	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 8 Conductor	789.000	LF	4.00	2.50	
0680	636-B037	Electric Cable, Underground in Conduit, THHN, AWG #10, 3 Conductor	432.000	LF	4.00	2.50	
0690	636-B048	Electric Cable, Underground in Conduit, THHN, AWG #4, 3 Conductor	130.000	LF	7.00	5.00	
0700	637-A007	Pull Box Enclosure, Type 1, Tier 22	2.000	EA	1,200.00	700.00	
0710	637-A009	Pull Box Enclosure, Type 2, Tier 22	2.000	EA	1,300.00	1,000.00	
0720	637-A011	Pull Box Enclosure, Type 3, Tier 22	2.000	EA	1,500.00	1,000.00	
0730	637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	744.000	LF	4.50	2.50	
0740	637-D003	Traffic Signal Conduit, Underground Drilled or Jacked, Rolled Pipe, 3"	391.000	LF	18.50	18.00	
0750	639-B001	Optical Detector	3.000	EA	1,200.00	800.00	
0760	639-C001	Multimode Phase Selector	1.000	EA	4,500.00	3,000.00	
0770	639-E001	Optical Detector Cable	790.000	LF	3.50	2.50	
0780	640-A001	Vehicle Loop Assemblies	464.000	LF	12.00	10.00	

Intersection Improvements on Hwy 43 at Texas Flat Road, Kiln-Delisle Road, Benville Road, & Kiln-Waveland Cutoff, known as State Project No. SP-0032-01(022) / 106247301 in Hancock County.					JLB Contractors, LLC	Huey P Stockstill LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$1,526,875.17					\$1,514,614.00	\$1,621,719.70	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0790	640-B004	Shielded Cable, AWG #18, 4 Conductor	1,071.000	LF	3.00	2.00	
0800	640-C005	Loop Detector Amplifier, Card Rack Mounted, 4 Channel	1.000	EA	1,200.00	500.00	
0810	643-A003	Video Detection System, 1 Sensor, Type 2	3.000	EA	10,500.00	12,000.00	
0820	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS	2,600.00	7,000.00	
0830	653-B003	Street Name Sign, Type III	44.000	SF	42.00	35.00	
0840	699-A001	Roadway Construction Stakes	1.000	LS	35,000.00	30,000.00	
0850	304-F001	3/4" and Down Crushed Stone Base	2,868.000	TON			
0860	304-F002	Size 610 Crushed Stone Base	2,868.000	TON			
0870	304-F003	Size 825B Crushed Stone Base	2,868.000	TON	60.00	75.00	