

Call 04 Bridge Rehabilitation on US 98 at CNIC RR, [Bridge No. 78.3], known as Federal Aid Project No. BR-0014-01(058) / 106190301 in Pike County.

- Q1. The note on sheet 8002 under "Work To Be Performed During Bridge Closure" states that hydrodemolition and associated deck repairs can only be performed during a complete closure. Will MDOT consider allowing the Contractor to use nightly lane closures to perform full depth deck repairs associated with the existing joints prior to hydrodemolition and deck overlay work? All other full depth deck repairs discovered during the hydrodemolition process can be performed at the same time as the overlay using a complete bridge closure.
- A1. The drop slab repairs at the joints are expected to be performed with the hydrodemolition under the full bridge closure as indicated in the plans.