


STATE	PROJECT NUMBER	SHEET NO.
MISSISSIPPI	MP-1025-71(018)	1



DESIGN CONTROL		
_____ MPH = V (SPEED DESIGN)		
ADT (_____) = _____ : ADT (_____) = _____		
DHV = _____ : D = _____ % T = _____ %		
PERMITS ACQUIRED BY MDOT		
WETLANDS AND WATERS PERMITS		
	WATERS	WETLANDS
NATIONWIDE #14	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
NATIONWIDE (OTHER)*	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
GENERAL*	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
INDIVIDUAL (404)*	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
STORMWATER PERMIT <input checked="" type="checkbox"/>		
Y	REQUIRED, CNOI SUBMITTED BY MDOT (DISTURBED AREA = 5 ACRES)	
S	REQUIRED, SCNOI TO BE SUBMITTED BY CONTRACTOR (1 TO 4.99 ACRES)	
N	NO STORMWATER PERMIT REQUIRED (<1 ACRE)	
APPROVED BY: _____		

GENERAL INDEX

INCLUDED THIS PROJECT	BEGIN WITH SHEET
<input checked="" type="checkbox"/> ROADWAY	1
<input type="checkbox"/> PERMANENT SIGNS	1001
<input type="checkbox"/> TRAFFIC SIGNALS	2001
<input type="checkbox"/> ITS COMPONENTS	3001
<input type="checkbox"/> LIGHTING	4001
<input type="checkbox"/> (RESERVED)	5001
<input checked="" type="checkbox"/> ROADWAY STANDARD DWGS	6001
<input type="checkbox"/> BOX CULVERT STD. DRAWINGS (LRFD)	7001
<input type="checkbox"/> BOX CULVERT STD. DRAWINGS (STD. SPEC.)	7501
<input type="checkbox"/> BRIDGE	8001
<input type="checkbox"/> CROSS SECTIONS	9001

BRIDGE STRUCTURES REQ'D.

BOX BRIDGES REQ'D.

CONVENTIONAL SYMBOLS

COUNTY LINE	-----
TOWN CORPORATION LINE	-----
SECTION LINE	-----
EXISTING ROAD OR TRAVELED WAY	-----
PROPOSED ROAD OR TRAVELED WAY	-----
RAILROAD	-----
SURVEY LINE	-----
BRIDGES	-----

LENGTH OF ROADWAY	69,731 FT.	13.21 MI.
LENGTH OF BRIDGES	153 FT.	0.03 MI.
LENGTH OF PROJECT (NET)		13.18 MI.
LENGTH OF EXCEPTIONS		ML.
LENGTH OF PROJECT (GROSS)		13.18 MI.

EQUATIONS

LENGTH DATA

EXCEPTIONS

STATE OF MISSISSIPPI


MISSISSIPPI DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE OF PROPOSED STATE HIGHWAY STATE PROJECT NO. MP-1025-71(018)

S.R. 25 FROM ITAWAMBA COUNTY LINE TO NORTH OF HOLLY STREET TISHOMINGO COUNTY

FMS CON. NO. 306455/ 301000

SCALES		
PLAN	1 IN. =	100 FT.
PROFILE {	HOR. 1 IN. =	100 FT.
VERT.	1 IN. =	10 FT.
LAYOUT	1 IN. =	FT.



END OF PROJECT STA. 1647 + 95

BEGINNING OF PROJECT STA. 950 + 64

P S & E DATE: 4/21/2018	
APPROVED:	
DEPUTY EXECUTIVE DIRECTOR / CHIEF ENGINEER	
EXECUTIVE DIRECTOR	
MDOT MISSISSIPPI DEPARTMENT OF TRANSPORTATION	



STATE	PROJECT NO.
MISS.	MP-1025-71(018)

DESCRIPTION OF SHEET	REVISION DATE	WKG. NO.	SH. NO.
TITLE SHEET			1
DETAILED INDEX & GENERAL NOTES (1)			
DETAILED INDEX & GENERAL NOTES		DI-1	2
TYPICAL SECTION SHEETS (2)			
TYPICAL SECTION - MILL AND OVERLAY		TS-1	3
TYPICAL SECTION - CURB AND GUTTER		TS-1	4
QUANTITY SHEETS (2)			
SUMMARY OF QUANTITIES		SQ-1	5
SUMMARY OF QUANTITIES		SQ-2	6
SPECIAL DESIGN SHEETS (7)			
DETAIL OF CONSTRUCTION SIGNING		DSC-1	7
DETAIL OF CONSTRUCTION SIGNING		DSC-2	8
DETAIL OF CONSTRUCTION SIGNING		DSC-3	9
DETAIL OF CONSTRUCTION SIGNING		DSC-4	10
DETAIL OF CONSTRUCTION SIGNING		DSC-5	11
DETAIL OF CONSTRUCTION SIGNING		DSC-6	12
DETAIL OF CONSTRUCTION SIGNING		DSC-7	13
STANDARD DRAWINGS - ROADWAY SHEETS (12)			
PAVEMENT MARKING DETAILS FOR 2-LANE AND 4-LANE DIVEDED HIGHWAYS		PM-1	6051
PAVEMENT MARKING LEGEND DETAILS		PM-5	6055
PAVEMENT MARKING LEGEND DETAILS		PM-6	6056
TYPICAL PLACEMENT OF WARINING SIGNS & PAV'T MARKINGS AT R.R. - HWY GRADE CROSSINGS		PM-7	6057
2-WAY RAISED PAVEMENT MARKERS AT INTERSECTING ROADS (2-LANE)		PM-11	6061
RUMBLE STRIPES 2-LANE HIGHWAYS (ASPHALT LANES, 2-FT. OR WIDER ASPHALT SHOULDERS)		RS-1	6064
TRAFFIC CONTROL PLAN WITH FLAGGER (ONE-LANE CLOSURE OF TWO-WAY TRAFFIC)		TCP-1	6351
HIGHWAY SIGN AND BARRICADE DETAILS FOR CONSTRUCTION PROJECTS		TCP-8	6358
TRAFFIC CONTROL PLAN MOBILE OPERATIONS MULTILANE ROADS AND TWO-LANE ROADS		TCP-9	6359
TRAFFIC CONTROL PLANS UNEVEN PAVEMENT DETAILS		TCP-12	6362
TEMPORARY STRIPING FOR TRAFFIC CONTROL, 2-LANE AND 4-LANE DIVIDED HIGHWAYS		TCP-13	6363
TRAFFIC CONTROL DETAILS DRUM PLACEMENT AND SHOULDER CLOSURE		TCP-16	6366

GENERAL NOTES:

- (1) THE LOCATION AND SPACING OF SIGNS, SHOWN ON THE TRAFFIC CONTROL PLANS, ARE APPROXIMATE AND MAY BE ADJUSTED AS NECESSARY TO FIT FIELD CONDITIONS.
- (2) ALL TRAFFIC CONTROL DEVICES ON THIS PROJECT SHALL COMPLY WITH PART VI OF THE MUTCD (LATEST EDITION).
- (3) ALL PLASTIC DRUMS SHALL HAVE A BALLASTING COLLAR MADE FROM RECYCLED TRUCK TIRES OR OTHER SUITABLE MATERIAL.
- (4) THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING EXISTING STRUCTURES SUCH AS, BUT NOT LIMITED TO, PIPES, INLETS, APRONS, AND BRIDGES FROM DAMAGE WHICH MIGHT OCCUR DURING CONSTRUCTION. THE CONTRACTOR SHALL REPLACE OR REPAIR, AS DIRECTED BY THE ENGINEER, ANY STRUCTURES DAMAGED DURING THE LIFE OF THE CONTRACT. NO PAYMENT WILL BE MADE FOR REPLACEMENT OR REPAIR OF DAMAGED ITEMS.
- (5) FLUORESCENT ORANGE SHEETING SHALL BE USED ON ALL CONSTRUCTION AND TRAFFIC CONTROL SIGNS EXCEPT FOR THOSE DESIGNATED ON THE PLANS TO BE BLACK LEGEND AND BORDER ON WHITE BACKGROUND.
- (6) VEGETATIVE MATERIAL WILL BE REMOVED PRIOR TO PLACEMENT OF GRANULAR MATERIAL. THE COST OF WHICH SHALL BE ABSORBED IN OTHER BID ITEMS.
- (7) ROADWAY SIGNS THAT ARE IN CONFLICT WITH CONSTRUCTION OF THIS PROJECT SHALL BE REMOVED AND RELOCATED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER, THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.
- (8) REMOVAL OF RAISED PAVEMENT MARKERS THAT ARE IN CONFLICT WITH REQUIRED CONSTRUCTION IS NOT CONSIDERED A SEPARATE PAY ITEM. COST TO BE ABSORBED IN OTHER ITEMS BID.
- (9) WHERE MILLING IS REQUIRED, THE CONTRACTOR SHALL PROVIDE OUTLETS IN THE EXISTING SHOULDERS AT SUFFICIENT INTERVALS TO PREVENT POOLING OR STANDING WATER ON THE MILLED SURFACE, THE COST OF WHICH SHALL BE ABSORBED IN OTHER ITEMS BID.
- (10) TEMPORARY STRIPING SHALL CONFORM TO FINISHED STRIPE SPECIFICATIONS FOR ALIGNMENT, NEATNESS, AND STRAIGHTNESS.
- (11) ERECTION DATES ARE TO BE LEGIBLY WRITTEN IN BOLD, BLACK MARKINGS ON THE BACK OF ALL PERMANENT SIGNS WITH A PERMANENT MARKING STICK THAT IS WATERPROOF, FADE RESISTANT, AND MARKS ON WET OR DRY SURFACES.
- (12) ALL ADDENDA TO THESE PLANS WILL BE POSTED TO WWW.MDOT.MS.GOV UNDER THE PROPOSAL ADDENDA COLUMN. BIDDERS ARE ADVISED THAT HARD COPIES OF ANY ADDENDA FOR THIS PROJECT WILL NOT BE MAILED. IT IS THE BIDDER'S RESPONSIBILITY TO CHECK AND SEE IF ANY ADDENDA HAVE BEEN POSTED FOR THIS PROJECT.
- (13) WHERE A PAPER JOINT IS REQUIRED, A TAPER SHALL BE PLACED AT (3) THREE HORIZONTAL FEET PER EACH (1) VERTICAL INCH.

PS & E PLANS-DATE: 04/21/18		
FMS CON. # 306455/301000		
REVISIONS		
DATE	SHEET NO.	BY

REVISION

DATE

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

DETAILED INDEX & GENERAL NOTES

PROJ. NO.: MP-1025-71(018)
COUNTY: TISHOMINGO

FILENAME: 306455_SR25_TISH.dgn
DESIGN TEAM
CHECKED
DATE 2018-04-18

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

WORKING NUMBER
DI-1
SHEET NUMBER
2