

Bridge Repair on SR 15 over Potter Chitto Creek (Bridge No. 135.2), known as Federal Aid Project No. BR-0022-02(067) / 107640301 in Newton County.					Century Construction Group, Inc.	Gibson & Associates, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,144,883.45					\$1,929,312.98	\$2,052,819.94	\$2,128,676.65
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0010	202-B007	Removal of Asphalt Pavement, All Depths	67.000	SY	61.08	132.00	30.00
0020	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	566.000	LF	7.05	3.30	6.00
0030	202-B240	Removal of Traffic Stripe	770.000	LF	2.35	3.30	2.00
0040	203-EX040	Borrow Excavation, AH, LVM, Class B9	50.000	CY	46.41	44.00	110.00
0050	216-A001	Solid Sodding	30.000	SY	11.76	22.00	20.00
0060	219-A001	Watering	1.000	KGAL	20.00	20.00	20.00
0070	234-A001	Temporary Silt Fence	875.000	LF	5.29	4.95	7.50
0080	237-A002	Wattles, 20"	875.000	LF	5.88	5.50	5.00
0090	403-A002	12.5-mm, MT, Asphalt Pavement	15.000	TON	411.77	385.00	350.00
0100	403-A005	19-mm, MT, Asphalt Pavement	19.000	TON	411.77	385.00	250.00
0110	403-A014	9.5-mm, MT, Asphalt Pavement	74.000	TON	241.17	225.50	200.00
0120	404-A003	2" Cold Bituminous Pavement, Type Surface	20.000	SY	253.51	250.00	100.00
0130	406-A002	Cold Milling of Bituminous Pavement, All Depths	835.000	SY	11.27	38.50	10.00
0140	407-A001	Asphalt for Tack Coat	56.000	GAL	3.54	3.30	5.00
0150	503-C010	Saw Cut, Full Depth	93.000	LF	23.54	25.00	10.00
0160	606-B001	Guard Rail, Class A, Type 1	350.000	LF	27.06	23.10	23.00
0170	606-D022	Guard Rail, Bridge End Section, Type 1	4.000	EA	2,529.43	2,310.00	2,150.00
0180	606-E005	Guard Rail, Terminal End Section, Flared	4.000	EA	3,235.31	2,585.00	2,750.00
0190	618-A001	Maintenance of Traffic	1.000	LS	104,377.69	193,000.00	39,500.00
0200	619-A1002	Temporary Traffic Stripe, Continuous White	432.000	LF	5.88	2.20	5.00
0210	619-A2002	Temporary Traffic Stripe, Continuous Yellow	216.000	LF	5.88	2.20	5.00
0220	619-A4001	Temporary Traffic Stripe, Skip Yellow	108.000	LF	5.88	2.20	5.00
0230	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	32.000	SF	8.24	7.70	7.00
0240	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	232.000	SF	8.24	7.70	7.00
0250	619-G4001	Barricades, Type III, Double Faced	24.000	LF	18.82	17.60	16.00
0260	619-G7001	Warning Lights, Type "B"	2.000	EA	58.83	55.00	50.00

Bridge Repair on SR 15 over Potter Chitto Creek (Bridge No. 135.2), known as Federal Aid Project No. BR-0022-02(067) / 107640301 in Newton County.					Century Construction Group, Inc.	Gibson & Associates, Inc.	Key, LLC
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$2,144,883.45					\$1,929,312.98	\$2,052,819.94	\$2,128,676.65
Ref#	Item	Item Description	Item Qty	Units	1	2	3
0270	620-A001	Mobilization	1.000	LS	137,989.47	200,000.00	210,000.00
0280	626-C001	6" Thermoplastic Double Drop Edge Stripe, Continuous White	1,112.000	LF	11.76	5.50	10.00
0290	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	448.000	LF	11.76	5.50	10.00
0300	626-E002	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	216.000	LF	11.76	5.50	10.00
0310	627-D001	Two-Way Yellow Reflective Raised Markers	14.000	EA	47.06	55.00	40.00
0320	630-F006	Delineators, Guard Rail, White	22.000	EA	23.54	20.90	20.00
0330	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	2.000	EA	94.13	121.00	80.00
0340	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	2.000	EA	94.13	121.00	80.00
0350	699-A001	Roadway Construction Stakes	1.000	LS	15,867.99	15,000.00	34,500.00
0360	503-C001	Saw Cut, 1-inch	48.000	LF	24.36	5.00	20.00
0370	804-A009	Bridge Concrete, Substructure, Class AA	11.000	CY	1,013.96	9,300.00	4,450.00
0380	805-A001	Reinforcement	3,069.000	LBS	3.12	1.00	2.00
0390	808-A001	Joint Preparation	1,309.000	LF	5.88	5.50	5.00
0400	815-A007	Loose Riprap, Size 300	6,018.000	TON	77.44	83.60	94.00
0410	815-E001	Geotextile under Riprap	3,439.000	SY	5.63	3.03	3.35
0420	907-420-A001	Undersealing	264.000	LBS	7.36	6.88	15.00
0430	907-823-A001	Preformed Joint Seal, Type I	616.000	LF	29.41	27.50	25.00
0440	907-823-B001	Saw Cut, Type I	1,232.000	LF	9.41	8.80	8.00
0450	907-824-PP003	Bridge Repair, Bridge Deck Crack Sealing, Per Plans Bridge Deck Crack Sealing, Per Plans	13,090.000	SF	2.68	3.25	3.05
0460	907-824-PP003	Bridge Repair, Epoxy Repair, Per Plans Epoxy Repair, Per Plans	175.000	SF	493.30	270.00	315.00
0470	907-824-PP004	Bridge Repair, Slab Span Setting, Per Plans Slab Span Setting, Per Plans	1.000	LS	310,953.32	268,000.00	575,000.00
0480	907-824-PP006	Bridge Repair, Install Bearings, Per Plans Install Bearings, Per Plans	34.000	EA	1,879.61	515.00	950.00
0490	907-824-PP006	Bridge Repair, Longitudinal Restrainer Assembly, Per Plans* Longitudinal Restrainer Assembly, Per Plans*	340.000	EA	1,420.22	1,375.00	1,050.00
0500	907-824-PP008	Bridge Repair, Removal of End Post, Per Plans Removal of End Post, Per Plans	20.000	LF	602.90	400.00	155.00