

Overlay on US 98 from Forrest County Line to 1 Mile East of SR 29 , known as Federal Aid Project No. NH-0014-03(073) / 107652301 in Perry County.					Warren Paving, Inc.	Dunn Roadbuilders, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,458,583.15					\$3,964,802.31	\$5,139,468.00	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0010	202-B050	Removal of Concrete Combination Curb & Gutter	70.000	LF	27.00	22.00	
0020	202-B059	Removal of Concrete Median & Island Pavement, All Depths	60.000	SY	27.00	22.00	
0030	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	1,500.000	LF	6.35	6.50	
0040	304-F003	Size 825B Crushed Stone Base	7,000.000	TON	37.25	54.80	
0050	403-A015	9.5-mm, ST, Asphalt Pavement	3,500.000	TON	99.00	135.65	
0060	403-B010	9.5-mm, HT, Asphalt Pavement, Leveling	11,700.000	TON	79.15	108.70	
0070	403-D007	9.5-mm, HT, Asphalt Pavement, Polymer Modified	19,000.000	TON	87.00	112.76	
0080	406-D001	Fine Milling of Bituminous Pavement, All Depths	45,500.000	SY	3.00	4.35	
0090	407-A001	Asphalt for Tack Coat	26,000.000	GAL	2.80	3.75	
0100	423-A001	Rumble Strips, Ground In	14.000	MI	390.00	272.00	
0110	606-B002	Guard Rail, Class A, Type 1, 'W' Beam	1,200.000	LF	25.35	25.00	
0120	606-D001	Guard Rail, Bridge End Section	8.000	EA	1,760.00	1,744.00	
0130	606-E005	Guard Rail, Terminal End Section, Flared	8.000	EA	2,650.00	2,616.00	
0140	608-A001	Concrete Sidewalk, Without Reinforcement	190.000	SY	66.00	98.00	
0150	608-C001	Detectable Warning Panels	70.000	SF	42.00	45.60	
0160	609-D003	Combination Concrete Curb and Gutter Type 2	70.000	LF	63.50	66.00	
0170	618-A001	Maintenance of Traffic	1.000	LS	75,000.00	92,000.00	
0180	618-B001	Additional Construction Signs	1.000	SF	10.00	10.00	
0190	619-A1001	Temporary Traffic Stripe, Continuous White	28.000	MI	715.00	708.00	
0200	619-A2001	Temporary Traffic Stripe, Continuous Yellow	26.000	MI	715.00	708.00	
0210	619-A3001	Temporary Traffic Stripe, Skip White	31.000	MI	715.00	708.00	
0220	619-A5001	Temporary Traffic Stripe, Detail	50,000.000	LF	0.05	0.05	
0230	620-A001	Mobilization	1.000	LS	110,000.00	90,000.00	
0240	626-A004	6" Thermoplastic Traffic Stripe, Skip White	16.000	MI	1,650.00	1,635.00	
0250	626-B002	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	14.000	MI	3,025.00	2,998.00	
0260	626-E004	6" Thermoplastic Traffic Stripe, Continuous Yellow	13.000	MI	3,025.00	2,998.00	

Overlay on US 98 from Forrest County Line to 1 Mile East of SR 29 , known as Federal Aid Project No. NH-0014-03(073) / 107652301 in Perry County.					Warren Paving, Inc.	Dunn Roadbuilders, LLC	
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$4,458,583.15					\$3,964,802.31	\$5,139,468.00	
Ref#	Item	Item Description	Item Qty	Units	1	2	
0270	626-G002	Thermoplastic Detail Stripe, White	21,000.000	LF	1.06	1.10	
0280	626-G003	Thermoplastic Detail Stripe, Yellow	19,500.000	LF	1.06	1.10	
0290	626-H004	Thermoplastic Legend, White	2,105.000	SF	5.30	5.00	
0300	627-J001	Two-Way Clear Reflective High Performance Raised Markers	400.000	EA	4.25	4.40	
0310	627-K001	Red-Clear Reflective High Performance Raised Markers	2,000.000	EA	4.25	4.40	
0320	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	900.000	EA	4.25	4.00	
0330	635-A076	Traffic Signal Head, Type 6	2.000	EA	855.00	883.00	
0340	907-632-B007	Remove and Replace Existing Traffic Signal Cabinet Assembly, Type III Cabinet, Type 1 Controller	1.000	EA	19,000.00	19,250.00	
0350	907-634-A545	Traffic Signal Equipment Pole, Type VI, 8' Shaft	1.000	EA	3,845.00	3,983.00	
0360	907-634-C001	Pole Foundations, Class "B" Concrete	1.000	CY	0.01	1.00	
0370	907-636-B014	Electric Cable, Underground in Conduit, IMSA 20-1, AWG 14, 5 Conductor	446.000	LF	2.40	5.50	
0380	907-637-C028	Traffic Signal Conduit, Underground, Type 4, 2"	10.000	LF	10.50	12.00	
0390	907-640-A001	Vehicle Loop Assemblies	724.000	LF	15.85	16.00	
0400	907-645-B001	Accessible Pedestrian Detection Assembly	2.000	EA	1,700.00	1,760.00	