

Overlay approximately 10 miles of US 82 from US 49 W to Leflore CL, known as Federal Aid Project No. NH-0011-01(069) / 107720301 in Sunflower County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,052,603.80					\$5,283,713.73		
Ref#	Item	Item Description	Item Qnty	Units	1		
0010	202-B158	Removal of Guard Rail, Including Rails, Posts and Terminal Ends	750.000	LF	5.15		
0020	202-B188	Removal of Pavement, All Types and Depths	190.000	SY	252.35		
0030	203-G001	Excess Excavation, FM, AH	63.000	CY	30.00		
0040	304-B004	Granular Material, Class 5, Group D	18,365.000	TON	21.91		
0390	304-F001	3/4" and Down Crushed Stone Base	115.000	TON			
0400	304-F002	Size 610 Crushed Stone Base	115.000	TON	95.00		
0410	304-F003	Size 825B Crushed Stone Base	115.000	TON			
0050	403-A006	19-mm, ST, Asphalt Pavement	62.000	TON	125.00		
0060	403-A013	9.5-mm, HT, Asphalt Pavement	30,500.000	TON	90.00		
0070	403-A014	9.5-mm, MT, Asphalt Pavement	4,733.000	TON	120.00		
0080	406-A002	Cold Milling of Bituminous Pavement, All Depths	33,600.000	SY	3.00		
0090	407-A001	Asphalt for Tack Coat	34,155.000	GAL	3.50		
0100	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	51,000.000	LF	2.58		
0110	423-A001	Rumble Strips, Ground In	36.000	MI	425.00		
0120	606-B001	Guard Rail, Class A, Type 1	600.000	LF	22.66		
0130	606-D001	Guard Rail, Bridge End Section	4.000	EA	1,637.70		
0140	606-E007	Guard Rail, Terminal End Section, Non-Flared	4.000	EA	2,781.00		
0150	618-A001	Maintenance of Traffic	1.000	LS	450,000.00		
0160	618-B001	Additional Construction Signs	1.000	SF	10.00		
0170	619-A1004	Temporary Traffic Stripe, Continuous White, Paint	19.000	MI	772.50		
0180	619-A2004	Temporary Traffic Stripe, Continuous Yellow, Paint	18.000	MI	772.50		
0190	619-A3003	Temporary Traffic Stripe, Skip White, Paint	21.000	MI	772.50		
0200	619-A4004	Temporary Traffic Stripe, Skip Yellow, Paint	1.000	MI	772.50		
0220	619-A5002	Temporary Traffic Stripe, Detail, Paint Yellow	14,500.000	LF	0.15		
0230	619-A6003	Temporary Traffic Stripe, Legend, Paint	150.000	SF	2.06		
0240	619-A6004	Temporary Traffic Stripe, Legend, Paint	2,250.000	LF	1.03		

Overlay approximately 10 miles of US 82 from US 49 W to Leflore CL, known as Federal Aid Project No. NH-0011-01(069) / 107720301 in Sunflower County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$5,052,603.80					\$5,283,713.73		
Ref#	Item	Item Description	Item Qnty	Units	1		
0250	620-A001	Mobilization	1.000	LS	400,000.00		
0260	626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	21.000	MI	1,236.00		
0270	626-B002	6" Thermoplastic Double Drop Traffic Stripe, Continuous White	22.000	MI	2,884.00		
0280	626-D001	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	1.000	MI	1,236.00		
0290	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	18.000	MI	2,781.00		
0300	626-G004	Thermoplastic Double Drop Detail Stripe, White	18,300.000	LF	0.77		
0310	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	14,500.000	LF	0.72		
0320	626-H004	Thermoplastic Legend, White	150.000	SF	8.24		
0330	626-H005	Thermoplastic Legend, White	2,000.000	LF	3.09		
0340	627-J001	Two-Way Clear Reflective High Performance Raised Markers	1,110.000	EA	5.15		
0350	627-K001	Red-Clear Reflective High Performance Raised Markers	1,800.000	EA	5.15		
0360	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	280.000	EA	5.15		
0370	630-F012	Delineators, Post Mounted, Single White	28.000	EA	18.54		
0380	907-640-A001	Vehicle Loop Assemblies	237.000	LF	20.18		
0210	619-A5002	Temporary Traffic Stripe, Detail, Paint White	18,300.000	LF	0.15		