

Mill & Overlay approximately 6 miles of I-59 from 65th Avenue bridge to US 45, known as Federal Aid Project No. IM-0059-03(095) / 107299301 in Lauderdale County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,103,355.91					\$13,335,627.43		
Ref#	Item	Item Description	Item Qty	Units	1		
0010	202-B007	Removal of Asphalt Pavement, All Depths	1,565.000	SY	113.40		
0020	202-B062	Removal of Concrete Overlaid w/ Asphalt Pavement, All Depths	82.000	SY	176.50		
0030	202-B147	Removal of Guard Rail Double Faced Rail Including Rail & Posts	2,647.000	LF	9.00		
0040	202-B150	Removal of Guard Rail Including Post, Blockouts & Hardware	16,793.000	LF	6.00		
0050	202-B162	Removal of Impact Attenuator	1.000	EA	2,500.00		
0060	202-B169	Removal of Joint Material	1,389.000	LF	30.00		
0070	202-B172	Removal of Legend, All Types	335.000	SF	4.00		
0080	202-B240	Removal of Traffic Stripe	33,927.000	LF	2.00		
0090	203-G002	Excess Excavation, LVM, AH	607.000	CY	3.14		
0100	203-I002	Site Grading	280.000	SY	10.00		
0110	223-A001	Mowing	227.000	ACRE	50.00		
0120	304-A004	Granular Material, LVM, Class 5, Group C	2,006.000	CY	35.00		
0130	402-A002	Open Graded Friction Course, 9.5-mm Mixture	10,954.000	TON	115.00		
0140	402-B001	Bituminous Tack Coat	23,377.000	GAL	3.33		
0150	403-A004	19-mm, HT, Asphalt Pavement	2,078.000	TON	105.00		
0160	403-A015	9.5-mm, ST, Asphalt Pavement	2,945.000	TON	109.00		
0170	403-D007	9.5-mm, HT, Asphalt Pavement, Polymer Modified	26,088.000	TON	101.00		
0180	403-S002	Joint Sealant	70,738.000	LF	0.69		
0190	405-A002	Stone Matrix Asphalt, 9.5 mm Mixture	20,010.000	TON	125.00		
0200	406-A002	Cold Milling of Bituminous Pavement, All Depths	662.000	SY	39.71		
0210	406-D001	Fine Milling of Bituminous Pavement, All Depths	580,807.000	SY	2.75		
0220	407-A001	Asphalt for Tack Coat	58,093.000	GAL	4.00		
0230	413-D003	Cleaning and Filling Joints in PCC Pavement	1,356.000	LF	25.00		
0240	413-E001	Sawing and Sealing Transverse Joints in Asphalt Pavement	8,164.000	LF	3.50		
0250	423-A001	Rumble Strips, Ground In	14.000	MI	285.00		
0260	503-A001	8" and Variable Continuously Reinforced Concrete Pavement, Broom Finish	34.000	SY	313.50		

Mill & Overlay approximately 6 miles of I-59 from 65th Avenue bridge to US 45, known as Federal Aid Project No. IM-0059-03(095) / 107299301 in Lauderdale County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,103,355.91					\$13,335,627.43		
Ref#	Item	Item Description	Item Qty	Units	1		
0270	503-A002	8" and Variable Jointed Concrete Pavement	48.000	SY	313.50		
0280	503-B001	Saw Cut, Longitudinal Joints	62.000	LF	11.50		
0290	503-C004	Saw Cut, 3-inch	24.000	LF	11.50		
0300	503-C010	Saw Cut, Full Depth	2,542.000	LF	11.50		
0310	503-D001	Concrete for Base Repair	5.000	CY	344.85		
0320	503-E002	Tie Bars, No. 5 Deformed Drilled and Epoxied or Grouted	102.000	EA	10.45		
0330	512-A001	Holes	720.000	EA	100.00		
0340	512-B002	Cement Pressure Grout Slurry, Type 6	11,280.000	LBS	0.50		
0350	601-B001	Class "B" Structural Concrete, Minor Structures	1.000	CY	4,180.00		
0360	602-A001	Reinforcing Steel	150.000	LBS	3.25		
0370	606-B003	Guard Rail, Class A, Type 1, 'W' Beam, Metal Post	14,050.000	LF	22.00		
0380	606-B007	Guard Rail, Class A, Type 1, Double Faced, Metal Post	2,713.000	LF	26.00		
0390	606-B011	Guard Rail, Class A, Type 1, Thrie Beam, Metal Post	169.000	LF	32.00		
0400	606-B013	Guard Rail, Class A, Type 1, Thrie Beam, Transition Section	2.000	LF	55.00		
0410	606-C001	Guard Rail, Cable Anchor Type 1, Metal Post	27.000	EA	750.00		
0420	606-D005	Guard Rail, Bridge End Section, Type A	9.000	EA	1,450.00		
0430	606-D012	Guard Rail, Bridge End Section, Type D Modified	35.000	EA	1,250.00		
0440	606-E001	Guard Rail, Terminal End Section	42.000	EA	2,600.00		
0450	606-E003	Guard Rail, Terminal End Section, Double Faced	1.000	EA	5,500.00		
0460	618-A001	Maintenance of Traffic	1.000	LS	800,000.00		
0470	619-A1001	Temporary Traffic Stripe, Continuous White	59.000	MI	1,000.00		
0480	619-A2001	Temporary Traffic Stripe, Continuous Yellow	60.000	MI	1,000.00		
0490	619-A3001	Temporary Traffic Stripe, Skip White	54.000	MI	1,000.00		
0500	619-A5001	Temporary Traffic Stripe, Detail	70,989.000	LF	0.30		
0510	619-A6001	Temporary Traffic Stripe, Legend	2,526.000	SF	2.25		
0520	619-A6002	Temporary Traffic Stripe, Legend	5,292.000	LF	1.00		

Mill & Overlay approximately 6 miles of I-59 from 65th Avenue bridge to US 45, known as Federal Aid Project No. IM-0059-03(095) / 107299301 in Lauderdale County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,103,355.91					\$13,335,627.43		
Ref#	Item	Item Description	Item Qty	Units	1		
0530	619-C6001	Red-Clear Reflective High Performance Raised Marker	6,775.000	EA	6.00		
0540	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet	32.000	SF	5.00		
0550	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More	992.000	SF	5.00		
0560	619-F1001	Concrete Median Barrier, Precast	1,730.000	LF	20.90		
0570	619-F3004	Delineators, Median Barrier Mounted, Yellow	1,233.000	EA	15.00		
0580	619-F5001	Snap-Back Delineator, Replacement	65.000	EA	30.00		
0590	619-G4005	Barricades, Type III, Single Faced	66.000	LF	14.00		
0600	619-J1004	Impact Attenuator, 60 MPH	1.000	EA	4,500.00		
0610	620-A001	Mobilization	1.000	LS	950,000.00		
0620	626-A001	6" Thermoplastic Double Drop Traffic Stripe, Skip White	22.000	MI	1,500.00		
0630	626-C002	6" Thermoplastic Double Drop Edge Stripe, Continuous White	32.000	MI	3,100.00		
0640	626-D002	6" Thermoplastic Double Drop Traffic Stripe, Skip Yellow	2,996.000	LF	1.00		
0650	626-E001	6" Thermoplastic Double Drop Traffic Stripe, Continuous Yellow	12.000	MI	2,850.00		
0660	626-F001	6" Thermoplastic Double Drop Edge Stripe, Continuous Yellow	21.000	MI	2,850.00		
0670	626-G004	Thermoplastic Double Drop Detail Stripe, White	56,939.000	LF	1.00		
0680	626-G005	Thermoplastic Double Drop Detail Stripe, Yellow	12,938.000	LF	1.00		
0690	626-H001	Thermoplastic Double Drop Legend, White	2,526.000	SF	8.00		
0700	626-H002	Thermoplastic Double Drop Legend, White	5,292.000	LF	4.00		
0710	627-K001	Red-Clear Reflective High Performance Raised Markers	6,775.000	EA	6.00		
0720	627-L001	Two-Way Yellow Reflective High Performance Raised Markers	2,278.000	EA	6.00		
0730	630-F004	Delineators, Guard Rail, Double White	199.000	EA	20.00		
0740	630-F006	Delineators, Guard Rail, White	383.000	EA	18.00		
0750	630-F007	Delineators, Guard Rail, Yellow	73.000	EA	18.00		
0760	630-F010	Delineators, Post Mounted, Double White	479.000	EA	47.00		
0770	630-F011	Delineators, Post Mounted, Double Yellow	86.000	EA	47.00		
0780	630-F012	Delineators, Post Mounted, Single White	313.000	EA	38.00		

Mill & Overlay approximately 6 miles of I-59 from 65th Avenue bridge to US 45, known as Federal Aid Project No. IM-0059-03(095) / 107299301 in Lauderdale County.					APAC - Mississippi, Inc.		
MISSISSIPPI DEPARTMENT OF TRANSPORTATION: \$12,103,355.91					\$13,335,627.43		
Ref#	Item	Item Description	Item Qty	Units	1		
0790	630-F013	Delineators, Post Mounted, Single Yellow	261.000	EA	38.00		
0800	630-G003	Type 3 Object Markers, OM-3L, Post Mounted	15.000	EA	75.00		
0810	630-G007	Type 3 Object Markers, OM-3R, Post Mounted	30.000	EA	75.00		
0820	647-A001	Removal of Existing Traffic Signal Equipment	1.000	LS	995.00		
0830	682-A028	Underground Branch Circuit, AWG 4, 3 Conductor	600.000	LF	9.30		
0840	682-D003	Underground Pull Box	3.000	EA	700.00		
0850	907-619-E3001	Changeable Message Sign	2.000	EA	5,624.85		
0860	907-632-D001	Solid State Traffic Actuated Controller, Type 1	9.000	EA	3,725.00		
0870	907-641-A002	Signal Stop Bar Radar Vehicle Detection Sensor, Type 2	35.000	EA	6,495.00		
0880	907-641-D001	Radar Vehicle Detection Cable	4,350.000	LF	2.90		
0890	907-687-A001	Traffic Recorder Classification Permanent System	1.000	EA	70,450.00		
0900	907-899-A001	Railway-Highway Provisions	1.000	LS	15,000.00		
0910	907-906001	Trainees	720.000	HRS	5.00		
0920	907-823-A001	Preformed Joint Seal, Type I	1,153.000	LF	30.00		
0930	907-823-A002	Preformed Joint Seal, Type II	236.000	LF	35.00		
0940	907-823-B001	Saw Cut, Type I	2,305.000	LF	8.00		
0950	907-823-B002	Saw Cut, Type II	472.000	LF	10.00		
0960	907-824-PP004	Bridge Repair, Median Wall Repair	1.000	LS	5,434.00		
0970	907-824-PP007	Bridge Repair, Elastomeric Concrete for Bridge Joint Repair	25.000	CY	4,000.00		
0980	907-824-PP008	Bridge Repair, End Wall Repair	250.000	LF	167.20		