

Call 03 Overlay approximately 7 miles of US 98 from East ROW of SR 63 to SR 198 E Lucedale, known as Federal Aid Project No. NH-0014-03(075) / 107791301 in George County.

Q1. 1.) Is the 825B placed for shoulder material to be blended (mechanically mixed) in with the existing material on the shoulder? 2.) Will the removal of concrete aprons around the inlets be paid for as Removal of Paved Ditch? 3.) Will the new apron be paid as Paved Ditch? 4.) Will the newer asphalt at Beaver Dam Rd. be overlaid or will it be skipped?

A1. 1.) No. 2.) Yes. 3.) Yes. 4.) It will be overlaid.